

From: Owens, Bernard <sowens@littlerock.gov>
Sent: Wednesday, March 26, 2025 12:36 PM
To: Casey Jackson
Cc: Kimberly Davenport (adpce.ad); Bower, Trent A.
Subject: Re: City of Little Rock CY - Q1 Inspection report - With violations
Attachments: 2-27-2025 ADEQ 1Q compost inspection response.docx; DRAFT COLR Bid Document Final FLATTENED (002).PDF

Good Afternoon,

Here is response to Compost Q1 inspection. Let me know if you need anything else.



Bernard Owens
Solid Waste Services Manager
Department of Public Works | Solid Waste
O: 501-888-4492 | C: 5014121382
sowens@littlerock.gov

From: Kimberly Davenport (adpce.ad) <Kimberly.Davenport@arkansas.gov>
Sent: Monday, March 3, 2025 11:31 AM
To: Owens, Bernard <sowens@littlerock.gov>
Cc: Casey Jackson <Casey.Jackson@arkansas.gov>; Christopher Krou (adpce.ad) <Christopher.Krou@arkansas.gov>; Ryan Hayden (adpce.ad) <Ryan.Hayden@arkansas.gov>; Nicholas Jones (adpce.ad) <Nicholas.Jones@arkansas.gov>; Charles Hurt (adpce.ad) <Charles.Hurt@arkansas.gov>; Greg Banic (adpce.ad) <Greg.Banic@arkansas.gov>
Subject: City of Little Rock CY - Q1 Inspection report - With violations

EXTERNAL EMAIL - This email was sent by a person from outside your organization. Exercise caution when clicking links, opening attachments or taking further action, before validating its authenticity.

Attached:2/3/2025 - City of Little Rock CY - Q1 Inspection report - With violations

Kim Davenport | Solid Waste Inspector Supervisor
Division of Environmental Quality | Office of Land Resources
Regulated Waste Program
5301 Northshore Drive | North Little Rock, AR 72118
t: 501.682.0586 | c: [501.837.6911](tel:501.837.6911) | e: Kimberly.Davenport@arkansas.gov



ARKANSAS
ENERGY & ENVIRONMENT











March 26, 2025

Casey Jackson, Inspector
Arkansas Department of Environmental Quality
Solid Waste Management Division
5301 Northshore Drive
North Little Rock, AR 72118-5317

RE: Inspection conducted on February 27, 2025
AFIN 60-01071
Permit Number 0031-SCYW

Dear Mr. Jackson:

In response to your inspection of February 27, 2025, the following is a list of comments and corrective actions to be undertaken on the City of Little Rock's Compost Violations:

AFIN 60-01071 Permit Number 0031-SCYW,

- **Category 1, Regulation 804: Application Requirements.** Permit expired. An NOI was submitted via eportal and is awaiting signature. Electronic signature approval was hand delivered 7/3/2024. Still awaiting signature approval. The City had consultant Terracon Matt J. Acree hand delivered hard copy signed by him and myself on 8/26/2024.
- **Category 1, Regulation 805(b)(2);(c)(6): Conforms to Operating Plan.** An updated operating plan describing current operations is required. – The City has a contract to complete this. The City is currently updating the operating plan to revise the description of the facility. The City has also completed a design to rehabilitate the facility and hopefully will be constructing the improvements soon. Draft of our Operating plans have to be revised due to the construction improvements the City plans on pursuing by mid Summer. The city has not been composting due to needing these improvements completed. Draft will be submitted after construction bid is selected.

Thank you for your cooperation in this matter. If I can be of any further assistance please contact me at your convenience.

Sincerely,

Bernard Owens

City of Little Rock

Solid Waste Services Manager



Bid Documents and Specifications

Compost Pad Improvement
City of Little Rock
10803 Ironton Cut Off Road
Little Rock, Arkansas

DRAFT

September 2023
Project No. 35237144



Prepared for:
City of Little Rock
10803 Ironton Cut Off Road
Little Rock, Arkansas

Prepared by:
Terracon Consultants, Inc.
25809 Interstate 30 South
Bryant, Arkansas 72022
(501) 249-4334

terracon.com

Terracon

Environmental



Facilities



Geotechnical



Materials

BID FORM

BID FORM
 CITY OF LITTLE ROCK
 COMPOST PAD CONSTRUCTION - SEPTEMBER 2023

Item No.	Description	Unit	Estimated Quantities	Bid Unit Price	Bid Price
1	Mobilization/Demobilization	LS	1		\$ -
2	Erosion Controls	LS	1		\$ -
3	Subgrade (4" Leveling Layer)	SF	628,000		\$ -
	Phase 1	SF	163,500		
	Phase 2	SF	176,000		
	Phase 3	SF	142,500		
	Phase 4	SF	146,000		
4	Geosynthetics				
4a	6 oz/sf Nonwoven Geotextile	SF	628,000		\$ -
4b	Tensar NX850 Geogrid	SF	628,000		\$ -
				Total Geosynthetics	\$ -
5	14" Rock Layer	SF	628,000		\$ -
6	Perimeter Road Improvements (12" #67 Stone)	SF	42,500		\$ -
TOTAL COMPOST PAD CONSTRUCTION					\$ -
<p>NOTE: The quantities indicated in the Agreement have been estimated by Owner for contracting and comparison purposes. No Claim shall be made against Owner for any excess or deficiency therein. Payment at the prices stated in the Agreement shall be in full for the completed Unit Price Work, and will cover materials, supplies, labor, tools, machinery and all other expenditures incidental to satisfactory completion of the Unit Price Work. The Contractor shall be responsible for verifying these quantities.</p>					

TECHNICAL SPECIFICATIONS

Technical Specifications

Compost Pad Improvement
City of Little Rock
10803 Ironton Cut Off Road
Little Rock, Arkansas

September 2023
Project No. 35237144



Prepared for:
City of Little Rock
10803 Ironton Cut Off Road
Little Rock, Arkansas

Prepared by:
Terracon Consultants, Inc.
25809 Interstate 30 South
Bryant, Arkansas 72022
(501) 847-9292

terracon.com

Terracon

Environmental



Facilities



Geotechnical



Materials

TABLE OF CONTENTS

TECHNICAL SPECIFICATIONS

Division 1 – General Requirements

01010	Summary of Work
01025	Measurement and Payment
01039	Coordination and Meetings
01040	Coordination
01050	Field Engineering
01051	Control of Work
01300	Submittals
01400	Quality Control and Assurance Services
01500	Construction Facilities and Temporary Controls
01563	Control of Water
01565	Temporary Soil Erosion and Sediment Control
01600	Material & Equipment
01720	Project Record Documents

Division 2 – Site Work

02110	Clearing and Grubbing
02200	Earthwork
02210	Fill Compaction for Earthwork Structures
02228	Subgrade
02278	Geotextile and Geogrid

TABLES

1	Geotextile, and Geogrid MQC Testing Specifications
---	--

SECTION 01010 SUMMARY OF WORK

PART 1 GENERAL

1.01 SUMMARY

A. Section Includes:

- Description of Payment Items
- Work Covered by Contract Documents.
- Work by Others.
- Work Sequence.
- Existing Site Conditions.
- Contractor's Use of Premises.
- Erosion and Sediment Controls.

Erosion and Sediment Controls.

1.02 DESCRIPTION OF PAYMENT ITEMS

- A. The Earthwork Contractor shall be responsible for the work as described in this document and as indicated in the construction drawings. Payment for work will be made as indicated in the pay items listed below. Payment will be made based upon in-place quantities and will be verified by a Registered Land Surveyor. A ten (10) percent retainer will be applied to each of the monthly invoices. The retainer will be paid in full upon completion of the project and once a Receipt, Waiver, and Release of Lien Rights is executed. Any work, which the Earthwork Contractor believes not to be covered by one of these pay items shall be addressed in the bid, submitted to the Owner.

The Earthwork Contractor shall take all necessary actions needed to meet the proposed schedule, taking into account weather as could be expected for the project area and season. Unless otherwise approved by the Owner, construction activities at the site and material deliveries to the Facility shall be limited to hours approved by the Owner.

1.03 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work consists of, in general, improvements to of the City of Little Rock Compost Pad located in Little Rock, Arkansas. The Contractor shall provide all necessary materials, labor, full-time supervision (defined as Contractor's Superintendent, experienced in similar construction, unless otherwise approved

in writing by Owner and Engineer), and equipment to perform the services in accordance with the Construction Agreement, Plans, and Specifications herein or subsequently approved by the Owner. The Services include, but are not limited to, the following items:

- B. Installation of erosion control for the construction process.
- C. Installation of a 4 inch gravel leveling layer. Installation includes haul, place, compact, grade, and smooth roll.
- D. Installation of a 6 oz/sy nonwoven geotextile. Installation includes unloading, material, and installation.
- E. Installation of a geogrid. Installation includes unloading, material, and installation.
- F. Installation of a 14 inch gravel layer above the geogrid. Installation includes haul, place, compact, fine grade, and smooth roll.
- G. Installation of Perimeter Road Improvements. Installation includes haul, place, compact, and grading of 12 inches of gravel on the compost pad's perimeter roads and entrance ramp areas.

The Contractor is also responsible for the following during all phases of the Compost Pad Improvements Construction:

- 1. Excavation and Construction Dewatering – maintain and grade construction area to drain, maintain construction areas free of water, and provide, operate, and maintain pumping equipment.
- 2. Haul Road Grading – Daily Grading and maintaining haul roads near compost pad construction area is required as a part of this Project.
- 3. Haul Road Watering – Frequent watering of the haul roads will be required on a daily basis to keep dust generated from construction traffic to an absolute minimum. Water is to be obtained from Owners designated on-site source.

Also note that The Contract Price for all Items of Construction shall include but not be limited to performing Earthwork (Excavation, Structural Fill, and gravel placement) to Design Grades, including all labor, material (geotextile, geogrid, etc.), equipment, and other incidentals, such as, excavating, moving, placing and segregating, stockpiling, stockpile grading and maintenance, dewatering, and erosion and sedimentation control materials and practices as required to comply with the attached Drawings and Specifications (unless specifically identified as a pay item).

The quantities indicated in the Agreement have been estimated by Owner for contracting and comparison purposes. No Claim shall be made against Owner for any excess or deficiency therein. Payment at the prices stated in the Agreement shall be in full for the completed Unit Price Work, and will cover

to satisfactory completion of the Unit Price Work. The Contractor shall be responsible for verifying these quantities.

B. The following bid items correspond to the drawing set entitled Compost Pad Improvement Drawings for the City of Little Rock Landfill, Little Rock, Arkansas.

1. **Mobilization/Demobilization** – The Earthwork Contractor shall mobilize all equipment, materials, personnel, etc. to the site and demobilize after completion of construction, leaving allocated work areas, including borrow sources, haul roads and stockpiles, in a satisfactory condition. The Owner is not responsible for assisting the Contractor with unloading or loading of any materials or equipment. In addition to unloading geosynthetic materials, the Contractor shall be responsible for storing and protecting the materials from weather.

The Lump Sum Price for Mobilization and Demobilization shall be payment in full for all labor, equipment, material and other incidentals to the site, as well as Contractor provided utilities and ongoing related expenses, considered normal for administration of the work. Fifty (50) percent of the Lump Sum price bid will be paid with the first payment request following satisfactory evidence of mobilization of sufficient labor, equipment and material to adequately progress the work of this contract. The remaining fifty (50) percent of the Lump Sum price bid will be paid with the Final Payment request after satisfactory substantial completion of the *project*. The total price paid for this item in the first installment shall not exceed six (6) percent of the original Contract amount for the Contract. Assume one mobilization/demobilization for the project.

- Item #1 Mobilization/Demobilization – Provide Lump Sum Cost

2. **Erosion Controls** – The Earthwork Contractor shall be responsible for providing and maintaining Erosion Control devices around the downhill perimeter of the Construction area. Erosion control measures will be maintained for the duration of the project. The Contractor shall take all steps necessary to maintain compliance with the Owners Stormwater Permit.

- Item #2 Install silt fencing around the down gradient side of the improvement project.

3. **Subgrade** – The subgrade of the Compost Pad will need to be graded to the subgrade elevations. Expect approximately 4-inches of stone to be placed to get the existing grade to subgrade elevations.

- Item #3 Supply rock material. The gravel will be from off-site. The price will include material, hauling, grading, and compaction.

4. Geosynthetics (Geotextile and Geogrid)

- Item #4a Supply 6 oz/sf Nonwoven geotextile above the subgrade elevation. The installation includes unloading, material, and installation.
- Item #4b Supply geogrid above the geotextile. The installation includes unloading, material, and installation.

5. 14 - inch Rock Layer

- Item #5a Install a 14 - inch minimum rock layer to the line and grades in the Compost Pad Improvement Drawings. The material will be from an off-site borrow area and the price will include hauling, placing, and compacting the material according to the drawings.

6. Road Improvements

- Item #6a Add 12 inches of #67 stone to compost area support roads.

1.05 WORK SEQUENCE

Sequencing of the Work shall be the responsibility of the Contractor as long as the requirements of these specifications are met, the Contractor's progress is according to the schedule approved by the Engineer and Owner, and compliance with Contract Times stated in the Agreement are met.

1.06 EXISTING SITE CONDITIONS

The landfill is an active disposal facility. Construction operations shall not disturb normal landfill operations.

1.07 CONTRACTOR'S USE OF PREMISES

- A. All of the Contractor's operations on the Owner's premises, including the storage of materials, shall be confined to areas approved by the Owner or Engineer.
- C. The Owner and Engineer will not assume responsibility for damages to facilities on the site due to negligence or carelessness on the part of the Contractor. The Owner and Engineer will not be liable for loss or damage of Contractor's tools equipment or materials due to theft, vandalism or any other causes whatsoever.

1.08 EROSION AND SEDIMENT CONTROLS

Temporary measures to control soil erosion and sediment transport within the construction limits shall be constructed utilizing BMP's to maintain compliance with the Owners Stormwater Permit.

1.09 TEMPORARY AND PERMANENT SEEDING (If needed)

A stand of grass shall be established on all areas disturbed by construction within the construction limits.

1.10 INTERIM STORMWATER RUN-ON AND RUN-OFF CONTROLS

A. Stormwater management system improvements as shown on the Drawings shall be constructed.

B. Related Sections:

1. Section 02200 - Earthwork

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

NOTE:

At all times this facility must remain in compliance with laws and regulations governing the operation and construction of such a facility. Accordingly, the CONTRACTOR must at all times sequence their work and implement the necessary temporary facilities or activities to maintain the proper operation and compliance of this facility. Furthermore, all of the CONTRACTOR's activities must be completed while focusing on the proper management of stormwater and dust control. The Drawings provide the overall scope of work. It is the CONTRACTOR's responsibility to review and understand the necessary tasks required to complete the work. The CONTRACTOR may need to implement steps not necessarily shown on the Drawings in order to maintain landfill operations and landfill compliance. The CONTRACTOR is responsible for all bid items noted on the Bid Sheet and must complete all the work shown on the Drawings while maintaining the landfill operation and environmental compliance.

END OF SECTION

SECTION 01025 MEASUREMENT AND PAYMENT

PART 1 DESCRIPTION OF WORK

- A. The project is specified as the City of Little Rock Compost Pad Improvements in Little Rock, Arkansas.
- B. Payment shall be made on a Unit Rate basis and only be made for Work as specifically described in these Specifications and the Contract Documents. All other work shall be considered incidental to the Work. No payment shall be made for defective work or work beyond the lines and grades of the required Work.
- C. Payment shall only be made for approved, in-place materials and Work, unless specifically permitted otherwise by these Specifications.

PART 2 PRODUCTS

- A. Products are defined herein specific to the various aspects of construction. Products are considered to include those purchased and delivered to the site as well as those constructed on the site.

PART 3 EXECUTION

3.01 UNIT PRICE SCHEDULE

- A. See Schedule of Values - Bid Sheet.

3.02 CONTRACT PAY ITEMS

- A. See Specification 01010 – Summary of Work.

3.03 INCIDENTALS

- A. Some items are considered incidental to the Work and shall not be measured or paid. Items not specifically listed as a pay item are considered incidental.

END OF SECTION

SECTION 01039 COORDINATION AND MEETINGS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Coordination
- B. Pre-construction conference
- C. Progress Meetings

1.02 COORDINATION

- A. Contractor Shall
 - 1. Coordinate scheduling, submittals, and Work of the various sections of Specifications to assure efficient and orderly sequence of installation of interdependent construction elements.
 - 2. Coordinate work of various sections having independent responsibilities for fabrication, installation, connection to, and placing in service, such equipment.
 - 3. Coordinate space requirements and installation of structural work which are indicated diagrammatically on Drawings.
 - 4. Coordinate completion and cleanup of Work of separate sections in preparation for Substantial Completion.
 - 5. After occupancy of premises by Owner, coordinate access to site for correction of defective Work and Work not in accordance with Specifications, to minimize disruption of Owner's activities.

1.03 PRECONSTRUCTION CONFERENCE

- A. Owner will schedule a pre-construction conference.
- B. Agenda:
 - 1. Distribution of Specifications.
 - 2. Finalize estimated progress schedule, Shop Drawing Schedule and schedule of values.

3. Designation of personnel representing the parties in Contract, and the Engineer.
4. Procedures and processing of field decisions, submittals, substitutions, applications for payments, proposal request, Change Orders, and Contract closeout procedures.
5. Scheduling.

1.04 PROGRESS MEETINGS

A. Owner shall:

1. Schedule and administer meetings throughout progress of the Work.
2. Make arrangements for meeting, prepare agenda with copies for participants, preside at meetings, record minutes, and distribute copies within two calendar days to Engineer, Contractor, participants, and those affected by decisions made.

B. Attendance Required: Contractor, Owner, Engineer or Engineer's Representative, and others as appropriate to agenda topics for each meeting.

C. Agenda:

1. Review minutes of previous meetings.
2. Review of Work in progress.
3. Field observations, problems, and decisions.
4. Identification of problems which impede planned schedules.
5. Review of submittals schedule and status of submittals.
6. Review of off-site fabrication and delivery schedules.
7. Maintenance of progress schedule.
8. Corrective measures to regain projected progress.
9. Planned progress during succeeding work period.
10. Coordination of projected progress.
11. Maintenance of quality and work standards.
12. Effect of proposed changes on progress schedule and coordination.
13. Safety issues relating to Work.
14. Other business relating to Work.

PART 2 PRODUCTS

(NOT USED)

PART 3 EXECUTION

(NOT USED)

END OF SECTION

SECTION 01040 COORDINATION

PART 1 GENERAL

1.01 DESCRIPTION OF WORK

- A. The Contractor shall coordinate material supply, construction, and inspection to assure efficient and orderly completion of the Work:
- B. The Contractor shall notify the Owner in writing when coordination of the Owner's or other contractors' activities is required.

1.02 PROJECT PERSONNEL

- A. The Engineer is:
David C. McCormick, P.E.
Terracon Consultants, Inc.
25809 Interstate 30 South
Bryant, Arkansas 72022
(501) 847-9292 email: dcmccormick@terracon.com
- B. The Owner is:
Nathan Charles, P.E.
City of Little Rock Landfill
Solid Waste Services Manager
10803 Ironton Cut Off Road
Little Rock, Arkansas
(501) 888-4492 email: ncharles@littlerock.gov
- C. The Surveyor-of-Record is:
TBD
- D. The Technical/Quality Assurance Representative is:
David C. McCormick, P.E.
Terracon Consultants, Inc.
25809 Interstate 30 South
Bryant, Arkansas 72022
(501) 847-9292 email: dcmccormick@terracon.com

END OF SECTION

SECTION 01050 FIELD ENGINEERING

PART 1 GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the contract including General Conditions, Supplementary Conditions and other Division 1 Sections apply to work of this section. This section applies to work of all sections of the Specifications.

1.02 OWNER'S RESPONSIBILITY

- A. The Owner will provide reference dimensions for the Contractor's use in determining and controlling horizontal dimensions and vertical elevations of improvements as follows:

The Owner's site control will be shown on the drawings as a part of the issued construction package by Terracon. Baseline control and benchmark data as shown on Drawings. Benchmarks and control points will be supplied to the Contractor.

1.03 CONTRACTOR'S RESPONSIBILITY

- A. Protect all control points, property pins, right-of-way markers, and elevation bench marks. Replace points disturbed or damaged by Contractor at no additional cost to Owner.
- B. Provide additional engineering control surveys as deemed necessary for Contractor's benefit. Employ qualified and approved surveyor, engineer, or engineering technician for field surveys.
- C. Provide detailed construction layout staking as required for proper construction of site improvements.
- D. Where work requires the removal of property pins, or right-of-way monuments or markers; employ an approved Arkansas Professional Land Surveyor to reference points before they are disturbed and to reset points in their original position and condition after the work in that area is complete.

1.04 CONSTRUCTION LAYOUT STAKING

- A. The specifications of this subsection shall be applicable in the event that Contractor

employs the Engineer to furnish detailed construction layout staking.

B. Notification and request for Services:

1. Properly coordinate requests for staking services with construction activities so as to preclude inefficient scheduling of staking crews.
2. Notify Engineer a minimum of 48 hours in advance of the date that specific services are desired.
3. Stipulate the particular stakes or marks required giving the specific location and/or limiting stations, offsets and other pertinent information.
4. Requests for services shall be for a minimum of 1,500 linear feet of line.

C. Control Staking:

1. Control stakes which are referenced points for all construction, work shall be conspicuously and visibly marked with flagging tape, paint, or other suitable means.
2. Contractor shall protect all control points and shall replace points disturbed or damaged by Contractor at his expense.
3. Control stakes which are in the work area and which require removal in order to properly execute work will be referenced and removed at no cost to Contractor.

D. Flagging for Clearing:

1. For utilities, road right-of-way or other proposed improvements presently located in wooded areas, Engineer will flag proposed centerline or one side of right-of-way to be cleared.
2. After clearing and grubbing is completed, the remainder of construction will be staked.

E. Road Alignment and Grade Staking:

1. Contractor is responsible for constructing the proper road cross-section as shown on the Drawings.
2. One set of initial alignment and cut and fill stakes shall be set along one right-of-way for rough grading purposes. Stakes at 100-foot intervals and at other critical

points shall indicate cut and/or fill to finished centerline elevation.

3. One set of final hubs shall be set on 100-foot stations along one side of the road and shall indicate finish gravel course alignment and cut and/or fill to top of gravel.

F. Restaking and Checking:

1. Contractor responsible for verifying location and elevation of all reference stakes and all markings noted thereon.
2. At Contractor's request, Engineer shall check validity of any questionable stake. Any stakes found to be in error will be reset at no charge to the Contractor.
3. Engineer not responsible for any standby or "down" time as a result of such checking and/or resetting.
4. All stakes or reference marks described in this section shall be set one time only. Upon written request by Contractor, Engineer will perform restaking at Contractor's expense.

END OF SECTION

SECTION 01051

CONTROL OF WORK

PART 1 GENERAL

1.01 SUMMARY

- A. This section includes the control of Work, including:
 - 1. Plans and working drawings;
 - 2. Conformity with plans and specifications;
 - 3. Construction stakes, lines, and grades;
 - 4. Load restrictions;
 - 5. Maintenance of traffic; and
 - 6. Maintenance during construction.

1.02 PLANS AND WORKING DRAWINGS

- A. Plans will show such details of all structures, lines, grades, location, and design of all structures and pipelines as are necessary to give the comprehensive idea of the proposed construction. The Contractor shall keep one set of the most current plans available on the project at all times.
- B. The plans may be supplemented by additional drawings as are necessary to adequately control the Work only in the event of an approved change order.

1.03 CONFORMITY WITH PLANS AND SPECIFICATIONS

- A. All Work performed and all materials furnished shall be in conformity with the lines, grades, details, dimensions, and material requirements including tolerances as indicated on the drawings or in the specifications.
- B. In the event the Engineer finds the materials, the finished product in which the materials are used, or the Work performed are not in conformity with the drawings and specifications or within tolerances specified on the drawings or in the specifications, and the Engineer finds that this has resulted in an inferior or unsatisfactory product, the Work or materials shall be removed and replaced or otherwise corrected by, and at the expense of the Contractor.
- C. In the event the Engineer finds the materials, the finished product in which the materials are used, or the Work performed are not in conformity with the drawings

and specifications or within tolerances specified on the drawings or in the specifications, but that reasonably acceptable Work has been produced, the Engineer will document the basis of acceptance by contract modification which will provide for an appropriate adjustment in the contract price for such work or materials.

1.04 CONSTRUCTION STAKES, LINES AND GRADES

- A. The Contractor shall be responsible to provide his own construction control stakes to establish lines, slopes, and grades as necessary for layout and completion of the Work. All survey work performed for layout of the site and final grade checks shall be performed by a licensed surveyor of the State of Arkansas. The Surveyor shall have construction experience with projects of similar type and nature to this project.

1.05 LOAD RESTRICTIONS

- A. The Contractor shall comply with all legal load restrictions in the hauling of materials on public highways beyond the limits of the project. The Contractor shall be responsible for all damage done by his hauling equipment and his construction activities.

1.06 MAINTENANCE OF TRAFFIC

- A. All public and private roads used for haul roads shall be maintained to provide an adequate and safe driving condition for all public and private traffic.

1.07 MAINTENANCE DURING CONSTRUCTION

- A. The Contractor shall maintain the Work during construction and until the project is accepted. The maintenance shall constitute continuous and effective work performed day to day with adequate equipment and forces such that all structures are kept in satisfactory condition at all times.
- B. The Contractor shall provide all necessary drainage control and diversion structures, and sufficient pumping equipment and manpower to keep the construction area well drained and free of standing water that may adversely impact construction procedures and schedules.
- C. The Contractor shall supply a description of the Contractor's maintenance schedule on equipment.

1.08 FUEL STORAGE, WASTE PRODUCTS, TRASH AND DEBRIS

- A. The Contractor shall observe all federal, state, and local requirements and regulations regarding the transportation, storage, and containment of fuels.
- B. The Contractor shall be responsible for proper containment and labeling of containers, handling of all waste products and trash from all machinery, vehicles, and other items used during the Work with the following exception. Containers will be provided, marked, and routinely picked up for putrescible waste, office trash, etc. Waste will be properly transferred for Off-Site Disposal under the direction of the Owner

PART 2 PRODUCTS

(NOT USED)

PART 3 EXECUTION

(NOT USED)

END OF SECTION

SECTION 01300 SUBMITTALS

PART 1 GENERAL

1.01 SUMMARY

Section includes submittal procedures and types of submittals required prior to the beginning of certain phases of the Work, prior to the incorporation of products in the Work, and during the progress of the Work.

1.02 INITIAL SUBMITTALS

- A. Submit the following to the Engineer for review not more than fourteen calendar days after the Effective Date of the Agreement:
 - 1. Preliminary Schedule of Values.
 - 2. Initial Construction Progress Schedule (specified in this Section).
 - 3. Preliminary Schedule of Shop Drawing and Sample Submittals (specified in this Section).
 - 4. Proposed Products List (specified in this Section).

1.03 PROGRESS SUBMITTALS

- A. Submit the following to the Engineer for review during the progress of the Work:
 - 1. Applications for Payment.
 - 2. Individual processing submittals and change orders.
 - 3. Independent quality control inspection and testing information.
 - 4. Project Record Documents.
 - 5. Equipment manufacturer's instructions and certificates.
 - 6. All other miscellaneous submittals not mentioned herein and as specified in other individual specification Sections.

1.04 SUBMITTAL PROCEDURES

- A. Timing of Submittals

1. Make submittals in advance of scheduled dates for installation, as specified in individual specification sections, to allow for reviews, for securing necessary approvals, for possible revisions and resubmittals, and for placing orders and securing deliveries. Preferred timing for the submittals will be discussed during the Preconstruction Meeting.
 2. Contractor shall be responsible for delays occasioned by incomplete submittals.
- B. Submittals shall be complete and shall be combined into one package for each Section of the specifications, unless otherwise specified.
 - C. Sequentially number the transmittal forms.
 - D. Identify Project, Contractor, Subcontractor or supplier; pertinent Drawing sheet and detail number(s), and specification section number, as appropriate.
 - E. Apply Contractor's stamp, signed or initialed certifying that review, verification of products required, field dimensions, adjacent construction work, and coordination of information, is in accordance with the requirements of the Work and Contract Documents.
 - F. Schedule submittals to expedite the project and deliver to Engineer. Coordinate submission of related items.
 - G. Identify variations from Contract Documents and product or system limitations, which may be detrimental to successful performance of the completed Work.
 - H. Provide a four-inch square blank space for Engineer's review stamp.
 - I. Revise and resubmit submittals in the same quantity as required for the original submittal. Identify all changes made since previous submittal.
 - J. Distribute copies of reviewed submittals to concerned parties. Instruct parties to promptly report any inability to comply with provisions.
 - K. Maintain one copy of each submittal in Project Record Documents.

1.05 CONSTRUCTION PROGRESS SCHEDULE

- A. Submit initial Construction Progress Schedule (first revision of schedule submitted with the Bid) in duplicate within the time specified in subsection 1.02 of this Section.

- B. Submit revised Schedule with each Application for Payment, identifying changes since previous version.
- C. Show complete sequence of construction by activity, identifying Work of separate stages and other logically grouped activities. Indicate the early and late start, early and late finish, float dates, and duration. Schedule shall be in accordance with the required work sequence and completion dates specified in Section 01010 and elsewhere in the Contract Documents.
- D. Indicate estimated percentage of completion for each item of Work at each submission.
- E. Indicate submittal dates required for shop drawings, product data, samples, product delivery, and quality control test reports.
- F. The Schedule shall be revised as required throughout the project to indicate anticipated and actual duration and sequence of activities. Copies of revised Schedules shall be provided promptly to the Engineer for review and comment.

1.06 PROPOSED PRODUCTS LIST

- A. Within the time specified in subsection 1.02 of this Section, submit complete list of major products proposed for use, with name of manufacturer, trade name, and model number of each product.
- B. For products specified only by reference standards, give manufacturer, trade name, model or catalog designation, and reference standards.
- C. Indicate on the list the product delivery dates, including those furnished by the Owner.
- D. The Owner's Chemical Acquisition Procedure must be adhered to in order to bring in chemicals.

1.07 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

- A. Within the time specified in subsection 1.02 of this Section, submit a preliminary Schedule of Shop Drawings and Samples in accordance. Include the following:
 - 1. The dates for Contractor's submittals.
 - 2. The dates submittals will be required for Owner-furnished products, if applicable.

3. The dates approved submittals will be required from the Engineer.
4. A list of all long lead items (equipment, materials, etc.).

B. Shop Drawings and Product Data Submittals

1. Submit the number of copies, which Contractor requires, plus three copies, which will be retained by Engineer.
2. Mark each copy of product data submittals to identify applicable products, models, options, and other data. Supplement manufacturer's standard data to provide information unique to this Project.

C. Sample Submittals

1. Submit samples to illustrate functional and aesthetic characteristics of the product, with integral parts and attachment devices. Coordinate sample submittals for interfacing work.
2. Include identification on each sample, with full project information.
3. Submit the number of samples specified in the individual specification Sections. The Engineer will retain one sample.

D. After review, distribute in accordance with subsection 1.03 above.

1.08 MANUFACTURERS' INSTRUCTIONS

- A. When specified in individual specification Sections, submit manufacturers' printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, in quantities specified for Shop Drawings and Product Data in subsection 1.07.A above.
- B. Identify conflicts between manufacturers' instructions and Contract Documents.

1.09 MANUFACTURERS' CERTIFICATES

- A. When specified in individual specification Sections, submit manufacturers' certificates to Engineer for review, in quantities specified for Shop Drawings and Product Data in subsection 1.07.A above.
- B. Indicate material or product conforms to or exceeds specified requirements Submit supporting reference data, affidavits, and certificates as appropriate.
- C. Certificates shall be based on test results acceptable to the Engineer.

1.10 INSPECTION AND TEST CERTIFICATES

- A. Submit to Engineer for review, inspection and test certificates required for demonstrating proof or compliance of materials with specification requirements.
- B. Each certificate shall be signed by an official authorized to certify on behalf of the manufacturing company and shall indicate the name and address of the Contractor, the project name and location, and the quantity and date or dates of shipment or delivery to which the certificates apply.
- C. Copies of laboratory test reports submitted with certificates shall contain the name and address of the testing laboratory and the date or dates of the test to which the report applies.
- D. Certification will not be construed as relieving the Contractor from furnishing satisfactory material, if, after tests are performed on selected samples, the material is found not to meet the specified requirements.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01400

QUALITY CONTROL AND ASSURANCE SERVICES

PART 1 GENERAL

1.01 DESCRIPTION OF WORK

- A. Owner will employ and pay for the services of the Technical Representative to perform construction monitoring and testing services to assure the Owner that the Work is completed according to the Specifications and Drawings.
- B. Contractor shall cooperate with the Technical Representative to facilitate the execution of its required services.
- C. Employment of the Technical Representative shall in no way relieve Contractor's obligations to perform the Work and supply materials in accordance with the Contract Documents.
- D. The Contractor shall provide any additional testing and services required to control construction quality at no additional cost to the Owner. Quality control testing and services do not include activities performed by the Technical Representative.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.01 CONTRACTOR'S RESPONSIBILITIES

The Contractor shall:

- A. Cooperate with the Technical Representative and its personnel and provide access to Work and to Supplier's operations.
- B. Secure and deliver to the Technical Representative adequate quantities (5-gallon bucket per sample) of representative samples of materials proposed to be used which require testing.
- C. Furnish copies of Supplier's test reports as required.
- D. Furnish incidental labor and facilities:

1. To provide access to Work to be tested;
 2. To obtain and handle samples at the Project site or at the source of the product to be tested;
 3. To facilitate inspections and tests; and
 4. For storage and curing of test samples.
- E. Coordinate activities to accommodate services with a minimum delay. Notify Technical Representative 48 hours in advance of operations to allow for laboratory assignment of personnel and scheduling of tests. When tests or inspections cannot be performed after such notice, reimbursing Owner for laboratory personnel and travel expenses incurred due to Contractor's negligence;
- F. Employ and pay for the services of a separate, qualified independent testing laboratory to perform additional inspections, sampling and testing required:
1. For the Contractor's convenience;
 2. As required by the Specifications or approved Quality Control Plans; or
 3. When initial tests indicate Work does not comply with Contract Documents.
- G. Promptly notify the Technical Representative of observed irregularities or deficiencies of Work or products;
- H. Promptly submit a copy of a written report of each test to Technical Representative. Each report shall include:
1. Date issued;
 2. Project title and number;
 3. Testing laboratory name, address and telephone number;
 4. Name and signature of laboratory inspector;
 5. Date and time of sampling or inspection;
 6. Record temperature and weather conditions;
 7. Date of test;
 8. Identification of product and specification section;
 9. Location of sample or test in the Project;
 10. Type of inspect or test;
 11. Results of tests and compliance with Contract Documents; and
 12. Interpretation of test results, when requested by Technical Representative.
- I. Be responsible for retesting where results of inspections and tests prove unsatisfactory and indicates noncompliance with requirements.

3.02 REPAIR AND PROTECTION

Unless specified otherwise, the Contractor shall protect construction exposed for testing and shall repair construction damaged by sampling, testing or inspection.

END OF SECTION

SECTION 01500 CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

PART 1 GENERAL

1.01 SUMMARY

A. Section includes:

1. Mobilization.
2. Temporary Utilities.
3. Barriers and enclosures.
4. Protection of existing utilities and installed Work.
5. Site security.
6. Access roads and parking.
7. Temporary Controls: construction cleaning; noise; water; soil erosion and sediment; pollution; and, dust.
8. Traffic control and haul routes.
9. Project identification and signs.
10. Field offices and sheds.
11. Removal of temporary utilities, facilities and controls.

1.02 MOBILIZATION

- A. Mobilize to the site and be prepared to initiate the construction activities within 5 Business days after receiving Notice of Award from the Owner.**
- B. Mobilization shall not be attempted unless the Contractor has:**
1. Obtained all permits, licenses and OSHA training certificates necessary to perform the Work, where required.
 2. Received approval from the Owner for the location of temporary structures and storage areas.
 3. Submitted initial documents to the Engineer as listed in subsection 1.02 A of Section 01300.

- C. Mobilization includes but is not necessarily limited to: transportation of personnel, equipment and operating supplies to the site; establishment of offices, buildings, all necessary temporary utilities; installation and relocation of necessary facilities at the site; and, other preparatory work at the site.

1.03 TEMPORARY UTILITIES

- A. The Owner will supply power service to provide required temporary electrical utilities to the project area.
- B. The Contractor will provide and maintain adequate lighting for construction operations and field offices.
- C. The Owner will provide adequate drinking water for construction operations.
- D. The Contractor will provide adequate fire protection at the site as required by local fire codes and standards.
- E. The Owner will provide adequate temporary sanitary facilities in compliance with laws and regulations. Arrange for proper maintenance of such facilities.
- F. The Contractor will provide, maintain and pay for telephone service to Contractor's offices. The Owner will supply radios for internal communication.
- G. The Contractor will provide, maintain and pay for any other temporary utility that is necessary to accomplish the Work.

1.04 BARRIERS AND ENCLOSURES

- A. Provide barriers to prevent unauthorized entry to construction areas to protect existing facilities and adjacent properties from damage from construction operations.
- B. Provide barricades, covered walkways and other temporary construction required by governing authorities for public rights-of-ways.
- C. All temporary construction shall be in accordance with applicable federal, state and local laws and building codes.
- D. Provide protection for plant life designated to remain. Trim tree branches if necessary for access and only if permitted by the Owner. Replace damaged plant life, or repair as follows:

1. Damaged branches shall be properly pruned and all wounds covered with approved tree paint.
 2. Repair work shall be done on a daily basis without exception.
- E. Protect non-covered vehicular traffic, stored materials, site and structures from damage.

1.05 PROTECTION OF EXISTING UTILITIES

- A. Contact and cooperate with the Owner and utility companies to locate all utilities (including pipelines, cables, power poles and other structures) on the construction site prior to beginning the Work.
- B. All utilities shall be protected from damage during construction, unless otherwise indicated to be removed or abandoned.
- C. Comply with requirements of the utility owners for clearances and access for all construction within and adjacent to the utility right-of-way.
- D. If damaged, the utilities shall be repaired as required by the Owner at the Contractor's expense.
- E. If a utility is encountered which is not shown on the Drawings or otherwise made known to the Contractor prior to beginning the Work, promptly take necessary steps to assure that the utility is not damaged, and give written notice to the Owner or Engineer and to the utility owner. The Owner and Engineer will then review the conditions and determine the extent, if any, to which a change is required in the Contract Documents to reflect and document the consequences of the existence of the utility.

1.06 PROTECTION OF INSTALLED WORK

- A. Protect installed Work and provide special protection where required in individual specification sections.
- B. Provide temporary and removable protection for installed Products. Control activity in immediate work area to minimize damage.

1.07 SECURITY

The Owner will provide Security at the Construction Gate. Any additional Security the Contractor required in the working area will be paid for by the Contractor.

1.08 ACCESS ROADS AND PARKING

- A. Construct and maintain temporary roads accessing existing roads to serve construction area.
- B. Extend and relocate, as Work progress requires. Provide detours necessary for unimpeded traffic flow.
- C. Designated existing on-site roads may be used for construction traffic, unless otherwise directed by the Owner or Engineer.
- D. Construct temporary gravel surface parking areas in areas approved by the Owner to accommodate construction personnel.
- E. When site space is not adequate, provide additional off-site parking.
- F. Repair existing roads damaged by operation of construction equipment, as determined by the Engineer.

1.09 CONSTRUCTION CLEANING

- A. Maintain areas free of trash and rubbish. Maintain site in a clean and orderly condition.
- B. No trash or rubbish containers will be supplied by Owner. Supply all containers required for storage and removal of trash, rubbish and debris resulting from the Work included in this project.
- C. The Owner will put the pick-up of routine trash on the maintenance route. All disposal shall occur in the approved containers at the facility.

1.10 NOISE CONTROL

Contractor's vehicles and equipment shall be such as to minimize noise to the greatest degree practicable. Noise levels shall conform to the latest OSHA standards and state, county and local ordinance requirements, and in no case will noise levels be permitted which interfere with the work of the Owner or others.

1.11 WATER CONTROL

Provide and maintain water control as specified in Section 01563.

1.12 SOIL EROSION AND SEDIMENT CONTROL

Provide and maintain soil erosion and sediment control as specified in Section 01565.

1.13 POLLUTION CONTROL

- A. Provide methods, means and facilities required to prevent contamination of soil, water or atmosphere by the discharge of noxious substances from construction operations.
- B. Provide equipment and personnel, perform emergency measures required to contain significant spillage on-site, as determined necessary by the Engineer and Owner. Collect all oil and other fluids discharged during vehicle maintenance operation in drums and dispose of properly.
- C. Take special measures to prevent harmful substances from entering public waters. Prevent disposal of wastes, effluents, chemicals, or other such substances adjacent to streams, or in sanitary or storm sewers. Conform to Owner's existing NPDES permit for the facility.
- D. Provide systems for control of atmospheric pollutants. Prevent toxic concentrations of chemicals and prevent harmful dispersal of pollutants in the atmosphere.
- E. All Contractors' equipment used during construction shall conform to all current federal, state and local laws and regulations. The Contractor must supply all the Spec Sheets for Pumps and Compressors they will bring on site.

1.14 DUST CONTROL

- A. Maintain all excavations, embankments, stockpiles, roads, and all other work areas within or outside the project boundaries free from visible airborne dust that would cause a hazard or nuisance to others.
- B. Approved temporary methods of stabilization, consisting of sprinkling with clean water, or similar methods, will be required to control dust. Sprinkling must be repeated at such intervals as to keep all parts of the disturbed area at least damp at all times.

1.15 TRAFFIC CONTROL

- A. Coordinate movement of construction equipment and hauling vehicles with Owner to prevent interference with public traffic and parking, access by emergency vehicles, and Owner's operations.
- B. Provide trained and equipped flag persons to regulate traffic when construction operations or traffic encroach on public traffic lanes.

1.16 HAUL ROUTES

- A. Consult with authority having jurisdiction in establishing public thoroughfares to be used for haul routes and site access.
- B. Confine construction traffic to designated haul routes.

1.17 FIELD OFFICES AND SHEDS

- A. Office: Weather-tight, with lighting, electrical outlets, heating, cooling and ventilating equipment, and equipped with sturdy furniture.

1.18 REMOVAL OF TEMPORARY UTILITIES, FACILITIES AND CONTROLS

- A. Remove temporary above-grade and buried utilities, equipment, facilities and materials prior to final inspection.
- B. Clean and repair damage caused by installation or use of temporary work.
- C. Restore existing facilities used during construction to original condition.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01563 CONTROL OF WATER

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Controlling surface water runoff.
- B. Dewatering trenches, excavations, and other elements.
- C. Controlling water of every origin.

1.02 SUBMITTALS

Submit in accordance with Section 01300 -Submittals

PART 2 PRODUCTS

Provide structures, machinery, appliances, and equipment designed and manufactured to control water.

PART 3 EXECUTION

3.01 GENERAL

- A. Dewatering Procedures: The Contractor shall construct, maintain, and operate channels, sumps, pumps, or other temporary diversion and protection works. Furnish materials required, install, maintain and operate necessary pumping and other equipment for the environmentally safe removal and disposal of water from the various parts of the Work.
- B. Dewater and dispose of water in a manner that will not cause injury to public and private property.
- C. Do not cause a nuisance to the Owner's operations.
- D. Keep sufficient pumping equipment and machinery on hand at all times for emergencies, including electric power failures.

- E. Keep experienced personnel available at all times to operate pumping equipment, machinery and appliances.
- F. Do not shut down dewatering systems between shifts, on holidays and weekends, nor during Work stoppages, unless authorized by Owner or Engineer.

END OF SECTION

SECTION 01565

TEMPORARY SOIL EROSION AND SEDIMENT CONTROL

PART 1 GENERAL

1.01 SUMMARY

Section includes construction of temporary measures to control soil erosion and sediment transport within the construction limits.

1.02 REFERENCES

- A. "Erosion and Sediment Control Handbook", published by McGraw-Hill Book Company.
- B. American Society for Testing and Materials (ASTM):
 - 1. ASTM D 488, Standard Classification for Sizes of Aggregate for Road and Bridge Construction.

1.03 SUBMITTALS

Submit product data and specifications for approval as required by the Engineer prior to use.

1.04 QUALITY ASSURANCE

Comply with the requirements of governmental authorities having jurisdiction.

1.05 PROJECT REQUIREMENTS

- A. Obtain all required permits prior to commencement of Work in areas requiring erosion control measures.
- B. The use of temporary control measures shall be coordinated with the permanent erosion control features specified elsewhere to the extent practical, to assure effective and continuous erosion control.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Mulch: Hay, straw, wood chips, or other suitable material reasonably clean of noxious weeds and deleterious material.
- B. Grasses: Rye grass, cereal grasses, or other quick-growing species suitable to the area and as a temporary cover, which will not compete with the grasses specified for permanent cover.
- C. Silt Fencing: "Envirofence" by Mirafi, "Propex Silt Stop" by Amoco, or equivalent. Posts shall be as shown on the Drawings.
- D. Check Dams shall be constructed of locally available sound crushed stone; size conforming to ASTM D 448, size number 1.

PART 3 EXECUTIONS

3.01 GENERAL

- A. All Work under this contract shall be performed in such a manner that objectionable erosion shall not be created in watercourses through or adjacent to the project area.
- B. The Contractor shall be responsible for the selection of appropriate temporary erosion control measures to suit the intended construction methods. The Contractor shall submit a scheme of control measures for each potentially impacted area prior to construction for approval by the Engineer.
- C. Notify the Engineer and Owner in the event of conflict between these specification requirements and pollution control laws, rules or regulations of other federal, state, or local agencies.

3.02 EROSION AND SEDIMENT CONTROL

- A. The Engineer shall have the authority to limit the surface area of erodible earth material exposed by clearing and grubbing, excavation, borrow, and fill operations and to direct the Contractor to provide immediate, permanent or temporary sediment control measures to minimize damage to adjacent property and to minimize effects on adjacent streams or other watercourses, lakes, ponds, or other areas of water impoundment.

- B. Incorporate all permanent erosion control features (including seeding) into the project at the earliest practical time. Temporary control measures shall be those that are needed prior to installation of permanent control features; or that is needed temporarily to control erosion that develops during normal construction activities but are not associated with permanent control features on the project.
- C. Where erosion is likely to be a problem, clearing and grubbing operation should be so scheduled and performed that grading operations and permanent erosion control features can follow immediately thereafter, if the project conditions permit; otherwise temporary erosion control measures may be required between successive construction stages.

3.03 INSTALLATION AND MAINTENANCE OF SILT FENCING

- A. Install in accordance with details shown on the Drawings and as specified in paragraphs B through E below.
- B. Install posts at a maximum spacing of six feet, and to depth of approximately 18 inches, or as otherwise approved by the Engineer and Owner.
- C. Excavate six-inch wide by six-inch deep trench along line of posts and upslope from barrier, or as otherwise approved by the Engineer and Owner.
- D. Fasten fabric to upstream side of posts using heavy-duty wire staples (at least one-inch long), tie wires or hog rings. Eight inches of the fabric shall extend into the trench.
- E. Backfill trench and compact soil over the fabric.
- F. Remove sediment deposits when deposits reach approximately one-half the height of the barrier. Sediment shall be placed in areas approved by the Engineer and spread uniformly over the ground surface.
- G. Replace fabric when it has deteriorated, is torn, loose or no longer effectively performs.
- H. Replace any silt fence, which has been overtopped with two new parallel fences.

3.04 APPLICATION OF TEMPORARY GRASS AND MULCH (If Needed)

- A. Comply with Section 02930.
- B. Temporary seeding shall be applied to areas lacking vegetation if no construction activities will be performed in the area for more than 30 Calendar days. Temporary seed mixtures shall be applied to such areas within 21 Calendar days of temporarily suspending work in the area.

3.05 CONSTRUCTION AND MAINTENANCE OF CHECK DAMS

- A. Construct across creeks within the project limits as shown on the Drawings.
- B. Inspect after each rainfall event. Make required repairs if the check dams have deteriorated to the extent that their effectiveness is reduced.
- C. Remove sediment deposits when deposits reach approximately one-half the height of the dams. Sediments shall be placed in areas approved by the Engineer and spread uniformly over the ground surface.
- D. Check dams shall be removed after completion of construction activities. Coarse aggregate shall be deposited on-site where approved by the Engineer.

3.06 INSTALLATION AND MAINTENANCE OF OTHER EROSION CONTROL MEASURES

- A. Install according to manufacturer's recommendations and standard local practice.
- B. Maintenance of the installations shall be performed as required for proper erosion and sediment control until the Work is accepted by the Owner.

3.07 REMOVAL OF SILT FENCING

- A. Silt fencing shall be removed when approved by the Engineer and Owner, after a sufficient stand of grass has been established on all disturbed areas.
- B. Any sediment deposits remaining after the silt fence is removed shall be dressed to conform to the existing grade, prepared, and seeded.

END OF SECTION

SECTION 01600

MATERIAL AND EQUIPMENT

PART 1 GENERAL

1.01 SUMMARY

- A. Section Addresses:
 - 1. Products;
 - 2. Transportation and handling;
 - 3. Storage and protection;
 - 4. Product options; and
 - 5. Substitutions.

1.02 PRODUCTS

- A. Products: Means new material, machinery, components, equipment, fixtures, and systems forming the Work. Does not include machinery and equipment used for preparation, fabrication, conveying and erection of the Work. Products may also include existing materials or components required for reuse.

1.03 TRANSPORTATION AND HANDLING

- A. Contractor shall transport and handle products in accordance with manufacturer's instructions.
- B. Contractor shall promptly inspect shipments to assure that products comply with requirements, quantities are correct, and products are undamaged.
- C. Contractor shall provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, and damage.

1.04 STORAGE AND PROTECTION

- A. Contractor shall store and protect products in accordance with manufacturer's instructions, with seals and labels intact and legible. Contractor shall store sensitive products in weather-tight, climate controlled enclosures.
- B. For exterior storage of fabricated products, materials shall be placed on sloped supports, above ground.

- C. Contractor shall provide off-site storage and protection when site does not permit on-site storage or protection.
- D. Contractor shall cover products subject to deterioration with impervious sheet covering. Contractor shall provide ventilation to avoid condensation.
- E. Contractor shall store loose granular materials on solid flat surfaces in a well-drained area. Contractor shall make every effort to prevent mixing with foreign matter.
- F. Contractor shall provide equipment and personnel to store products by methods to prevent damage.
- G. Contractor shall arrange storage of products to permit access for inspection. Contractor shall periodically inspect storage areas to assure products are undamaged and are maintained under specified conditions.

1.05 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Any product meeting those standards or description.
- B. Products Specified by Naming One or More Manufacturers: Products of manufacturers named and meeting specifications; no options or substitutions allowed.
- C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.

1.06 SUBSTITUTIONS

- A. Engineer will consider requests for Substitutions only within 15 Calendar days after Effective Date of Agreement.
- B. Subsequent Substitutions will be considered only when a product becomes unavailable through no fault of the Contractor. Improper planning will not be considered as a reason to increase Contract Price as a result of product substitution.
- C. A request constitutes a representation that the Contractor:
 - 1. Will provide the same warranty for the Substitution as for the specified product.
 - 2. Will coordinate installation and make changes to other Work which may be required for the Work to be complete with no additional cost to the Owner.

3. Waives claims for additional costs or time extension which may subsequently become apparent.
 4. Will reimburse Owner for review or redesign services associated with re-approval by Engineer and Engineer's consultants and regulatory agencies.
- D. Substitutions will not be considered when they are indicated or implied on shop drawing or product data submittals, without separate written request, or when acceptance will require revision to the Contract Documents.
- E. Substitution Submittal Procedure:
1. Contractor will submit copies of each request for Substitution for consideration. Contractor shall limit each request to one proposed Substitution.
 2. Contractor shall submit the number of copies required for all submittals, as specified in Section 01300.
 3. Contractor shall submit shop drawings, product data, and certified test results attesting to the proposed product equivalence.

1.07 MANUFACTURER'S INSTRUCTIONS

- A. Installation of equipment and materials shall comply with manufacturer's instructions. Contractor shall obtain and distribute printed copies of such instructions to parties involved in installation, including two copies to Owner.
1. Contractor shall maintain one set of complete instructions at job site during installation and until completion of work.
- B. Contractor shall handle, store, install, connect, clean, condition, and adjust materials and equipment in accordance with manufacturer's written instructions and in conformance with specifications.
1. If job conditions or specified requirements conflict with manufacturer's instructions, Contractor shall consult with Owner or Engineer for further instructions.
 2. Contractor shall not proceed with work without written instructions.

1.08 INSTALLATION, INSTRUCTIONAL, AND POST START-UP SERVICES

A. Installation Services:

1. Where installation services are called for in Specifications, Contractor shall provide competent and experienced technical representatives of manufacturers of equipment and systems to resolve assembly or installation procedures attributable to, or associated with, equipment furnished.
2. After equipment is installed, representatives shall perform initial equipment and system adjustment and calibration to conform to Specifications and manufacturer's requirements and instructions.
3. Contractor shall provide "Certificate of Installation Services" stating proper adjustments have been made to equipment or system and equipment or system ready for start-up and operation.

B. Instructional Services:

1. Where training is called for in Specifications, Contractor shall provide competent and experienced technical representative of supplier to provide detailed instructions to Owner's personnel for operation of equipment. Training services shall include maintenance of instrumentation, maintenance of process equipment and operation of process equipment in classroom and on-site equipment instruction, as stated in Specifications.
2. Contractor shall coordinate pre-startup training periods with Owner and supplier's representatives.
 - a. Contractor shall notify Owner at least 48 hours before training sessions are to begin so Owner can make arrangements with operating personnel.
 - b. Contractor shall reschedule canceled training sessions 48 hours in advance.
 - c. Failure of supplier's or manufacturer's representative to appear for scheduled training, failure to notify Owner 24 hours in advance of need to cancel scheduled training or failure to arrive within 30 minutes of start of scheduled training shall result in reimbursement to Owner for time lost by Owner's operating personnel in waiting for arrival of manufacturer's representative. Except in case of failure to arrive on time, time will not exceed one hour for each employee scheduled to receive training. Failure to arrive on time will be reimbursed by actual time late up to one hour, after one hour training will be rescheduled.
3. Similar types of equipment differing in model, size or manufacturer shall require equal service time as stated in specific Specification section.

4. Contractor shall complete pre-startup training Calendar 14 days prior to system operations demonstrations.
5. O&M data shall constitute basis of instruction.
 - a. Contractor shall review data contents with personnel in full detail to explain aspects of operations and maintenance.
6. Contractor shall provide "Certificate of Instructional Services," co-signed by Owner and supplier's representative, verifying training accomplished to satisfaction of all parties.

1.09 SPECIAL TOOLS AND LUBRICATING EQUIPMENT

- A. Contractor shall furnish, in accordance with manufacturer's recommendations, special tools required for checking, testing, parts replacement, and maintenance. Special tools are those specially designed or adapted for use on parts of equipment, and not customarily and routinely carried by maintenance mechanics.
- B. Special tools and lubricating equipment (when applicable) will be delivered to Owner when unit placed into operation and after operating personnel have been properly instructed in operation, repair, and maintenance of equipment.
- C. Tools and lubricating equipment shall be of quality compatible to equipment manufacturer has furnished.

1.10 LUBRICATION

- A. Where lubrication is required for proper operation of equipment, Contractor shall incorporate necessary and proper provisions in equipment in accordance with manufacturer's requirements. Where possible, lubrication shall be automated and positive.
- B. Where oil is used, reservoir shall be of sufficient capacity to supply unit for 24-hour period.
- C. Contractor shall supply a description of the Contractor's maintenance schedule on equipment.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01720 PROJECT RECORD DOCUMENTS

PART 1 GENERAL

1.01 DESCRIPTION

- A. Owner will have the right to the access of all records, such as correspondence and claims that are maintained on site or any other locations by Contractor.
- B. Contractor shall maintain at site for Owner one record copy of:
 - 1. Drawings;
 - 2. Specifications;
 - 3. Addenda;
 - 4. Change orders and other modifications to Contract;
 - 5. Field orders, written instructions, or clarifications;
 - 6. Approved submittals;
 - 7. Field test records;
 - 8. All associated permits; and
 - 9. Certificates of inspection and approvals.

1.02 MAINTENANCE OF DOCUMENTS AND SAMPLES

- A. Contractor shall maintain documents in clean, dry, legible condition and in good order. Contractor shall not use record documents for construction purposes.
- B. Contractor shall provide secure storage space for storage of samples and maintain same in good order.
- C. Contractor shall make documents and samples available at all times for inspection by Owner.
- D. Failure to properly maintain record documents may be reason to delay a portion of progress payments until records comply with Contract Documents.

1.03 RECORD DOCUMENTS

- A. Contractor shall maintain a record set of drawings and specifications legibly changed to transfer approved modifications in completed work that differ from Contract Documents.
- B. Contractor shall label each document "PROJECT RECORD" in neat, large printed letters.
- C. Contractor shall record information concurrently with construction progress.
 - 1. Contractor shall not cancel any work until required information is recorded.
 - 2. Contractor shall record changes made by Written Amendment, Field Order, Change Order, or Work Directive Change.

D. Drawings (By Owner)

Based on Contractor mark-ups and survey data provided by Contractor and Owner's survey, a set of record as-built drawings will be prepared by Owner (or Owner's representative) for inclusion in the project Certification Report.

- E. At completion of work:
 - 1. Using data accumulated on drawings, Contractor shall submit a set of marked up drawings showing all approved changes and revisions to the Work as authorized by the Owner and Engineer. This information will provide the basis for preparation of the as-built record drawings (by others).
 - 2. Submit separate document indicating changes made to specifications during work.

1.04 SUBMITTALS

A. At substantial completion Contractor shall:

1. Deliver one set of marked up record drawings to Owner; and
2. Deliver documents described in Paragraph 1.01.B to Owner.

B. Submittals shall include a transmittal letter in duplicate, containing:

1. Date;
2. Project title and number;
3. Contractor's name and address;
4. Title of record document; and
5. Signature of Contractor or authorized representative.

PART 2 PRODUCTS

(NOT USED)

PART 3 EXECUTION

(NOT USED)

END OF SECTION

SECTION 02110 CLEARING AND GRUBBING

PART1 GENERAL

1.01 SUMMARY

- A. Section includes clearing woodchips from the work area, grubbing of vegetation, stripping of topsoil, and disposal of vegetation in the Work Area.

1.02 QUALITY ASSURANCE

- A. Site clearing shall be performed in a manner that does not disturb existing structures, utilities, monitoring wells, or other facilities not indicated to be removed or abandoned.
- B. Conform to applicable local codes for disposal of cleared and grubbed vegetation.
- C. Coordinate clearing work with utility companies.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.01 CLEARING

- A. Remove compost piles, exposed trees, brush, logs, grass, and other vegetative material resting on or protruding through the ground surface in the work area shown on the Drawings.
- B. Remove roots of all vegetation (including tree stumps) to a minimum depth of one foot below existing grade, or the proposed subgrade elevation, whichever is lower.

3.02 TOPSOIL STRIPPING

- A. Excavate topsoil from areas to receive fill.
- B. Stockpile topsoil in an area on-site where approved by the Owner or Engineer. Implement temporary erosion and sediment control measures specified in Section 01565.

3.03 DISPOSAL OF WOOD AND BRUSH

- A. All wood and brush shall be disposed of within 15 calendar days after cutting or felling unless otherwise approved. Coordinate disposal with owner.

END OF SECTION

SECTION 02200 EARTHWORK

PART 1 GENERAL

1.01 SUMMARY

- A. Section includes general earthwork for grading of the site, excavation, subgrade fill, general fill, fill placement for access roads, berms, underground pipelines, and stormwater facilities.
- B. Related Sections:
 - 1. Section 02220 - Excavation and Backfilling

1.02 REFERENCES

- A. American Society for Testing and Materials (ASTM).
 - 1. ASTM D 422, Standard Method for Particle-Size Analysis of Soils.
 - 2. ASTM D 698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort.
 - 3. ASTM D 1140, Standard Test Method for Amounts of Material in Soils Finer than the Number 200 Sieve.
 - 4. ASTM D 1557, Standard Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures Using Ten-Pound (4.54 kg) Hammer and 18-Inch (457 mm) Drop.
 - 5. ASTM D 2216, Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil and Rock.
 - 6. ASTM D 2487, Standard Test Method for Classification of Soils for Engineering Purposes.
 - 7. ASTM D 6938, Standard Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
 - 8. ASTM D 3017, Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).

9. ASTM D 4318, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.

1.03 DEFINITIONS

- A. Excavation: Consists of the removal of material encountered to subgrade elevations and the reuse disposal of materials removed.
- B. Subgrade: The uppermost surface of an excavation or the top surface of a fill or backfill immediately below base course.
- C. Borrow: Soil material obtained from borrow areas when sufficient approved soil material is not available from excavations.
- D. Unauthorized Excavation: Consists of removing materials beyond indicated subgrade elevations or dimensions without direction by the Engineer. Unauthorized excavation shall be at the Contractor's expense.

1.04 QUALITY ASSURANCE/QUALITY CONTROL

Owner will retain the services of an inspection and testing firm to determine conformance of the materials and constructed work with the specifications.

1.05 PROJECT CONDITIONS

- A. Provide temporary controls as specified in Sections 01563 and 01565.
- B. The Contractor is solely responsible for excavation slope stability. Excavation work shall be in compliance with applicable OSHA regulations and State regulations.

PART 2 PRODUCTS

2.01 GENERAL

Provide all labor, materials, and equipment necessary to accomplish the Work specified in this section.

2.02 SOIL MATERIALS

- A. General Fill: On-site soil or borrow material free of large rock, debris, waste, frozen material, vegetation, and other deleterious matter with a maximum particle size of six inches.
- B. Prepared Subgrade: In areas to be filled, unless otherwise noted, upper eight inches of in-situ soil, scarified and recompactd to density of subsequent layer of fill/backfill material.

2.03 OTHER MATERIALS

Provide other materials (like gravel), not specifically described herein but required for a complete and proper installation, as selected by the Contractor subject to the approval of the Engineer.

2.04 WATER FOR COMPACTION

Furnish as required. Contractor will have to obtain a source from Owner.

PART 3 EXECUTION

3.01 PREPARATION

- A. Protect structures, utilities, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by earthwork operations.
- B. Protect subgrades and foundation soils against freezing temperatures or frost. Provide protective insulating materials as necessary.
- C. Provide erosion control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties.

3.02 DEWATERING

- A. Prevent surface water and subsurface or ground water from entering excavations, from ponding on prepared subgrades, and from flooding Project site surrounding areas.
- B. Protect subgrade soils from softening and damage by rain or water accumulation.

3.03 EXCAVATION

- A. Perform excavation of every type of material encountered within the limits of the Work to the lines, grades, and elevations indicated on the Drawings and specified herein.
- B. Satisfactory Excavated Materials shall be transported to, and place in, fill or embankment areas within the limits of Work.
- C. Unsatisfactory Excavated Materials
 - 1. Unsatisfactory material excavation shall include excavation and disposal of soft or compressible soils, old spoil material, or any other materials judged by the Engineer to be unsuitable for foundations or the placement of compacted soils.
 - 2. Excavate to a distance below grade as directed by the Engineer and replace with satisfactory materials.
 - 3. The Contractor shall include excavation of unsatisfactory materials, and replacement by satisfactory materials, as parts of the Work of this Section.
 - 4. Dewatering shall be provided in areas of undercutting to a depth of at least two feet below the bottom of the excavation and shall be maintained until compacted earth fill is placed to at least three feet above the original water level or original ground level, whichever is higher.
- D. Surplus Materials or unsatisfactory excavated materials, and surplus satisfactory excavated material, shall be disposed of on-site in designated areas.

3.04 DITCHES AND GUTTERS

- A. Cut accurately to the cross sections, grades and elevations shown on the Drawings.
- B. Maintain excavation from detrimental quantities of debris until completion of work.
- C. Dispose of excavated materials as shown on the Drawings or as directed by the Engineer; except do not, in any case, deposit materials less than three feet from the edge of a ditch.

3.05 UNAUTHORIZED EXCAVATION

Unauthorized excavation consists of removal of materials beyond indicated subgrade elevations or dimensions without specific instruction from the Engineer.

3.06 STABILITY OF EXCAVATIONS

Comply with local codes, ordinances, and requirements of authorities having jurisdiction to maintain stable excavations.

3.07 APPROVAL OF SUBGRADE

- A. Notify Engineer when excavations have reached required subgrade.
- B. When Engineer determines that unforeseen unsatisfactory soil is present, continue excavation and replace with compacted backfill or fill material as directed.
- C. Unforeseen additional excavation and replacement material will be paid according to the Contract provisions for changes in Work.
- D. Reconstruct subgrades damaged by freezing temperatures, frost, rain, accumulated water, or construction activities, as directed by the Engineer.

3.08 STORAGE OF SOIL MATERIALS

- A. Stockpile excavated materials acceptable for backfill and fill soil materials, including acceptable borrow materials. Stockpile soil materials without intermixing. Place, grade, and shape stockpiles to drain surface water. Cover to prevent wind-blown dust.
- B. Stockpile soil material away from edge of excavations. Do not store within drip line of remaining trees or coordinate with owner.

3.09 GENERAL BACKFILLING

- A. Backfill excavations promptly, but not before completing the following:
 - 1. Acceptance of construction below finish grade including, where applicable, dampproofing, waterproofing, and perimeter insulation.
 - 2. Surveying locations of underground utilities for record documents.
 - 3. Testing, inspecting, and approval of underground utilities.

4. Removal of trash and debris from excavation.
5. Removal of temporary shoring, bracing, and sheeting.
6. Installing permanent or temporary horizontal bracing on horizontally supported walls.

3.10 FILL

- A. Preparation: Remove compost, vegetation, topsoil, debris, wet, and unsatisfactorily soil materials, obstructions, and deleterious materials from ground surface prior to placing fills.
- B. Place fill material in not more than eight to nine-inch loose layers to required elevations for each location listed below.

3.11 MOISTURE CONTROL

- A. Unless otherwise noted, uniformly moisten or aerate subgrade and each subsequent fill or backfill layer to obtain compaction.
 1. Do not place backfill or fill material on surfaces that are muddy, frozen, or contain frost or ice.
 2. Remove and replace or scarify and air-dry satisfactory soil material that is too wet to compact and is rutting when equipment is operating.
 3. Stockpile or spread and dry removed wet satisfactory soil material.

3.12 COMPACTION

- A. Place backfill and fill materials in layers not more than eight to nine inches in loose depth for material compacted by heavy compaction equipment and not more than four inches loose depth for material compacted by hand-operated tampers.
- B. Place backfill and fill materials evenly on all sides of structures to required elevations.
- C. Unless otherwise noted, scarify and recompact upper six inches of subgrade to density not less than required for the subsequent layer of fill/backfill material.

3.13 GRADING

- A. General: Uniformly grade areas to a smooth surface free from irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and evaluations indicated.
 - 1. Provide a smooth transition between existing adjacent grades and new grades.
 - 2. Cut off soft spots, fill low spots, and trim high spots to conform to required surface tolerances.
- B. Site Grading: Slope grades to direct water away from buildings and to prevent ponding. Finish subgrades to required elevations within plus or minus 0.10-foot tolerances:

3.14 TOPSOIL

After rough grading is completed and reviewed by Engineer, spread topsoil over specified areas as shown on the Drawings to a minimum compacted thickness of twelve inches.

3.15 FIELD QUALITY CONTROL

- A. Testing Agency Services: Allow testing agency to inspect and test each subgrade and each fill or backfill layer. Do not proceed until test results for previously completed work verify compliance with requirements.
- B. When testing agency reports that subgrades, fills, or backfill are not properly stable, scarify and moisten or aerate, or remove and replace soil to the depth required, recompact and retest until required density is obtained.

3.16 PROTECTION

- A. Protecting Graded Areas: Protect newly graded areas from traffic, freezing, and erosion. Keep free of trash and debris.
- B. Repair and re-establish grades to specified tolerances where completed or partially completed surfaces become eroded, rutted, settled, or lose compaction due to subsequent construction operations or weather conditions.
 - 1. Scarify or remove and replace material to depth directed by the Engineer; reshape and recompact to optimum moisture content or the required density.
- C. Settling: Where settling occurs during the Project correction period, remove finished surfacing, backfill with additional approved material, compact, and reconstruct surfacing.
- D. Restore appearance, quality, and condition of finished surfacing to match adjacent work, and eliminate evidence of restoration to the greatest extent possible.

END OF SECTION

SECTION 02210 GENERAL FILL

PART 1 GENERAL

1.01 DESCRIPTION OF WORK

- A. The Contractor shall furnish all labor, materials, tools, supervision, transportation, and installation equipment necessary for the construction of earthwork structures as specified herein, as shown on the Drawings, and in accordance with the project specifications.
- B. The work of this Section shall include, but not necessarily be limited to: separating, hauling, stockpiling, backfilling, compacting, and grading of soils. The work of this Section may pertain in whole or in part to construction of the following: perimeter berm, roads, settling pond, and access pads. The work of this Section also includes dewatering and protection. The Contractor shall be prepared to construct the structural fill in conjunction with other construction activities and subcontractors at the site.
- C. Notwithstanding the prequalification of any material sources for the structural fill, the Contractor shall be entirely responsible for meeting the requirements of this Section.

1.02 REFERENCES

- A. *Compost Pad Improvements for the City of Little Rock Landfill, Little Rock, Arkansas.*, dated September 2023, Terracon Consultants, Inc.
- B. Latest version of American Society for Testing and Materials (ASTM) standards:
 - 1. ASTM D 422, Standard Test Method for Particle-Size Analysis of Soils.
 - 2. ASTM D 698, Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³)).
 - 3. ASTM D 1556, Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method.
 - 4. ASTM D 1557, Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN-m/m³)).
 - 5. ASTM D 2216, Standard Test Method for Laboratory Determination of

Water (Moisture) Content of Soil and Rock.

6. ASTM D 2487, Standard Classification of Soils for Engineering Purposes (Unified Soil Classification System).
7. ASTM D 6938, Standard Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
8. ASTM D 2937, Standard Test Method for Density of Soil in Place by the Drive-Cylinder Method.
9. ASTM D 3017, Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).
10. ASTM D 4220, Standard Practices for Preserving and Transporting Soil Samples.
11. ASTM D 4318, Standard Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.

1.03 SUBMITTALS

- A. The Contractor shall discuss with the Owner and the CQA Consultant the proposed methods of construction, including stripping, dewatering, excavation, filling, compaction, and backfilling for the various portions of the work. The review shall be for method only. The Contractor shall remain responsible for the adequacy and safety of the methods.
- B. For each soil type specified in Part 2 of this Section, the Contractor shall submit to the Owner and the CQA Consultant the following information and samples a minimum of calendar 14 days prior to starting construction:
 1. the proposed material source;
 2. the results of grain-size analyses conducted on the proposed material in accordance with ASTM D 422;
 3. for fine-grained materials, the results of liquid and plastic limit tests conducted on the proposed material in accordance with ASTM D 4318;
 4. the results of a moisture-density relation test (ASTM D 698); and
 5. a 50-lb sample of each of the proposed soils or authorization to access the

proposed source(s) for sampling.

- C. The Contractor shall notify the Owner and the CQA Consultant in writing at least seven calendar days in advance of intention to perform the work of this Section.
- D. If work is interrupted for reasons other than inclement weather, the Contractor shall notify the Owner and the CQA Consultant immediately and provide a plan and schedule for resumption of the work.
- E. The Contractor shall abide by all qualification requirements of the CQA Plan.

1.04 CONSTRUCTION QUALITY ASSURANCE

- A. The construction of the structural fill shall be performed in accordance with the requirements of this section.
- B. The construction of the structural fill shall be monitored by the CQA Consultant as outlined in the project specifications.
- C. The Contractor shall be aware of the CQA activities outlined in the project specifications and account for these CQA activities in the construction schedule.

1.05 PROTECTION

- A. The Contractor shall contact utility companies and locate, mark and protect all existing utilities before commencement of construction.
- B. The Contractor shall protect trees, shrubs, lawns, rock outcroppings and other features remaining as part of final landscaping.
- C. The Contractor shall protect benchmarks, survey markers, fences, roads, sidewalks, paving, curbs and other existing structures from damage due to the Contractor's activities.
- D. The Contractor shall repair damage caused by the construction operations.
- E. Erosion control must be maintained. Erosion control measures shall be as noted on the grading plan or as directed by the Company.
- F. If any damages occur the Contractor shall notify the Owner through their Project Manager.

PART 2 PRODUCTS

2.01 MATERIALS

- A. All laboratory testing to evaluate the suitability or conformance of soil materials for the structural fill shall be carried out in accordance with the test methods indicated in Part 1.04 of this Section.
- B. Structural fill shall consist of relatively homogeneous, natural soils that are free of debris, foreign objects, large rock fragments, roots, and organics. No materials larger than three in. shall be allowed.

PART 3 EXECUTION

3.01 FAMILIARIZATION

- A. Prior to implementing any work described in this Section, the Contractor shall become thoroughly familiar with the site, the site conditions, and all portions of the work falling within this Section and the CQA Plan.
- B. Inspection:
 - 1. Prior to implementing any of the work in this Section, the Contractor shall carefully inspect the installed work of all other Sections and verify that all work is complete to the point where the installation of the work specified in this Section may properly commence without adverse impact.
 - 2. If the Contractor has any concerns regarding the installed work of other Sections, the Owner should be immediately notified in writing within 48 hours of the site inspection. Failure to notify the Owner or continuance with structural fill placement shall be construed as Contractor's acceptance of the related work of all other Sections.

3.02 SITE PREPARATION

- A. The Contractor shall develop access to the construction area in accordance with the requirements of the Drawings and any supplemental Specifications.
- B. The Contractor shall install silt fences immediately down-slope of each area to be disturbed prior to the beginning of work in that area. The Contractor shall maintain the silt fences for the duration of construction. Accumulated sediment behind the silt fences shall be disposed of on-site by the Contractor in a manner approved by the Owner.

- C. All brush, vegetation, rubbish, and other objectionable material shall be removed from the construction area and disposed of in an area designated by the Owner.
- D. All topsoil shall be removed from the construction area and stockpiled.
- E. Stormwater ditches, either permanent or temporary, shall be constructed in accordance with the Drawings. The Contractor shall be responsible for constructing diversion ditches as required to divert potential run-on around the construction area. The construction of temporary ditches not shown on the Drawings shall not be undertaken until the Contractor's plan for constructing the ditches is approved by the Owner.

3.03 EXCAVATION AND STOCKPILING

- A. Excavated materials to be used as structural fill shall be stockpiled in designated areas segregated from soils not suitable for use as fill, clearing debris, or other objectionable materials. Stockpile areas shall be designated by the Owner.
- B. Stockpiles of structural fill shall have side slopes no steeper than 3H:1V (3 horizontal:1 vertical) unless approved otherwise by the Owner. The stockpiles of structural fill shall be graded to drain, sealed by tracking parallel to the slope with a dozer or other means approved by the Owner, and dressed daily during periods when structural fill is taken from the stockpile. The Contractor may cover structural fill stockpiles with plastic sheeting or other material approved by the Owner in order to preserve the moisture content of the structural fill.
- C. Stockpiles that shall remain out of active use for a period greater than seven months shall either be covered as described in Part 3.03.C of this Section or stabilized by seeding and fertilizing in accordance with the requirements given in Section 02930.
- D. Surplus excavated soils shall not be removed from the site or disposed of by the Contractor unless such removal or disposal is approved by the Owner.

3.04 STRUCTURAL FILL

- A. The structural fill used during this construction shall be constructed to the lines and grades shown on the Drawings using the appropriate material.
- B. The structural fill shall meet the requirements of Part 2.01 of this Section.
- C. The structural fill shall be placed in a loose lift that results in a compacted lift thickness of no greater than 12 inches.

- D. The Contractor shall be responsible for installation of suitable material that meets the projects specifications for classification, moisture content and density. The Contractor shall not proceed to the next lift until the current lift has been tested and approved by the CQA representative. The Contractor will be held responsible for proceeding to the next lift without prior approval from the CQA Firm.
- E. If the moisture content of the structural fill is not suitable for proper compaction, the structural fill shall be moisture conditioned and reworked, as appropriate. Wetting shall be accomplished using a water truck and spray nozzle, unless the CQA Consultant approves an alternative method. During wetting or drying, the structural fill shall be regularly disced or otherwise mixed so that uniform moisture conditions are obtained
- F. The Contractor shall not place frozen structural fill, nor shall structural fill be placed on frozen ground.
- G. If the structural fill freezes during construction, the Contractor shall remove the frozen structural fill, scarify the remaining unfrozen fill, and then place and compact new structural fill in accordance with these Specifications and any supplemental Specifications. The frozen structural fill shall not be reused until it has thawed, been disced, and then reworked to an acceptable uniform moisture content.

3.05 SURVEY CONTROL

- A. The Contractor shall survey the location and elevation of the structural fill, access road, drainage ditches, and drainage swales.
- B. The Owner will supply surveying for quality assurance purposes and Record Drawings.

3.06 PROTECTION OF WORK

- A. The Contractor shall use all means necessary to protect all materials and all partially-completed and completed work specified in this Section and prior work of other Sections.
- B. At the end of each day, the Contractor shall verify that the entire work area was left in a state that promotes surface drainage off and away from the area and from finished work. If threatening weather conditions are forecast, compacted surfaces shall be seal-rolled to protect finished work.
- C. In the event of damage to prior work or work completed as specified in this Section, the Contractor shall submit a repair plan to the Owner and CQA Consultant(s). The repair plan shall describe the areas requiring repair, and the Contractor shall make all repairs and replacements necessary to the approval of the Owner and CQA Consultant(s) and at no additional cost to the Owner.

3.07 PUMPING AND DRAINAGE

- A. At all times during construction, the Contractor shall provide and maintain proper equipment and facilities to remove all water entering excavations and keep such excavations dry so as to obtain a satisfactory condition for progress of work.
- B. Drainage shall be disposed of only in an area approved by the Owner. Drainage shall be disposed of in a manner which prevents flow or seepage back into the excavated area.

END OF SECTION

SECTION 02228 SUBGRADE

PART 1 - GENERAL

1.01 DESCRIPTION OF WORK

- A. The Contractor shall furnish all labor, materials, tools, supervision, transportation, and installation equipment necessary for the construction of the subgrade as specified herein, as shown on the Drawings, and in accordance with the Construction Quality Assurance (CQA) Plan.
- B. The Contractor shall be prepared to coordinate the construction of the subgrade with other construction activities and subcontractors at the site.
- C. Notwithstanding the prequalification of any material sources for the subgrade, the Contractor shall be entirely responsible for meeting the requirements of this Section.
- D. The work of this Section shall include, but not necessarily be limited to, the construction of the subgrade component of the compost area.

1.02 RELATED SECTIONS

- A. Section 02200 – Earthwork
- B. Section 02278 – Geotextile and Geogrid

1.03 REFERENCES

- A. *Compost Pad Improvements for the City of Little Rock Landfill, Little Rock, Arkansas.*, dated September 2023, Terracon Consultants, Inc.
- B. Latest version of American Society for Testing and Materials (ASTM) standards:
 - 1. ASTM D 422 Standard Test Method for Particle-Size Analysis of Soils.
 - 2. ASTM D 698 Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³)).
 - 3. ASTM D 1140 Standard Test Method for Amount of Material in Soils Finer than the No. 200 (75-µm) Sieve.
 - 4. ASTM D 1556 Standard Test Method for Density of Soil in Place by the Sand-Cone Method.
 - 5. ASTM D 1557 Test Method for Laboratory Compaction Characteristics of Soil

- Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN-m/m³)).
6. ASTM D 2216 Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil and Rock.
 7. ASTM D 2487 Standard Classification of Soils for Engineering Purposes (Unified Soil Classification System).
 8. ASTM D 6938 Standard Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
 9. ASTM D 2937 Standard Test Method for Density of Soil in Place by the Drive-Cylinder Method.
 10. ASTM D 3017 Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).
 11. ASTM D 4220 Standard Practices for Preserving and Transporting Soil Samples.
 12. ASTM D 4318 Standard Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
 13. ASTM D 5084 Standard Test Method for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible-Wall Permeameter.
 14. ASTM D 5093 Standard Test Method for Field Measurement of Infiltration Rate Using a Double-Ring Infiltrometer with a Sealed-Inner Ring.

1.04 SUBMITTALS

- A. The Contractor shall notify the Owner and CQA Consultant in a minimum of 3 calendar days prior to starting construction of the subgrade. The notice shall state the source of the material to be used, the equipment to be used, the date and time that placement operations shall start, and the name of the person in the field who shall be in charge of the construction of the subgrade.
- B. If work is interrupted for reasons other than inclement weather, the Contractor shall notify the Owner and CQA Consultant immediately and provide a plan and schedule for resumption of the work.

1.05 CONSTRUCTION QUALITY ASSURANCE

- A. The construction of the subgrade shall be monitored by the CQA Consultant as outlined in the project specifications.
- B. The Contractor shall be aware of the activities outlined in the project specifications and shall account for these activities in the construction schedule.

PART 2 - PRODUCT

2.01 MATERIAL FOR SUBGRADE

- A. All laboratory testing to evaluate the suitability or conformance of soil materials for the subgrade shall be carried out in accordance with the test methods indicated in Part 1.04 of this Section.
- B. The subgrade shall consist of relatively homogeneous, natural soils which are substantially free of debris, foreign objects, large rock fragments, roots, and organics. The soils selected shall not be gap-graded or susceptible to piping. Any material which is found by the CQA Consultant to be unsuitable shall be removed from the work area by the Contractor.
- C. Soil testing shall be performed by the CQA Consultant provided by the Owner.

PART 3 - EXECUTION

3.01 FAMILIARIZATION

- A. Prior to implementing any work of this Section, the Contractor shall become thoroughly familiar with the site, the site conditions, and all portions of the work falling within this Section and the project specifications.

3.02 SUBGRADE PLACEMENT

- A. The Contractor shall construct the subgrade to the grades, slopes, and elevations shown on the Drawings and as specified in this Section.
- B. No frozen or partially thawed subgrade material shall be placed, spread or compacted.
- C. No compacted subgrade material shall be placed or spread while the surface on which the material is to be placed is frozen or thawing, during unfavorable weather conditions, or during periods of precipitation.

- D. The subgrade surface shall be made smooth and free from ruts or indentations at the end of every working day when precipitation is forecast and/or at the completion of the compaction operations in that area.
- E. The entire area shall be left in a manner to promote runoff at the end of each day.
- F. The final surface of the subgrade shall be compacted using a smooth drum or pneumatic wheel compactor.
- G. The subgrade material shall be placed in loose lifts which result in a maximum compacted lift thickness of 6 inches.
- H. The subgrade must have sufficient compaction and strength to enable the placement and compaction of the gravel subbase. The subgrade also must be stable to prevent large differential settlement that would be conducive to rutting of the top gravel layer.
- I. The Contractor shall not proceed to the next lift until the current lift has been approved by the Engineer. The Contractor will be notified of approval by the Engineer or CQA Representative. The Contractor will be held responsible for proceeding to the next lift without prior approval from the CQA Firm.

3.03 FIELD QUALITY CONTROL AND TESTING

A. Frequency:

- 1. The frequency of quality control testing is outlined below. The Contractor shall take this testing frequency into account in planning his construction schedule.
 - a. The minimum testing frequencies for material evaluation and construction quality evaluation shall be as presented in the project specifications.
 - b. Sampling locations shall be selected by the CQA Consultant. If necessary, the location of routine in-place moisture content and dry density tests shall be determined using a non-biased sampling plan.
 - c. A special testing frequency shall be used at the discretion of the Owner and/or the CQA Consultant when visual observations of construction performance indicate a potential problem. Additional testing for suspected areas shall be considered when:
 - i. the rollers slip during rolling operation;
 - ii. the lift thickness is greater than specified;

- iii. the subgrade soil is at improper and/or variable moisture content;
 - iv. fewer than the specified number of roller passes are made;
 - v. dirt-clogged rollers are used to compact the material;
 - vi. the rollers do not have optimum ballast; or
 - vii. the degree of compaction is doubtful.
- d. During construction, the frequency of testing may also be increased in the following situations:
- i. adverse weather conditions;
 - ii. breakdown of equipment;
 - iii. at the start and finish of grading;
 - iv. if the material fails to meet specifications; or
 - v. the work area is reduced.

B. Defective Areas:

1. If a defective area is discovered in the subgrade, the CQA Consultant shall immediately determine the extent and nature of the defect. If the defect is indicated by an unsatisfactory test result, the CQA Consultant shall determine the extent of the defective area by additional tests, observations, a review of records, or other means that the CQA Consultant deems appropriate. If the defect is related to adverse site conditions, such as overly wet soils or surface desiccation, the CQA Consultant shall define the limits and nature of the defect.
2. After determining the extent and nature of a defect, the CQA Consultant shall notify the Contractor and schedule appropriate retests when the work deficiency has been corrected.
3. The Contractor shall correct the deficiency to the satisfaction of the CQA Consultant. The cost of corrective actions shall be borne by the Contractor.
4. All retests recommended by the CQA Consultant must verify that the defect has been corrected before any additional work is performed by the Contractor in the area of the deficiency. The CQA Consultant shall also verify that all installation requirements are met and that all submittals are provided.

3.04 SURVEY CONTROL

- A. The contractor shall be responsible for all layout work. Once the subgrade is completed

and CQA verified, the Contractor shall be responsible for surveying the location and elevation of the top of subgrade. Final elevations of the top of subgrade surface shall be 0 to +0.1 ft. compared to the grades shown on the Construction Drawings.

- B. Owner will provide one survey for certification and documentation of subgrade elevations. Any additional surveying will be at the expense of the Contractor.

3.05 PRODUCT PROTECTION

- A. The Contractor shall use all means necessary to protect all prior work, including all materials and completed work specified in this and other Sections.
- B. In the event of damage to prior work or work completed as specified in this section, the Contractor shall immediately make all repairs and replacements necessary to the approval of the Owner and CQA Consultant and at no additional cost to the Owner.

END OF SECTION

SECTION 02278

GEOTEXTILE AND GEOGRID

PART 1 GENERAL

1.01 SUMMARY

- A. Section includes furnishing and installing a geotextile (6 oz nonwoven geotextile) and a geogrid (NX850) as part of the compost area improvement.

1.02 REFERENCES

- A. American Society for Testing and Materials (ASTM):
 1. ASTM D 413, Standard Test Methods for Rubber Property - Adhesion to Flexible Substrate.
 2. ASTM D 7179, Standard Test Method for Determining Geonet Breaking Force.
 3. ASTM D 1505, Standard Test Method for Density of Plastics by the Density Gradient Technique.
 4. ASTM D 1603, Standard Test Method for Carbon Black in Olefin Plastics.
 5. ASTM D 3786, Standard Test Method for Hydraulic Bursting Strength of Knitted Goods and Nonwoven Fabrics - Diaphragm Bursting Strength Tester Method.
 6. ASTM D 4218, Standard Test Method for Determination of Carbon Black Content in Polyethylene Compounds by the Muffle-Furnace Technique.
 7. ASTM D 4354, Standard Practice for Sampling of Geosynthetics for Testing.
 8. ASTM D 4491, Standard Test Methods for Water Permeability of Geotextiles by Permittivity.
 9. ASTM D 4533, Standard Test Method for Trapezoid Tearing Strength of Geotextiles.
 10. ASTM D 4595, Standard Test Method for Tensile Properties of Geotextiles by the Wide-Width Strip Method.
 11. ASTM D 4632, Standard Test Method for Grab Breaking Load and Elongation of Geotextiles.

12. ASTM D 4716, Standard Test Method for Constant Head Hydraulic Transmissivity (In-Plane Flow) of Geotextiles and Geotextile Related Products.
13. ASTM D 4751, Standard Test Method for Determining Apparent Opening Size of a Geotextile.
14. ASTM D 4833, Standard Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products.
15. ASTM D 5199, Standard Test Method for Measuring Nominal Thickness of Geotextiles and Geomembranes.
16. ASTM D 5261, Standard Test Method for Measuring Mass per Unit Area of Geotextiles.

1.03 SUBMITTALS

- A. Submit the following to the CQA Engineer, for review and approval, no later than 14 calendar days prior to scheduled shipment of geotextile and geogrids:
 1. Documentation of manufacturers' qualifications as specified in subsection 1.04.A of this Section.
 2. Manufacturer's quality control program manual or descriptive documentation.
 3. List of material properties and samples of the material.
 4. Manufacturers' certification that the products to be furnished will comply with all product specifications in this section.
 5. Documentation of installers' qualifications, as specified in subsection 1.04.13 of this Section.

- B. Submit the following to the CQA Engineer for review and approval no later than one calendar day prior to shipment of the products:
 1. The manufacturers' quality control certifications, including results of source quality control testing of the products, as specified in subsection 2.01 of this Section, to verify that the materials supplied for the project are in compliance with all product specifications in this Section. The certifications shall be signed by a responsible party employed by the manufacturer, such as the QA/QC Manager, Production Manager, or Technical Services Manager. Certifications shall include lot and roll numbers, and corresponding shipping information.

- C. No geotextile or geogrid shall be deployed until the manufacturer's quality control certifications are submitted to and approved by the CQA Engineer. Should the material be deployed prior to CQA Engineer's approval, it shall be at sole risk of the Installer and Contractor, and if the material does not meet project specifications, it shall be removed from the project at the expense of the Contractor.

1.04 QUALITY ASSURANCE/QUALITY CONTROL

- A. **Manufacturer's Qualifications:** The manufacturers shall be specialists in the manufacture of geotextile and/or geogrid, as applicable. Geotextile and geogrid manufacturers shall have at least five years experience in the manufacture of such material.
- B. **Installer's Qualifications**
 - 1. The Installer shall be an approved contractor for the City of Little Landfil.
 - 2. The Installer shall have at least five years experience in similar construction projects.
- C. **Codes and Standards:** Perform all work in compliance with applicable requirements of governing authorities having jurisdiction.

1.05 DELIVERY, STORAGE AND HANDLING

- A. Store material off of the ground, rolled and covered to protect from ultraviolet light exposure, precipitation or other inundation, mud, dirt, dust, puncture, cutting or any other damaging or deleterious conditions.
- B. Rolls shall be marked or tagged with the following information:
 - 1. Manufacturer's name
 - 2. Product identification
 - 3. Lot number
 - 4. Roll number
 - 5. Roll dimensions
- C. Replace defective or torn material at no cost to the Owner.

PART 2 PRODUCTS

2.01 SOURCE QUALITY CONTROL

- A. The following test methods and frequencies shall be used, at a minimum, by the manufacturer for the quality assurance and control of the geotextiles and geogrids prior to shipment of each product. Sampling and testing frequency shall conform to ASTM D 4354. Every effort shall be made to minimize the number of lots of each geosynthetic for use in the project.

- B. Geotextile Manufacturing QC
 - 1. Geotextile Tests:
 - a. Mass Per Unit Area - ASTM D 5261
 - b. Grab Tensile Strength and Grab Tensile Elongation - ASTM D 4632
 - c. Thickness – ASTM D5199
 - d. Puncture Resistance - ASTM D 6241
 - e. Apparent Opening Size - ASTM D 4751
 - f. Permittivity - ASTM D 4491
 - g. Trapezoid Tear Strength - ASTM D 4533
 - h. Mullin Burst – ASTM D3786

Frequency: Minimum of one test per 100,000 square feet and minimum of one test per lot.

- D. For manufacturer's quality control testing of geotextiles and geogrids, the sample average test results (weaker principal direction for mechanical tests) for a particular property for any individual roll tested within a lot designated as first quality shall meet or exceed the Minimum Average Roll Value indicated in the manufacturer's certification.

2.02 GEOTEXTILE

- A. The geotextile shall be a continuous filament polyester or polypropylene nonwoven needle-punched fabric. The fabric shall be inert to commonly encountered chemicals, biological degradation, hydrocarbons, acids, alkalines and mildew. The fabric shall be resistant to rot, ultraviolet light, insects and rodents.
- B. The polyester or polypropylene filaments shall be formed into a stable network such that the filaments retain their relative position.
- C. Geotextile for compost area improvements shall conform to the following minimum requirements shown on attached Table 02278-1.
- D. Minimum roll width shall be 12.5 feet. The roll length shall be maximized in order to minimize seams.

PART 3 EXECUTION

3.01 FIELD QUALITY CONTROL

- A. The CQA Firm shall ensure that the geotextiles and geogrids are installed according to manufacturer recommendations and the Contract Documents. The CQA Firm shall observe and document the installation activities.

3.02 PREPARATION

Surfaces to receive geotextile and geogrids shall be smooth and free of litter, sharp protrusions, and large stones.

3.03 GEOTEXTILE INSTALLATION

- A. General
 - 1. All geotextiles shall be weighted with sandbags or the equivalent when required. Such sandbags shall be installed during placement and shall remain until replaced with cover material.

B. Installation

1. The geotextile shall be placed where shown on the Drawings and placed in such a manner that placement of overlying material will not excessively stretch or tear the fabric.
2. Overlapped seams shall have a minimum overlap of 6 inches.

C. Seaming

1. Seaming shall be by sewing, adhesives, fusion, leister or other approved bonds. All seams shall be continuously seamed. Spot seaming may only be considered as a measure against wind uplift. Overlaps shall be oriented in the direction of earth filling.
2. Any sewing shall be done using polymeric thread with chemical properties equal to or exceeding those of the geotextile.

3.04 GEOTEXTILE REPAIR

A. Holes or tears in the fabric shall be repaired as follows:

1. Flat Areas (flatter than 10 to 1): A fabric patch shall be spot-seamed in place or leistered with a minimum of 12 inches of overlap beyond the perimeter of the tear or damage in all directions.

END OF SECTION



TABLE 1
Geotextile & Geogrid MQC Testing Specifications

Manufacturer's Quality Control			
Test	Method (1)	Testing Frequency	Min. Requirements
Geotextile			
Mass per Unit Area	ASTM D 5261	1/90,000 sf	<u>>6</u> oz/sq. yd.
Grab Tensile	ASTM D 4632	1/90,000 sf	160 lbs.
Grab Elongation	ASTM D 4632	1/90,000 sf	50%
Trapezoid Tear Strength	ASTM D 4533	1/90,000 sf	60 lbs.
CBR Puncture Strength	ASTM D 6241	1/90,000 sf	410 lbs.
Permittivity, T	ASTM D 4491	1/540,000 sf	1.50 Sec ⁻¹
AOS (largest opening size)	ASTM D 4751	1/540,000 sf	70 Sieve Size
Geogrid			
N/A ²	-	-	-

1. Test to be performed according to the latest test method as approved by the certifying engineer.
2. Geogrid material shall be Tensare Triax NX850 geogrid or Engineer approved equivalent.

CONTRACT DRAWINGS

DRAWINGS FOR THE
COMPOST PAD CONSTRUCTION

CITY OF LITTLE ROCK
YARD WASTE COMPOSTING FACILITY (PERMIT #0031-SCYW)
LITTLE ROCK, ARKANSAS

SEPTEMBER 2023
PROJECT NO. 018-001-35237144

PROFESSIONAL ENGINEER'S CERTIFICATION

"I CERTIFY TO THE BEST OF MY PROFESSIONAL JUDGMENT THAT THIS DRAWING SET PROPERLY ADHERES TO ESTABLISHED, SOUND ENGINEERING PRACTICES. THIS CERTIFICATION IS CONTINGENT ON THE FACT THAT ALL INFORMATION SUPPLIED TO THE SIGNATORY AUTHORITY, UP TO THE DATE OF THIS CERTIFICATION, IS UNQUESTIONABLY ACCURATE AND WAS PROVIDED IN GOOD FAITH."

PREPARED FOR



LITTLE ROCK SOLID WASTE DEPARTMENT
10805 IRONTON CUT-OFF ROAD
LITTLE ROCK, AR 72206
(501) 888-2208

PREPARED BY



25809 I-30 SOUTH
PH. (501) 847-9292


BRYANT, AR 72022
FAX. (501) 847-9210



VICINITY MAP
N.T.S.



SITE LOCATION



MAP PRODUCED BY THE UNITED STATES GEOLOGICAL SURVEY. LITTLE ROCK QUADRANGLE MAP, 2017.
SOURCE DATUM: NAD83, WGS84, UNIVERSAL TRANSVERSE MERCATOR, ZONE 15S, ARKANSAS COORDINATE SYSTEM
1983 NORTH AND SOUTH ZONES, NAVD 1988.

SITE LOCATION MAP
SCALE: N.T.S.

ISSUED FOR REVIEW


INDEX OF DRAWINGS

DRAWING NO.	TITLE
1.	COVER SHEET
2.	INDEX SHEET
3.	SITE LAYOUT
4.	EXISTING CONDITIONS
5.	TOP OF GRAVEL
6.	CONTROL POINTS

TYPICAL ABBREVIATIONS

ADEQ	ARKANSAS DEPARTMENT OF ENVIRONMENTAL QUALITY
CB	CATCH BASIN
DIA	DIAMETER
DWG	DRAWING
ELEV	ELEVATION
EXIST	EXISTING
FT	FEET
HDPE	HIGH DENSITY POLYETHYLENE
HORZ	HORIZONTAL
ID	INSIDE DIAMETER
IN	INCHES
INV	INVERT
MAX	MAXIMUM
MH	MANHOLE
MIN	MINIMUM
MSL	MEAN SEA LEVEL
NOM	NOMINAL
NSPS	NEW SOURCE PERFORMANCE STANDARDS
NTS	NOT TO SCALE
OD	OUTSIDE DIAMETER
ℙ	PROPERTY LINE
SDR	STANDARD DIMENSION RATIO
TYP	TYPICAL
VERT	VERTICAL
NPDES	NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM

SECTION/DETAIL KEY



CONTACT INFORMATION

OWNER:
LITTLE ROCK SOLID WASTE DEPARTMENT
ATTENTION: NATHAN CHARLES, P.E. MANAGER
CIVIL ENGINEERING DIVISION
10805 IRONTON CUT-OFF ROAD
LITTLE ROCK, AR 72206
PHONE: (501) 888-2208

ENGINEER:
TERRACON CONSULTANTS, INC.
ATTENTION: DAVE MCCORMICK P.E. - SR. PROJECT ENGINEER
25809 I-30 SOUTH
BRYANT, ARKANSAS 72022
PHONE: (501) 847-9292
FAX: (501) 847-9210

REGULATORY AUTHORITY:
ARKANSAS DEPARTMENT OF ENVIRONMENTAL QUALITY
SOLID WASTE MANAGEMENT DIVISION
ATTENTION: SOLID WASTE MANAGEMENT DIVISION CHIEF
5301 NORTHSORE DRIVE
NORTH LITTLE ROCK, AR 72118-5317
PHONE: (501) 682-0600
FAX: (501) 682-0611

GENERAL NOTES

- EXISTING CONTOURS SHOWN ON THESE PLANS ARE BASED ON AN AERIAL SURVEY PROVIDED BY TERRACON DATED (01-26-23) BASED ON NAD83 SOUTH ARKANSAS HORIZONTAL DATUM AND NAVD83 VERTICAL DATUM. CARE SHOULD BE TAKEN WHEN INTERPRETING CONTOURS TO VERIFY THE AREAS AND THE TRANSITIONS BETWEEN THEM.
- SLOPES AND GRADES ARE IN UNITS OF FT(H):FT(V), UNLESS OTHERWISE NOTED.
- THE EROSION CONTROL FACILITIES REQUIRED BY THESE PLANS AND SPECIFICATIONS ARE CONSIDERED MINIMUM AND MAY BE IMPROVED AT THE DISCRETION OF THE OWNER TO CONSIDER CURRENT SITE DRAINAGE AND GENERAL CONDITIONS.
- THESE DRAWINGS WERE PREPARED IN ACCORDANCE WITH APPLICABLE STATE (ADEQ) AND FEDERAL (EPA) SOLID WASTE REGULATIONS. THESE REGULATIONS INCLUDE ARKANSAS REGULATION 22 (ADEQ, 1995) AND 40 CFR 258 (EPA SUB-TITLE D, 1991).
- CONTRACTOR SHALL PROTECT EXISTING SITE INFRASTRUCTURE. DAMAGE TO ANY INFRASTRUCTURE BY THE CONTRACTOR WILL BE REPAIRED AT CONTRACTOR EXPENSE.
- BELOW GRADE UTILITY ALIGNMENTS SHOWN ARE APPROXIMATE AND LOCATED BASED ON INFORMATION PROVIDED BY OWNER. THERE MAY BE UTILITIES NOT SHOWN. CONTRACTOR SHALL LOCATE, VERIFY, AND PROTECT IN PLACE BELOW GRADE UTILITIES PRIOR TO EXCAVATION. DAMAGE TO BELOW GRADE UTILITIES WILL BE REPAIRED AT CONTRACTOR EXPENSE.

REV. DATE BY DESCRIPTION



INDEX
COMPOST PAD CONSTRUCTION
CITY OF LITTLE ROCK
LITTLE ROCK LANDFILL
LITTLE ROCK
ARKANSAS



DRAWING 2

DESIGNED BY: TLB
DRAWN BY: TLB
APPVD BY: DCM
SCALE: SEE SCALE
DATE: 9-14-2023
JOB NO. 018-001-35237144
ACAD NO. 002
SHEET NO.: 1 OF 6

ISSUED FOR REVIEW



N

LEGEND:

- - - APPROXIMATE LIMITS OF WORK
- △ SURVEY MONUMENTS
- ⊕ MONITORING WELLS
GROUNDWATER ELEVATION
- HW-6 ⊗ PIEZOMETER

NOTE:
1. AERIAL IMAGE FROM TERRACON DRONE SURVEY 2023

REV.	DATE	BY	DESCRIPTION



SITE LAYOUT
COMPOST PAD CONSTRUCTION
CITY OF LITTLE ROCK
LITTLE ROCK LANDFILL

LITTLE ROCK
ARKANSAS

25609 130 SOUTH
PH. (501) 847-9292

BRYANT, AR 72022
FAX. (501) 847-9210



DRAWING 3

DESIGNED BY:	TLB
DRAWN BY:	TLB
APPVD. BY:	DCM
SCALE:	SEE SCALE
DATE:	9-14-2023
JOB NO.	018-001-35237144
ACAD NO.	003
SHEET NO.:	3 OF 6

ISSUED FOR REVIEW

N:\GEC\ARCHIVE\CAD\01800135237144\PLAN\ANS003 - SITE LAYOUT.DWG

N:\GIS\CAD\DWG\CAD01\8001132374\PLANS\004 - EXISTING CONDITIONS.DWG



- LEGEND:**
- 100 EXISTING GRADE CONTOURS
 - APPROXIMATE LIMITS OF WORK AREA
 - EXISTING PERIMETER DITCH

NOTE:
1. AERIAL IMAGE FROM TERRACON DRONE SURVEY 2023

REV.	DATE	BY	DESCRIPTION




EXISTING CONDITIONS
COMPOST PAD CONSTRUCTION
CITY OF LITTLE ROCK
LITTLE ROCK LANDFILL

ARIZONA
LITTLE ROCK

Terracon
25609 130 SOUTH
PH. (501) 847-9292
BRYANT, AR 72022
FAX. (501) 847-9210

DRAWING 4	
DESIGNED BY:	TLB
DRAWN BY:	TLB
APPVD BY:	DCM
SCALE:	SEE SCALE
DATE:	9-14-2023
JOB NO:	018-001-35237144
ACAD NO:	004
SHEET NO.:	4 OF 6

ISSUED FOR REVIEW



ADD 12" OF GRAVEL TO PERIMETER ROADS

COMPOSTING POND

COMPOST PAD TIE OUT AT ROAD

COMPOST PAD TIE OUT (TYPICAL)

PHASE 3 (3.3 ACRES)

PHASE 1 (3.8 ACRES)

COMPOST PAD SHALL DRAIN INTO EXISTING PERIMETER DITCH

COMPOST FACILITY

COMPOST PAD SYSTEM


COMPOST PAD SHALL DRAIN INTO EXISTING PERIMETER DITCH

PHASE 4 (3.3 ACRES)

PHASE 2 (4.0 ACRES)


COMPOST PAD TIE OUT AT ROAD

COMPOST PAD TIE OUT (TYPICAL)




- LEGEND:**
- 100 — EXISTING GRADE CONTOURS (2-FT CONTOURS)
 - 100 — PROPOSED TOP OF GRAVEL (2-FT CONTOURS)
 - APPROXIMATE LIMITS OF WORK AREA
 - EXISTING PERIMETER DITCH
 - CONSTRUCTION PHASES


NOTE:
1. AERIAL IMAGE FROM TERRACON DRONE SURVEY 2023



COMPOST PAD SYSTEM
DETAIL 1/5
N.T.S.



COMPOST PAD TIE OUT (TYPICAL)
DETAIL 2/5
N.T.S.



COMPOST PAD TIE OUT AT ROAD
DETAIL 3/5
N.T.S.

REV.	DATE	BY	DESCRIPTION



TOP OF GRAVEL
 COMPOST PAD CONSTRUCTION
 CITY OF LITTLE ROCK
 LITTLE ROCK LANDFILL
 LITTLE ROCK
 ARKANSAS

BRYANT, AR 72022
 PH. (501) 847-9292
 FAX. (501) 847-9210


DRAWING 5

DESIGNED BY:	TLB
DRAWN BY:	TLB
APPVD BY:	DCM
SCALE:	SEE SCALE
DATE:	9-14-2023
JOB NO:	018-001-35237144
ACAD NO:	005
SHEET NO.:	5 OF 6

ISSUED FOR REVIEW

N:\GEC\ARCHIVE\CAD\018001\35237144\PLAN\ANS005 - TOP OF GRAVEL.DWG

N:\GE\ARCHIVE\CAD\01\80011382744\PLANS\006-CONTROL POINTS.DWG



- LEGEND:**
- 100 EXISTING GRADE CONTOURS (2-FT CONTOURS)
 - 100 PROPOSED TOP OF GRAVEL (2-FT CONTOURS)
 - APPROXIMATE LIMITS OF WORK AREA
 - CONSTRUCTION PHASES

IN PROCESS

REV.	DATE	BY	DESCRIPTION



CONTROL POINTS
COMPOST PAD CONSTRUCTION
CITY OF LITTLE ROCK
LITTLE ROCK LANDFILL

LITTLE ROCK
ARKANSAS

25009 I-30 SOUTH
PH. (501) 847-9292
BRYANT, AR 72022
FAX. (501) 847-9210

DRAWING 6	
DESIGNED BY:	TLB
DRAWN BY:	TLB
APPVD BY:	DCM
SCALE:	SEE SCALE
DATE:	9-14-2023
JOB NO:	018-001-35237144
ACAD NO:	006
SHEET NO.:	6 OF 6

ISSUED FOR REVIEW



ARKANSAS
ENERGY & ENVIRONMENT