

DEPARTMENT OF POLLUTION CONTROL & ECOLOGY
D.A.P.C.

SUMMARY REPORT RELATIVE TO PERMIT APPLICATION

SUBMITTED BY: Arkansas Cement Corporation

Foreman Production Facilities

CSN: 410001

FIRST SUBMITTAL: Sept 21, 1971 AMENDED: _____

CASE REFERENCES: _____

SCOPE: Total Compliance

SUMMARY: Application being made for three "Precipitair" electrostatic precipitators and supporting equipment. Potential emission rate without control from three kiln stacks (lbs/hr): 648,648,1702; Total 2998 Proposed emission rate (lbs/hr): 6.48, 6.08, 17.02; Total 29.58

Reported Efficiency of ESP's 99%

ESTIMATED COST: \$1,600,000.00 TOTAL PROJECT: \$1,760,000.00

COMMENCEMENT OF INSTALLATION: October 1, 1971

DATE OF COMPLIANCE: GIVEN July 1, 1972 SET _____

REVIEWED BY: TA NEW APPROVED: _____

RECOMMENDATION: Approval

ASSIGNED PERMIT NUMBER: 75-A

COMMISSION MINUTE ORDER NUMBER: 71-2f