


C. C. J. ex  
AR 4220088

ARKANSAS DEPARTMENT OF ENVIRONMENTAL QUALITY  
NOTICE OF INTENT  
INDIVIDUAL TREATMENT FACILITIES  
NPDES GENERAL PERMIT ARG550000



Application Type: New  Renewal  (Permit # ARG55 \_\_\_\_\_)

**I. PERMITTEE/OPERATOR INFORMATION**

Permittee (Legal Name): Anthony Forest Products Company Operator Type:  
Permittee Mailing Address: PO Box 724  State  Partnership  
Permittee City: Strong  Federal  Corporation\*  
Permittee State: AR Zip: 71765  Sole Proprietorship/Private  
Permittee Telephone Number: 870-962-3291 \*State of Incorporation: \_\_\_\_\_  
Permittee Fax Number: 870-962-3320 The legal name of the Permittee must be  
Permittee E-mail Address: smurphy@anthonyforest.com identical to the name listed with the  
Arkansas Secretary of State.

**II. INVOICE MAILING INFORMATION (Home owners are exempt.)**

Invoice Contact Person: Stephen Murphy City: Strong  
Invoice Mailing Company: Anthony Forest Products-Urbana Sawmill State: AR Zip: 71765  
Invoice Mailing Address: P.O. Box 724 Telephone: 870-962-3291

**III. FACILITY INFORMATION**

Facility Name: Anthony Forest Products Company-  
Urbana Sawmill Facility Contact Person: Kelly Olivier  
Facility Address: 1236 Urbana Rd. Telephone Number: 870-962-3291  
Facility County: Union Facility City, State & Zip: Urbana, AR, 71768  
Facility Latitude: 33 Deg 09 Min 34.06Sec Facility Longitude: 92 Deg 26 Min 37.68Sec  
Accuracy: Un Method: Un Datum: Un Scale: Un Description: Un


**IV. DISCHARGE INFORMATION**

Outfall Number: One Flow: 500 gpd (Gallons per Day)  
Stream Segment: 2E Hydrologic Basin Code: 8040202  
Outfall Latitude: 33 Deg 09 Min 34.06Sec Outfall Longitude: 92 Deg 26 Min 37.11Sec  
Accuracy: Un Method: Un Datum: Un Scale: Un Description: Un  
Type of Treatment: Pretreatment Aeration Chlorination  
Receiving Stream: Ouachita River

**V. FACILITY PERMIT INFORMATION**

NPDES Individual Permit Number (If Applicable): AR0047384  
NPDES General Permit Number (If Applicable): ARG  
State Construction Permit Number: \_\_\_\_\_  
NPDES General Construction Stormwater Permit Number (If Applicable): ARR15

WATER DIVISION  
5301 NORTHSHORE DRIVE / NORTH LITTLE ROCK, ARKANSAS 72118  
PHONE 501-682-0623 / FAX 501-682-0880  
www.adeq.state.ar.us



**VI. OTHER INFORMATION:**

Operator Name: Mike O'Connor  
Operator License Number: 010202 License Class: II

Consultant Contact Name: Mike O'Connor  
Consultant Email Address: Michael@ArkansasSeptic.com  
PO Box  
Consultant Address: 992 City: Cabot State: AR Zip: 72023  
Consultant Phone Number: 501-517-7198 Consultant Fax Number: 501-843-2546

Has this treatment system been approved by AHD? Yes  No

**Disclosure Statements:**

Arkansas Code Annotated Section 8-1-106 requires that all applicants for the issuance or transfer of any permit, license, certification or operational authority issued by the Arkansas Department of Environmental Quality (ADEQ) file a disclosure statement with their applications. The filing of a disclosure statement is mandatory. No application can be considered complete without one. You must submit a new disclosure statement even if you have one on file with the Department. The form may be obtained from ADEQ web site at: [http://www.adeq.state.ar.us/disclosure\\_stmt.pdf](http://www.adeq.state.ar.us/disclosure_stmt.pdf).

**VII. CERTIFICATION OF OPERATOR**

SM (Initial) "I certify that, if this facility is a corporation, it is registered with the Secretary of the State of Arkansas."  
SM (Initial) "I certify that the cognizant official designated in this Application is qualified to act as a duly authorized representative under the provisions of 40 CFR 122.22(b). If no cognizant official has been designated, I understand that the Department will accept reports signed only by the Applicant."  
SM (Initial) "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Responsible Official Printed Name: Stephen Murphy Title: General Manager  
Responsible Official Signature: *Stephen Murphy* Date: 9-13-11  
Responsible Official Email: smurphy@anthonyforest.com  
Cognizant Official Printed Name: \_\_\_\_\_ Title: \_\_\_\_\_  
Cognizant Official Signature: \_\_\_\_\_ Telephone: \_\_\_\_\_  
Cognizant Official Email: \_\_\_\_\_

**X. PERMIT REQUIREMENT VERIFICATION**

Please check the following to verify completion of permit requirements.  
Yes No \* If No is answered for any of the questions, then a permit can not be issued!

Submittal of Complete NOI?    
Submittal of Required Permit Fee?   Check Number: \_\_\_\_\_  
Submittal of AHD Form EHP-19?    
Submittal of Site Map?

WATER DIVISION  
5301 NORTHSHORE DRIVE / NORTH LITTLE ROCK, ARKANSAS 72118  
PHONE 501-682-0623 / FAX 501-682-0880  
[www.adeq.state.ar.us](http://www.adeq.state.ar.us)

Submittal of Disclosure Statement?

WATER DIVISION  
5301 NORTSHORE DRIVE / NORTH LITTLE ROCK, ARKANSAS 72118  
PHONE 501-682-0623 / FAX 501-682-0880  
[www.adeg.state.ar.us](http://www.adeg.state.ar.us)

**NOTICE OF INTENT**  
**NPDES GENERAL PERMIT ARG550000**  
**INDIVIDUAL TREATMENT FACILITIES**

The attached form can be used by all persons desiring coverage under NPDES general permit ARG550000 (Individual Treatment Facilities). The form should be completed and submitted to this Department no later than thirty (30) days prior to the date coverage is desired.

All information must be provided. If a question does not apply, place "NA" in that space. Do not leave questions blank.

Be sure to read the Individual Treatment Facilities General Permit, ARG550000. It describes what constitutes coverage under this permit, effluent requirements, discharge limitations, and other standard conditions that are applicable to this permit.

40 CFR 122.22(b) states that all reports required by the permit, or other information requested by the Director, shall be signed by the applicant (or person authorized by the applicant) or by a duly authorized representative of that person. A person is a duly authorized representative only if the authorization is made in writing by the applicant (or person authorized by the applicant); the authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, superintendent, or position of equal responsibility for environmental matters for the company; the written authorization is submitted to the Director. This Notice of Intent must be signed by a person authorized under the provisions of state and federal law, and who should be familiar with the provisions of 40 CFR 122.22 pertaining to signatory authority. Be sure to read the Certification.

If you have any questions concerning the ARG550000 permit information or Notice of Intent, please contact Permits Branch of this Department at (501) 682-0623. For the purpose of this permit a Home Owner is an individual owning a single residence.

**REMEMBER THE FOLLOWING:**

1. The Notice of Intent (NOI) must be complete. Do not leave any question blank; use "NA" if a question is not applicable. Outfall information must be completed; it cannot be blank or "NA".
2. A map showing the location of the discharge points must be attached to the Notice of Intent at the time of submission.
3. Read the Certification.
4. A \$200.00 Check payable to ADEQ (Re: ARG550000). (Home owners are exempt.)
5. A Disclosure form as required by ACA 8-1-106. (Home owners are exempt.)
6. **Written approval from the Arkansas Department of Health (ADH) (EHP-19Form) must be submitted with the NOI.**
7. Please call the following number if you have any questions on this Form:

<u>Topic</u>	<u>Contact person</u>	<u>Phone Number</u>
Area Map and USGS Hydrologic Unit Code	Department of the Interior United States Geological Survey	(501)296-1877
Domestic Drinking Water Supply Intake	Department of Health	(501)661-2623
General Information	Permits Branch	(501)682-0623

**INSTRUCTIONS**

**I. How to Determine Latitude and Longitude:**

WATER DIVISION  
5301 NORTHSORE DRIVE / NORTH LITTLE ROCK, ARKANSAS 72118  
PHONE 501-682-0623 / FAX 501-682-0880  
www.adeq.state.ar.us

If a physical address is known go to [www.terraserver-usa.com](http://www.terraserver-usa.com) and proceed with the following steps:

1. Select Advanced Find
2. Select Address
3. Input address
4. Click on Aerial Photo
5. Click on the Info link at the top of the page
6. Note the Latitude and Longitude are in Decimal Coordinates.
7. Go to [www.geology.enr.state.nc.us/gis/latlon.html](http://www.geology.enr.state.nc.us/gis/latlon.html) to convert coordinates to Degrees, Minutes, and Seconds.

NOTE: If a physical address does not exist you may find the coordinates in the Legal Description of the property.

II. How to Determine the Accuracy, Method, Datum, Scale, and Description for the Facility/Outfall Latitude and Longitude:

**Horizontal Accuracy Measure** – This indicates the accuracy, in meters, of the latitude/longitude location, or how close the specific latitude/longitude location is guaranteed to be to the real-world location. It is typically a function of the method used to obtain the latitude/longitude.

**Horizontal Collection Method** - The text that describes the method used to determine the latitude and longitude coordinates for a point on the earth.

Address Matching-House Number	Public Land Survey-Quarter Section
Address Matching-Block Face	Public Land Survey-Section
Address Matching-Street Centerline	Classical Surveying Techniques
Address Matching-Nearest Intersection	Zip Code-Centroid
Address Matching-Digitized	Unknown
Address Matching-Other	GPS-Unspecified
Census Block-1990-Centroid	GPS with Canadian Active Control System
Census Block/Group-1990-Centroid	Interpolation-Digital Map Source (TIGER)
Census Block/Tract-1990-Centroid	Interpolation-SPOT
Census-Other	Interpolation-MSS
GPS Carrier Phase Static Relative Position	Interpolation-TM
GPS Carrier Phase Kinematic Relative Position	Public Land Survey-Eighth Section
GPS Code (Pseudo Range) Differential	Public Land Survey-Sixteenth Section
GPS Code (Pseudo Range) Precise Position	Public Land Survey-Footing
GPS Code (Pseudo Range) Standard Position (SA Off)	Zip+4 Centroid
GPS Code (Pseudo Range) Standard Position (SA On)	Zip+2 Centroid
Interpolation-Map	Loran C
Interpolation-Photo	Interpolation-Other
Interpolation-Satellite	

**Horizontal Reference Datum** - The code that represents the reference datum used in determining latitude and longitude coordinates.

Unknown	WGS84
NAD27	NAD83

**Source Map Scale** - The scale used to determine the latitude and longitude coordinates.

Not Applicable	1:62,500
Unknown	1:63,000
1:15,840	1:63,350
1:20,000	1:63,360
1:24,000 (1" = 2,000')	1:100,000
1:25,000	1:250,000

**Reference Point Description** - The place for which geographic coordinates were established.

Facility/Station Building Entrance or Street Address	Facility Center/Centroid
Boundary Point	Intake Point
Treatment/Storage Point	Release Point
Monitoring Point	Other

**III. How to Determine your Hydrologic Basin Code for the Facility/Outfall:**

1. Locate the county of your facility on the map on Page 4.
2. Find the numbered segment overlaying the county. For example 2C overlays most of Saline County.
3. Find the Eight Digit Hydrologic Basin Code located inside the numbered segment.

**IV. How to Determine your Stream Segment for the Facility/Outfall:**

1. Locate the county of your facility on the map on Page 4.
2. Find the numbered Stream Segment overlaying the county. For example 2C overlays most of Saline County. 2C would be the Stream Segment for any facility located within that segment.

**V. How to Determine your Ultimate Receiving Waters:**

1. Locate the county of your facility on the map on Page 4.
2. Find the numbered segment overlaying the county. For example 2C overlays most of Saline County.
3. Match the number from the segment to one of the numbered Ultimate Receiving Waters. For example: A facility located in Western Saline County is in segment 2C. The "2" determines that the Ultimate Receiving Water for the project is the Ouachita River.

**VI. Signatory Requirements:** The information contained in this form must be certified by a ***responsible official*** as defined in the "signatory requirements for permit applications" (40 CFR 122.22).


Responsible official is defined as follows:

**Corporation**, a principal officer of at least the level of vice president, treasurer

**Partnership**, a general partner

**Sole proprietorship**: the proprietor/owner

**Municipal, state, federal, or other public facility**: principal executive officer, or ranking elected official



**Ultimate Receiving Waters**

1. Red River
2. Ouachita River
3. Arkansas River
4. White River
5. St. Francis River
6. Mississippi River

WATER DIVISION  
 5301 NORTHSORE DRIVE / NORTH LITTLE ROCK, ARKANSAS 72118  
 PHONE 501-682-0623 / FAX 501-682-0880  
[www.adeg.state.ar.us](http://www.adeg.state.ar.us)

# DISCLOSURE STATEMENT

Arkansas Code Annotated Section 8-1-106 requires that all applicants for the issuance, or transfer of any permit, license, certification or operational authority issued by the Arkansas Department of Environmental Quality (ADEQ) file a disclosure statement with their applications. The filing of a disclosure statement is mandatory. No application can be considered complete without one.

Disclosure statement means a written statement by the applicant which contains:

- (A) The full name, business address, and social security number of the applicant and all affiliated persons;
- (B) The full name and business address of any legal entity in which the applicant holds a debt or equity interest of at least five percent (5%) or which is a parent company or subsidiary of the applicant, and a description of the ongoing organizational relationships as they may impact operations within the state;
- (C) A description of the experience and credentials of the applicant, including any past or present permits, licenses, certifications, or operational authorizations relating to environmental regulation;
- (D) A listing and explanation of any civil or criminal legal actions by government agencies involving environmental protection laws or regulations against the applicant and affiliated persons in the ten (10) years immediately preceding the filing of the application, including administrative enforcement actions resulting in the imposition of sanctions, permit or license revocations or denials issued by any state or federal authority, actions that have resulted in a finding or a settlement of a violation, and actions that are pending;
- (E) A listing of any federal environmental agency and any other environmental agency outside this state that has or has had regulatory responsibility over the applicant; and
- (F) Any other information the Director of the Arkansas Department of Environmental Quality may require that relates to the competency, reliability, or responsibility of the applicant and affiliated persons.

The following persons or entities are not required to file a disclosure statement:

- (A)(1) Governmental entities, consisting only of subdivisions or agencies of the federal government, agencies of the state government, counties, municipalities, or duly authorized regional solid waste authorities as defined by § 8-6-707.
- (2) This exemption shall not extend to improvement districts or any other subdivision of government which is not specifically instituted by an act of the General Assembly; and
- (B) Applicants for a general permit to be issued by the department pursuant to its authority to implement the National Pollutant Discharge Elimination System for storm water discharge.
- (C) If the applicant is a publicly held company required to file periodic reports under the Securities and Exchange Act of 1934 or a wholly owned subsidiary of a publicly held company, the applicant shall not be required to submit a disclosure statement, but shall submit the most recent annual and quarterly reports required by the Securities and Exchange Commission which provide information regarding legal proceedings in which the applicant has been involved. The applicant shall submit such other information as the director may require that relates to the competency, reliability, or responsibility of the applicant and affiliated persons.

Deliberate falsification or omission of relevant information from disclosure statements shall be grounds for civil or criminal enforcement action or administrative denial of a permit, license, certification, or operational authorization.



# ARKANSAS DEPARTMENT OF ENVIRONMENTAL QUALITY DISCLOSURE STATEMENT

## Instructions for the Completion of this Document:

- A. Individuals, firms or other legal entities with no changes to an ADEQ Disclosure Statement, complete items 1 through 6 and 19.
- B. Individuals who never submitted an ADEQ Disclosure Statement, complete items 1 through 5, 7, 8, and 17 through 19.
- C. Firms or other legal entities who never submitted an ADEQ Disclosure Statement, complete 1 through 5, and 7 through 19.

**Mail to:**  
**ADEQ**  
**DISCLOSURE STATEMENT**  
*[List Proper Division(s)]*  
 5301 Northshore Drive  
 North Little Rock, AR 72118-5317

**Hand Deliver to:**  
**ADEQ**  
**DISCLOSURE STATEMENT**  
*[List Proper Division (s)]*  
 5301 Northshore Drive  
 North Little Rock, AR 72118-5317

<b>1. APPLICANT: (Full Name)</b> Anthony Forest Products Company	<b>2. SOCIAL SECURITY NUMBER OR TAX I.D. NUMBER:</b> 71-0390470
<b>3. MAILING ADDRESS (Number and Street, P.O.Box Or Rural Route) :</b> 309 North Washington Ave.	
<b>4. CITY, STATE, AND ZIPCODE:</b> El Dorado, AR 71730	

**5. (check all that apply.)**

Individual       Corporate or Other Entity  
 Permit     License     Certification     Operational Authority  
 New Application     Modification     Renewal Application (If no changes from previous disclosure statement, complete number 6 and 19.)  
 Air     Water     Hazardous Waste     Regulated Storage Tank     Mining     Solid Waste  
 Environmental Preservation and Technical Service

**6. Declaration of No Changes:**  
 The violation history, experience and credentials, involvement in current or pending environmental lawsuits, civil and criminal, have not changed since the last Disclosure Statement I filed with ADEQ on N/A

---

Signature of Individual or Authorized Representative of Firm or Legal Entity  
 (Also complete #19.)

*AHE*

**7. Describe the experience and credentials of the Applicant, including the receipt of any past or present permits, licenses, certifications or operational authorization relating to environmental regulation. (Attach additional pages, if necessary.)**

Within the State of AR:

1. Air Operating Permits: 1681-A and 1681-AOP-R0 through R10 (current)
2. Water - NPDES Industrial: AR0047384
3. Water - NPDES Storm Runoff: ARR00B474
4. Regulated Storage Tank: 70001653

Other similar permits within other states.

**8. List and explain all civil or criminal legal actions (except minor traffic violations) by government agencies against the Applicant \* in the last ten years including:**

1. Administrative enforcement actions resulting in the imposition of sanctions;
2. Permit or license revocations or denials issued by any state or federal authority;
3. Actions that have resulted in a finding or a settlement of a violation; and
4. Pending actions.

(Attach additional pages, if necessary.)

CAO Lis No. 09-046 and Lis No. 10-100

\* Firms or other legal entities shall also include this information for all persons and legal entities identified in sections 9-17 of this Disclosure Statement.

*ARR*

9. List all officers of the Applicant. (Add additional pages, if necessary.)

NAME: See attached list TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

10. List all directors of the Applicant. (Add additional pages, if necessary.)

NAME: See attached list TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

11. List all partners of the Applicant. (Add additional pages, if necessary.)

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_  
 STREET: \_\_\_\_\_  
 CITY, STATE, ZIP: \_\_\_\_\_

12. List all persons employed by the Applicant in a supervisory capacity or with authority over operations of the facility subject to this application.

NAME: Stephen Murphy TITLE: General Mgr., Lumber Operations SSN: \_\_\_\_\_  
 STREET: P. O. Box 724 (physical address: 1236 Urbana Road, Urbana, AR 71768)  
 CITY, STATE, ZIP: Strong, AR 71765

NAME: Derek Ratchford TITLE: General Mgr., EWP Operations SSN: \_\_\_\_\_  
 STREET: 309 North Washington Ave.  
 CITY, STATE, ZIP: El Dorado, AR 71730

NAME: Johnny Nolan TITLE: Manager SSN: \_\_\_\_\_  
 STREET: P. O. Box 1877 (physical address: 256 Cooper Drive, El Dorado, AR 71730)  
 CITY, STATE, ZIP: El Dorado, AR 71731-1877

*Handwritten initials*

13. List all persons or legal entities, who own or control more than five percent (5%) of the Applicant's debt or equity.

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

14. List all legal entities, in which the Applicant holds a debt or equity interest of more than five percent (5%).

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ EMPLOYER ID #: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ EMPLOYER ID #: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ EMPLOYER ID #: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

15. List any parent company of the Applicant. Describe the parent company's ongoing organizational relationship with the Applicant.

NAME: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

Organizational Relationship:

16. List any subsidiary of the Applicant. Describe the subsidiary's ongoing organizational relationship with the Applicant.

NAME: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

Organizational Relationship:

*Handwritten initials*

17. List any person who is not now in compliance or has a history of noncompliance with the environmental laws or regulations of this state or any other jurisdiction and who through relationship by blood or marriage or through any other relationship could be reasonably expected to significantly influence the Applicant in a manner which could adversely affect the environment.

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_ SSN: \_\_\_\_\_

STREET: \_\_\_\_\_

CITY, STATE, ZIP: \_\_\_\_\_

18. List all federal environmental agencies and any other environmental agencies outside this state that have or have had regulatory responsibility over the Applicant.

- United States Environmental Protection Agency
- Texas Commission on Environmental Quality
- Louisiana Department of Environmental Quality
- Georgia Environmental Protection Division (GA EPD) of the GA Department of Natural Resources

*OH*

19. VERIFICATION AND ACKNOWLEDGEMENT

The Applicant agrees to provide any other information the director of the Arkansas Department of Environmental Quality may require at any time to comply with the provisions of the Disclosure Law and any regulations promulgated thereto. The Applicant further agrees to provide the Arkansas Department of Environmental Quality with any changes, modifications, deletions, additions or amendments to any part of this Disclosure Statement as they occur by filing an amended Disclosure Statement.

DELIBERATE FALSIFICATION OR OMISSION OF RELEVANT INFORMATION FROM DISCLOSURE STATEMENTS SHALL BE GROUNDS FOR CIVIL OR CRIMINAL ENFORCEMENT ACTION OR ADMINISTRATIVE DENIAL OF A PERMIT, LICENSE, CERTIFICATION OR OPERATIONAL AUTHORIZATION.

State of Arkansas

County of Union


I, Aubra Anthony, Jr., swear and affirm that the information contained in this Disclosure Statement is true and correct to the best of my knowledge, information and belief.

APPLICANT SIGNATURE: *Aubra Anthony Jr*

COMPANY TITLE: President and Chief Executive Officer

DATE: 5/19/11

SUBSCRIBED AND SWORN TO BEFORE ME THIS 19<sup>th</sup> DAY OF May 2011.



*Lisa C. Ham*  
NOTARY PUBLIC

MY COMMISSION EXPIRES:  
8/9/16

## ANTHONY FOREST PRODUCTS COMPANY

### Board of Directors:

Beryl Anthony, Jr.  
Chairman of the Board  
4561 SW Parkgate Blvd.  
Palm City, FL 34990

Aubra Anthony, Jr.  
President & CEO  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Russ Anthony  
Executive Vice President  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Lynda Anthony  
Vice President  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Stephen Murphy  
General Manager, Lumber Operations  
Anthony Forest Products Company  
P.O. Box 724  
Strong, AR 71765

Wanda Anthony Ragsdale  
718 Bodenhamer Drive  
El Dorado, AR 71730

Clary Anthony, Jr.  
810 Woodland Lake Drive  
Atlanta, TX 75551

John Anthony, Jr., M.D.  
2511 Wildwood Drive  
Montgomery, AL 36111

Jim Olmedo  
1275 Rock Creek Rd.  
Hot Springs, AR 71913

Michael Johnson  
511 East 15<sup>th</sup> Street  
El Dorado, AR 71730

### Officers:

Aubra Anthony, Jr.  
President & CEO

Russ Anthony  
Executive Vice President

Lynda Anthony  
Vice President, Human Resources, Safety &  
Environment

Steve Barham  
Vice President, Forestry Management &  
& Procurement  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Kerlin Drake  
Vice President, Marketing  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Ronnie Clay  
Vice President, Finance & Treasurer  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Chantle Selman  
Controller & Assistant Treasurer  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Lisa Ham  
Executive Manager & Corporate Secretary  
Anthony Forest Products Company  
309 North Washington (71730)  
P.O. Box 1877  
El Dorado, AR 71731-1877

Arkansas Department of Health and Human Services  
Division of Health, Environmental Health Protection  
4815 West Markham, Little Rock, Arkansas 72205-3867

Receipt Number  
**17361376**

Individual Onsite System Permit Application  
Permit Type  New Installation  
 Alteration/Repair

Fee Schedule for Structures	
Structures 1500 sq feet or less	\$ 30.00
Structures more than 1500 sq ft and up to 2000 sq ft	\$ 45.00
Structures more than 2000 sq ft and up to 3000 sq ft	\$ 90.00
Structure more than 3000 sq ft and up to 4000 sq ft	\$120.00
Structures more than 4000 sq ft	\$150.00
Alteration and Repair	\$ 50.00

**D-1 Treatment Type (check one)**

STD = Standard Septic Tank  ATU = Aerobic Treatment Plant  
 ISF = Intermittent Sand Filter  RSF = Recirculating Sand Filter  
 PMF = Proprietary Media Filter  RGF = Recirculating Gravel Filter  
 OTH = Other (Describe)  HLD = Holding Tank

**Disposal Method (check one)**

STD = Standard Absorption Field  LPD = Low Pressure Distribution  
 SUR = Surface Discharge  HLD = Holding Tank  
 CPF = Capping Fill  SRL = Serial Distribution  
 OTH = Other  DRP = Drip Irrigation

1. Owner's/Applicant's Name **KELLY OLIVIER w/ ANTHONY FOREST PRODUCTS CO. - URBANA OFFICE**

2. Phone Number **870-310-8393 CELL 870-962-3206 OFFICE**

3. Mailing Address **P.O. BOX 724, STRONG, ARKANSAS 71765**

4. County **UNION COUNTY**

5. Address of Proposed System (If a 91.1 address is not available, attach detailed directions or map.)  
**1236 URBANA ROAD, STRONG, ARKANSAS 71765**

6. Subdivision Name **N/A**

7. Approval Date **N/A**

8. Date Recorded **N/A**

9. Lot Number **N/A**

10. Lot Dimensions **SEE ATTACHED DRAWING**

11. Total Area (Acres) **54 AC.**

12. No. of Bedrooms or No. of Persons (Commercial) **20 EMPLOYEES @ 15 GAL/DAY**

13. Est. Daily Flow (GPD) **300 GAL/DAY**

14. Brief Legal Description of Property (Attach a separate sheet of paper if necessary.)  
**NE 1/4 OF THE NE 1/4 OF SECTION 16, T. 18 S, R 13 W, UNION COUNTY, AR**

15. Water Supply (Specify supplier if Public Water.)  
**STRONG WATER ASSOC.**

16. GPS Coordinates **33° 09' 34.06" N 92° 26' 37.68" W**

17. Soil Determination (Primary Area) Indicate the depth to items a-f if observed in the soil (designate inches).

a. Bedrock	b. BSWT	c. MSWT	d. LSWT	e. Adj. MSWT	f. Adj. LSWT	g. H.C./Depth	h. Loading Rate (GPD/ft <sup>2</sup> )

18. Soil Determination (Secondary Area) Indicate the depth to items a-f if observed in the soil (designate inches).

a. Bedrock	b. BSWT	c. MSWT	d. LSWT	e. Adj. MSWT	f. Adj. LSWT	g. H.C./Depth	h. Loading Rate (GPD/ft <sup>2</sup> )

19. Percolation Test (min/in) - non-soil certified DRs

Rate for Hole 1	<b>UNSATURABLE</b>
Rate for Hole 2	
Rate for Hole 3	
Average Perc. (1-3)	

20. System Size

a. Size of Septic Tank	gal	f. Trench Depth	inches
b. Size of Dose Tank	gal	g. Trench Spacing	feet
c. Absorption Area	ft <sup>2</sup>	h. Media	
d. Number of Field Lines			
e. Length of Field Lines	ft.		

Comments **UNSATURABLE FOR SOIL ABSORPTION TRENCHES. A "NORWECO" MODEL 960-900 GPD TREATMENT PLANT HAS BEEN DESIGNED FOR THIS RESIDENCE. (SEE ATTACHED PLANS AND SPEC.)**

21. I certify that I have conducted the above tests and that the above listed information is in accordance with the latest requirements of the Arkansas Division of Health Rules and Regulations Pertaining to Onsite Wastewater Systems, Designated Representatives and Installers.

**Eddie Sullivan** Signature  
**EDDIE SULLIVAN** Typed Name

**DESIGNATED REP.** Title  
**7-19-11** Date

**173** D.R. Number  
**870-836-4565 MOM**  
**870-833-2001 CELL** Phone Number

22. Approval of Health Authority: The information above has been reviewed and found to meet the requirements of the Division of Health for onsite wastewater systems.

The Division has visited the site, examined the soils and made an interpretation of the soil properties.

A PERMIT FOR CONSTRUCTION is hereby issued.

Environmental Health Specialist **[Signature]** Date **8/23/11**

EHP-19 (R 3/07)

cont. on Mt. Pearl ...



Arkansas Department of Health and Human Services  
 Division of Health, Environmental Health Protection  
 4815 West Markham, Little Rock, Arkansas 72205-3867

Receipt Number

Fee Schedule for Structures

Structures 1500 sq feet or less	\$ 30.00
Structures more than 1500 sq ft and up to 2000 sq ft	\$ 45.00
Structures more than 2000 sq ft and up to 3000 sq ft	\$ 90.00
Structure more than 3000 sq ft and up to 4000 sq ft	\$120.00
Structures more than 4000 sq ft	\$150.00
Alteration and Repair	\$ 50.00

Individual Onsite System Permit Application

Permit Type

New Installation

Alteration/Repair

Part 1 Treatment Type (check one)

- STD = Standard Septic Tank
- ISF = Intermittent Sand Filter
- PMF = Proprietary Media Filter
- OTH = Other (Describe)
- ATU = Aerobic Treatment Plant
- RSF = Recirculating Sand Filter
- RGF = Recirculating Gravel Filter
- HLD = Holding Tank

Disposal Method (check one)

- STD = Standard Absorption Field
- SUR = Surface Discharge
- CPF = Capping Fill
- OTH = Other
- LPD = Low Pressure Distribution
- HLD = Holding Tank
- SRL = Serial Distribution
- DRP = Drip Irrigation

DOANAY CRAWFORD 870-310-9562

1. Owner's/Applicant's Name KELLY OLIVIER w/ ANTHONY FOREST PRODUCTS Co. - URBANA OFFICE

2. Phone Number 870-310-8393 CELL  
870-762-3206 OFFICE

3. Mailing Address P.O. BOX 724, STRONG, ARKANSAS 71765

4. County UNION COUNTY

5. Address of Proposed System (If a 911 address is not available, attach detailed directions or map.)  
1236 URBANA ROAD, STRONG, ARKANSAS 71765

6. Subdivision Name N/A

7. Approval Date N/A

8. Date Recorded N/A

9. Lot Number N/A

10. Lot Dimensions SEE ATTACHED DRAWING

11. Total Area (Acres) 54 AC.

12. No. of Bedrooms or No. of Persons (Commercial) 20 EMPLOYEES @ 15 GAL/DAY

13. Est. Daily Flow (GPD) 300 GAL/DAY

14. Brief Legal Description of Property (Attach a separate sheet of paper if necessary.)  
NE 1/4 OF THE NE 1/4 OF SECTION 16, T 18 S, R 13 W, UNION COUNTY, AR

15. Water Supply (Specify supplier if Public Water.)  
STRONG WATER ASSOC.

16. GPS Coordinates 33° 09' 34.06" N  
92° 26' 37.68" W

17. Soil Determination (Primary Area) Indicate the depth to items a-f if observed in the soil (designate inches)

a. Bedrock	b. BSWT	c. MSWT	d. LSWT	e. Adj. MSWT	f. Adj. LSWT	g. H.C./Depth	h. Loading Rate (GPD/ft <sup>2</sup> )

18. Soil Determination (Secondary Area) Indicate the depth to items a-f if observed in the soil (designate inches)

a. Bedrock	b. BSWT	c. MSWT	d. LSWT	e. Adj. MSWT	f. Adj. LSWT	g. H.C./Depth	h. Loading Rate (GPD/ft <sup>2</sup> )

19. Percolation Test (min/in) - non-soil certified DRs

Rate for Hole 1	<b>UNSUITABLE</b>
Rate for Hole 2	
Rate for Hole 3	
Alt Area Perc	
Average Perc. (1-3)	

20. System Size

a. Size of Septic Tank	gal	f. Trench Depth	inches
b. Size of Dose Tank	gal	g. Trench Spacing	feet
c. Absorption Area	ft <sup>2</sup>	h. Media	
d. Number of Field Lines			
e. Length of Field Lines	ft.		

Comments: UNSUITABLE FOR SOIL ABSORPTION TRENCHES. A "NORWECO" MODEL 960-900 GPD TREATMENT PLANT HAS BEEN DESIGNED FOR THIS RESIDENCE. (SEE ATTACHED PLANS AND SPEC.)

21. I certify that I have conducted the above tests and that the above listed information is in accordance with the latest requirements of the Arkansas Division of Health Rules and Regulations Pertaining to Onsite Wastewater Systems, Designated Representatives and Installers.

Eddie Sullivan  
Signature

DESIGNATED REP.  
Title

173

EDDIE SULLIVAN  
Typed Name

7-19-11  
Date

D.R. Number  
870-836-4565 HOME  
870-833-2001 CELL  
Phone Number

22. Approval of Health Authority: The information above has been reviewed and found to meet the requirements of the Division of Health for onsite wastewater systems.

The Division has visited the site, examined the soils and made an interpretation of the soil properties.

A PERMIT FOR CONSTRUCTION is hereby issued.

Environmental Health Specialist

Date

# Onsite Maintenance Contract

Date 7-18-11  
Homeowner ANTHONY FOREST PRODUCTS Co.  
Property address URBANA OFFICE  
P.O. BOX 724  
STRONG, AR 71765  
Contact number KELLY OLIVIER

Items to be reviewed, at minimum, each 6 months for 2 years. After 2 years, this contract is renewable for a yearly fee.

- > Chlorine residual
- > PH
- > Evaluation of system components, motor, wiring, alarm, etc
- > Document findings, and file necessary paper work with Health Department


This contract does not include the cost of chlorine tablets, replacement ozone bulbs, or any damaged components.

OMP Mike O'Connor  
Clear Flow  
P.O. Box 992  
Cabot, Arkansas 72023

Office phone: 501-843-8202  
Mobile phone: 501-517-7198

Signature

Mike O'Connor




Tank

72" + Risors (deep)  
 5'6" (wide)  
 10' (long)

Hole

7' Deep 81"  
 6' Wide  
 12' Long




<b>NORWECO</b>		DESIGNED BY	JMM
SINGULAR® BIO-KINETIC® WASTEWATER TREATMENT SYSTEM		APPROVED BY	GJS
MODEL 960-500 GPD		DATE	1-9-96
		SCALE	NTS
<small>This drawing is the property of NORWECO. It is to be used only for the project and location specified. It is not to be used for any other project or location without written permission from NORWECO.</small>		WORKSHEET NO.	PC-5-7006


## Constructed Discharge Route

When a discharging sewer system is installed on locations with limited fall along the discharge route, especially where surface contours are irregular and may allow effluent to pond. Or, where the natural drainage doesn't provide the required minimum 200 ft. of distance from property lines, suitable drainage will need to be constructed at the time of the installation by the installer. Such is the case with the installation of this system.

This constructed discharge route must provide constant and uniform elevation drop over the length of the discharge route. Depending on the location, there may not be enough fall over the length of the discharge route to allow cutting into natural ground to form the terrace. In such cases fill must be supplied to form the sides of the trough. A discharge route will start at the systems discharge point and often end near the edge of the property. A constructed discharge route is a shallow V shaped ditch, that where specified on the permit drawing forms the discharge route. It must be constructed in accordance with the drawing shown below.

This configuration is for relatively flat surfaces, or where the discharge route is running more or less with the direction of the ground slope. Where the direction of the discharge route is more or less at right angles to the direction of significant ground slope, the discharge terrace should be shaped somewhat differently. And another drawing with different specifications will be furnished.





TOTAL AC. 1.11 ±


STRUCTURE  
DISCHARGE  
004

PERVIOUS AREA AC. 6.16 ±  
 BLDG. AC. 1.10 ±  
 PAVEMENT AC. 0.05 ±  
 ON SITE TOTAL AC. 7.31 ±  
 OFF SITE AC. 0 ±  
 TOTAL AC. 7.31 ±

OVERLAND  
FLOW  
005

COUNTY ROAD

MEASURE-PHASE RW



VICINITY MAP

**CLEAR FLOW** *A WASTEWATER MANAGEMENT COMPANY*

---

Mike O'Connor  
P.O. Box 992  
Cabot, AR 72023

Michael@ArkansasSeptic.com  
Office 501-517-7198  
Fax 501-843-2546

September 22, 2011

Adeq  
Water Div.

To whom it may concern;

The treatment plant proposed for Anthony Forrest Products will use the Norweco model 960 as submitted  
By Strider Consulting Feb 25, 2010.

Sincerely,  
Clear Flow



Mike O'Connor  
DR # 60-37



# ARG550000 Checklist

ARG55 0398      New       Renewal       Modification

Business       Individual Homeowner

Discharges to Woodard Creek → North Lapile Creek → Lapile Creek

Ecologically Sensitive Waterbody:      Yes       No       → Ouachita River

303(d) list? Pathogens       Nutrients       DO

None       Other  \_\_\_\_\_

Name of Operator: Mike O'Connor      License Number 010202

Class of municipal wastewater operator:      I       II       III       IV

ADH Approval (EHP-19 Form):      Yes       No

Approved System:

	Company Name	System Name	Design Flow (gpd)
<input type="checkbox"/>	Orenco Systems, Inc.	Advantex AX20	500
<input type="checkbox"/>	Ecological Tank, Inc.	AquaSafe 500	500
<input checked="" type="checkbox"/>	Norweco, Inc.	Norweco (Singular) 960	500
<input type="checkbox"/>	Norweco, Inc.	Norweco (Singular) TNT-500	500
<input type="checkbox"/>	Clearstream Wastewater Systems, Inc.	Clearstream 500N+1100 Effluent Filter or a post aeration tank	500
<input type="checkbox"/>	Consolidated Treatment Systems, Inc.	MultiFlo FTB-0.5	500
<input type="checkbox"/>	EnviroGuard	ENV-0.75	750
<input type="checkbox"/>	Consolidated Treatment Systems, Inc.	Nyadic M6-A	500
<input type="checkbox"/>	Bio-Microbics, Inc.	MicroFast ® 0.5/With UV Disinfection and Post Aeration	500

Additional Treatment: \_\_\_\_\_

Other Comments: \_\_\_\_\_


\_\_\_\_\_

***norweco***<sup>®</sup>

**SINGULAIR<sup>®</sup> BIO-KINETIC<sup>®</sup>**  
**WASTEWATER TREATMENT SYSTEM**  
**MODEL 960**

**GENERAL SPECIFICATIONS**

The contractor shall furnish and install one complete Singulair Bio-Kinetic wastewater treatment system with all necessary parts and equipment as described in the following specifications. Treatment of the domestic wastewater shall be accomplished by the extended aeration process with non-mechanical flow equalization, pretreatment of the influent and filtration of the final effluent. The treatment system shall provide primary, secondary and tertiary treatment of the wastewater flow, and if required, chlorination and dechlorination of the effluent prior to discharge. All treatment processes shall be contained within reinforced precast concrete tankage meeting the requirements of ACI Standard 318. The wastewater treatment system shall be a Singulair Model 960 as manufactured by Norweco, Inc., Norwalk, Ohio, USA. Systems utilizing fiberglass, steel, or plastic tankage are subject to flotation when dewatered and shall not be considered for this application.



The wastewater treatment system shall include precast concrete tankage providing separate pretreatment, aeration and final clarification chambers. The tankage shall be furnished with cast-in-place inlets, submerged transfer ports, aerator mounting casting with removable cover, cast-in-place molded plastic vent assembly, cast-in-place outlet coupling and Bio-Kinetic system mounting casting with removable cover. Principal items of electro-mechanical equipment supplied with the Singulair system shall be a 1725 RPM mechanical aerator, UL Listed Service Pro electrical control center with MCD technology, Bio-Static sludge return and Bio-Kinetic tertiary treatment device for flow equalization and final filtration of system effluent.

**SPECIFICATIONS**


# SINGULAIR®

## OPERATING CONDITIONS

Total holding capacity of the system shall provide a minimum of 48 hour retention of the daily flow. The pretreatment chamber shall provide at least 18 hour retention, the extended aeration chamber shall provide at least 24 hour retention and the clarification chamber shall provide at least 6 hour retention. The non-mechanical flow equalization device shall increase each individual chamber and total system retention time in direct proportion to loading. Design of the system shall include a compartmented tank and non-mechanical flow equalization device to insure successful treatment performance without upset even when the significant runoff period is six hours. Hydraulic design considerations of the system and flow equalization device shall be such that intermittent peak flow factors as high as four shall not upset hydraulic reliability within the system. Capability of the system to perform as outlined, when built by an approved manufacturer, shall be certified by an independent testing laboratory and approved for use by the local governing regulatory agency.

## PRETREATMENT CHAMBER

The pretreatment chamber shall be an integral part of the wastewater treatment system. All domestic wastewater shall be preconditioned and flow equalized while passing through the pretreatment chamber prior to being introduced to the extended aeration chamber. The outlet of the pretreatment chamber shall be equipped with a discharge tee that extends vertically into the liquid so that only the preconditioned equalized flow from the center area of the chamber is displaced to the extended aeration chamber. The discharge tee and transfer port shall be of adequate size to handle a peak flow factor of four without restricting the outlet and disturbing hydraulic displacement to the extended aeration chamber. A removable inspection cover shall be cast into the top of the pretreatment chamber to allow tank and transfer tee inspection. As a safety measure, the uncovered opening shall be small enough to insure that the tank cannot be entered for inspection or service.



## AERATION CHAMBER


The extended aeration chamber shall provide in excess of 24 hour retention of the equalized daily flow. The chamber shall be of sufficient size to provide a minimum of 80 cubic feet of tank capacity per pound of applied BOD. The aeration chamber length-width-depth ratio shall be designed to insure uniform tank mixing and provide optimum treatment. The aeration chamber(s) shall be an integral part of the system flow path and constructed of properly reinforced 5,000 PSI, 28 day compression strength precast concrete. All castings used to construct the precast concrete tankage shall be monolithic units with external and internal walls incorporated into each section.

## FINAL CLARIFICATION CHAMBER

The final clarification chamber shall consist of 5 functionally independent zones operating together to provide satisfactory settling and clarification of the equalized flow. An inlet zone shall be provided and shall dissipate transfer turbulence at the flow inlet of the clarification chamber. Its performance shall also eliminate turbulence in other zones of the clarifier. Liquid shall be hydraulically displaced from the inlet zone to the sludge return zone. Hydraulic currents shall sweep settled sludge from the hopped walls and return these solids via the inlet zone to the aeration chamber. As solids are removed, liquid is displaced to the hopper zone of the clarifier. In this zone, settling by gravity takes place. Three of the four sidewalls are slanted to form a hopper which directs all settled material back to the sludge return zone. Clarified liquid from the hopper zone shall be displaced into the final settling zone to provide additional clarification of the liquid. The liquid is finally displaced to the outlet zone for final filtration and discharge from the system. Non-mechanical equalization of the flow, through all 5 independent zones, shall provide optimal settling and clarification.


## BIO-STATIC® SLUDGE RETURN

A Bio-Static sludge return shall be installed into the cast-in-place opening(s) in the aeration/clarification chamber wall to provide positive return of settled solids. Aeration chamber hydraulic currents shall enter the sludge return(s) and be directed into the sludge return zone of the clarification chamber. The Bio-Static sludge return shall accomplish resuspension and return of settled solids without disturbing the clarified liquid in the final settling zone and outlet zone.



## MECHANICAL AERATOR

Each Singulair aerator shall be installed in a concrete aerator mounting casting above the aeration chamber. Fresh air shall be supplied through a molded plastic vent assembly cast into the concrete access cover above the aerator. The Singulair aerator shall include plated mounting brackets, NEMA 6 rated electrical connector, UL recognized fractional horsepower motor, molded




plastic lifting handle, molded plastic air intake screens, molded plastic foam restrictor, stainless steel aspirator shaft and molded glass-filled nylon aspirator tip. The motor shall contain precision manufactured o-ring type seals installed between the motor shell and the machined aluminum endbells to insure watertight integrity is maintained. Molded Viton elastomer shaft seals shall be utilized to protect the bearings from contamination. Only the stainless steel aspirator shaft and glass-filled nylon aspirator tip shall be installed in contact with the liquid. There shall be no submerged electrical motors, bearings or fixed air piping in the aeration system. Singulair aerator motors shall be designed not to exceed the motor nameplate rating when installed and operated as recommended for the system. The fractional horsepower aerator motor shall be equipped with a foam restrictor to protect the motor against high water and foam. The motor shall be 4 pole, 1725 RPM, 115 volt, 60 Hertz, single phase, ball bearing constructed with a 1.0 service factor. It shall draw less than 4.0 amps when operating at the rated nameplate voltage. Aerator motors without UL recognition have not demonstrated compliance with international electrical standards for safety and reliability and shall not be considered for this application.

# BIO-KINETIC®

## SERVICE PRO® ELECTRICAL CONTROL CENTER


The Service Pro electrical control center with MCD technology shall provide Monitoring, Compliance and Diagnostic functions for the Singulair treatment plant using a microprocessor based platform. The Service Pro control center shall contain nonvolatile memory to prevent loss of programming in the event of a power failure. The pre-wired controls shall be mounted in a lockable NEMA rated enclosure designed specifically for outdoor use. Each Service Pro control center shall be a UL Listed assembly and shall include a time clock, alarm light, reset button, power switch, power light, phone light, aerator alarm light and three auxiliary alarm lights. The control center shall monitor all treatment system operating conditions including aerator over current, aerator under current and open motor circuit. In the event the control center detects one of these conditions, power to the aerator shall be interrupted, a diagnostic sequence shall begin and the visual alarm shall activate. After a programmed recovery interval, an automatic restart attempt shall be initiated. If normal aerator operation does not resume during 24 programmed recovery and restart cycles, the audible alarm shall activate and the telemetry system shall report the specific condition to the Service Pro monitoring center. In the event that any of the auxiliary inputs detect abnormal operation of the treatment system auxiliary equipment, the audible and visual alarms shall immediately activate and the telemetry system shall report the alarm condition to the monitoring center. The service provider shall automatically be notified by the Service Pro monitoring center of the specific alarm condition using phone, fax or email.



## TIME CLOCK

The aerator run cycle shall be controlled by an adjustable, pre-wired time clock. The minimum setting shall not permit the aerator to be "off" for more than 30 minutes per hour. It shall be adjustable in 5 minute increments and designed such that any adjustment results in additional run time up to "continuous" operation (60 minutes per hour). Use of a time clock can seriously affect system performance and operating cost. Systems that have not been performance certified at the minimum time clock setting by an independent testing laboratory shall not be considered for this application.

Systems that have not been performance certified at the minimum time clock setting by an independent testing laboratory shall not be considered for this application.




## SERVICE PRO® MONITORING CENTER

The Service Pro monitoring center shall include a 128 bit encrypted password protected website for interface with the monitoring center database. Access to the secure website shall be obtained through a unique user name and password that provides tiered access to data from monitored treatment systems. Access level tiers shall include distributors, service providers, regulatory agencies and individual system owners. Distributors and service providers shall be able to create accounts, maintain service records and grant regulatory agencies access to the information. Individual system owners shall be able to view information regarding their own systems, as well as download instructional information. Integrity of stored data shall be maintained through the use of multiple servers operating in geographically isolated locations.

# SPECIFICATIONS

## BIO-KINETIC® SYSTEM

A Bio-Kinetic system shall be installed in the mounting casting(s) above the clarification chamber. Each Bio-Kinetic system shall provide non-mechanical flow equalization through all plant processes including pretreatment, aeration, clarification, tertiary filtration, chlorination and dechlorination. The assembly shall be supplied with locking lugs and removable moisture/vapor shield and shall consist of a design flow and peak flow micronically molded filter, baffled perimeter settling zone, flow distribution deck, lifting handles, level indicator, adjustment lugs, optional chlorination feed tube, unbaffled perimeter settling zone, solids contact zone, vertical inlet zone, compartmented settling zone consisting of 42 baffled chamber plates, effluent stilling well, final discharge zone, adjustable outlet weir, optional dechlorination feed tube, outlet zone and gasketed discharge flange. All components shall be manufactured from inert synthetic materials or rubber, assembled in circular fashion and connected to a plastic outlet coupling. The outlet coupling shall accept a 4" diameter, Schedule 40, PVC pipe. Each Bio-Kinetic system shall be installed with the inverts of the design flow equalization ports located at the normal liquid level of the clarifier. If intermittent flow rates exceed the capacity of the design flow ports, flow shall be held upstream until the intermittent flow dissipates. If the intermittent flow continues to increase, the liquid level may reach a pair of sustained flow equalization ports. With four ports in use, flow through the system increases while continuing to provide flow equalization to all upstream and downstream processes. Peak flow equalization ports are supplied but should not be required in a properly sized system. Optional Blue Crystal and Bio-Neutralizer tablet feed tubes shall be positioned such that the flow-activated chemical cannot make contact with the liquid upstream of the feed tubes.



## FLOW EQUALIZATION

The wastewater treatment system shall include a non-mechanical, demand use, flow equalization device. The device shall control normal residential flow rates and reduce typical residential flow surges. The flow equalization rate shall be dependent upon the specific loading pattern and the duration of flow surges. At the 600 gallon per day NSF Standard 40 design loading schedule, minimum performance of the device shall equalize daily flow an average of 50%.

## BLUE CRYSTAL® CHLORINATION SYSTEM (Optional)

The Singulair system shall be furnished complete with a tablet feeder and a six month supply of Blue Crystal disinfecting tablets. Blue Crystal tablets shall be specifically formulated for consistent chlorine dosage and effluent disinfection to the sustained, variable and intermittent flows that are typical of domestic wastewater treatment systems. The tablets shall be manufactured from pure calcium hypochlorite and contain a minimum of 70% available chlorine. Each tablet shall be 2<sup>5</sup>/<sub>8</sub>" diameter, compressed to a 1" thickness, weigh approximately 5 ounces and be white in color with blue crystals for easy identification. The tablets shall dissolve in direct proportion to the flow rate, releasing controlled amounts of chlorine.

## BIO-NEUTRALIZER® DECHLORINATION SYSTEM (Optional)

The Singulair system shall be furnished complete with a tablet feeder and a six month supply of Bio-Neutralizer dechlorination tablets. The dechlorination tablets shall contain active ingredients specially formulated to chemically neutralize both free and combined chlorine. Each tablet shall be 2<sup>5</sup>/<sub>8</sub>" diameter, compressed to a 1<sup>3</sup>/<sub>16</sub>" thickness, weigh approximately 5 ounces and be green in color for easy identification. The tablets shall dissolve slowly, releasing controlled amounts of chemical for the instantaneous removal of residual chlorine from the system effluent.

## WARRANTY AND EXCHANGE PROGRAM

The manufacturer shall provide a three year limited warranty for each Singulair aerator, Service Pro control center and Bio-Kinetic system purchased from the manufacturer. A comprehensive exchange program offers Singulair owners a lifetime of equipment protection. The distributor shall provide warranty and exchange program details to the regulatory agency, contractor and customer as required.



## EQUIPMENT MANUFACTURER

The equipment specified herein shall be the product of a manufacturer having a minimum of seven years experience in the construction of prefabricated wastewater treatment equipment and systems. Bids shall be prepared on the basis of the equipment and material specified herein for purposes of determining the low bid. This is not done, however, to eliminate other products or equipment of equal quality and efficiency. If equipment is to be substituted, approval of such substitution must be made prior to execution of any order. It is assumed that substitution will result in a reduction of cost to the contractor and that if accepted, these savings will be passed along by a reduction in the base bid.

## SINGULAIR® MODEL 960 DATA CHART

Designation: Model 960-	500 GPD	750 GPD	1000 GPD	1250 GPD	1500 GPD
Daily Treatment Capacity (Gallons Per Day)	500/600	750/800	1000	1250	1500
Total System Capacity (Gallons)	1300	1600	2300	2850	3400
Number of Singulair Aerators	1	1	2	2	2
Number of Bio-Kinetic Systems	1	2	2	3	3
Number of Bio-Static Sludge Returns	1	1	1	2	2
Drawing Number (PC-5-)	7006	7007	7008	7009	7010

**PROGRESS THROUGH SERVICE SINCE 1906**

***norweco***®


*Engineering the future of water  
and wastewater treatment*

220 REPUBLIC STREET  
NORWALK, OHIO, USA 44857-1156  
TELEPHONE (419) 668-4471  
FAX (419) 663-5440  
www.norweco.com

**DISTRIBUTED LOCALLY BY:**

Norweco®, Norweco.com®, Singulair®, Modulair®, Travalair®, Singulair Green®, Lift-Rail®, Microsonic®, Bio-Dynamic®, Bio-Sanitizer®, Bio-Neutralizer®, Bio-Kinetic®, Bio-Static®, Bio-Gem®, Bio-Max®, Bio-Regeneration®, Bio-Perc®, Blue Crystal®, ClearCheck®, ChemCheck®, Service Pro®, Grease Buster® and "BUSTER" logo® are registered trademarks of Norwalk Wastewater Equipment Company, Inc.

©MMX NORWECO, INC.



- GENERAL NOTES:**
- ① SINGLAIR® AERATOR, AS TESTED AND ACCEPTED BY NSF.
  - ② FALL THROUGH SINGLAIR® PLANT FROM INLET INVERT TO OUTLET INVERT IS FOUR INCHES. INLET INVERT IS TWELVE INCHES BELOW TANK TOP.
  - ③ ON DEEPER INSTALLATIONS, PRECAST RISERS MUST BE USED TO EXTEND AERATOR MOUNTING CASTING AND BIO-KINETIC® SYSTEM MOUNTING CASTING TO GRADE. INSPECTION COVER ON PRETREATMENT CHAMBER MUST BE DEVELOPED TO WITHIN TWELVE INCHES OF GRADE.
  - ④ TANK REINFORCED PER ACI STD. 318-05.
  - ⑤ REMOVABLE COVERS ON RISERS WEIGH IN EXCESS OF SEVENTY-FIVE POUNDS EACH TO PREVENT UNAUTHORIZED ACCESS.
  - ⑥ CONTACT THE LOCAL, LICENSED SINGLAIR® DISTRIBUTOR FOR ELECTRICAL REQUIREMENTS.

**PROJECT ENGINEER'S APPROVAL:**  
 I (WE) HEREBY CERTIFY THAT THIS DRAWING HAS BEEN CHECKED AND IS APPROVED FOR USE IN CONFORMITY WITH THE CONTRACT DOCUMENTS.

DATE: \_\_\_\_\_

NAME: \_\_\_\_\_

**CONTRACTOR'S CERTIFICATION:**  
 I (WE) HEREBY CERTIFY THAT THIS DRAWING HAS BEEN CHECKED AND IS APPROVED FOR USE IN CONFORMITY WITH THE CONTRACT DOCUMENTS.

DATE: \_\_\_\_\_

NAME: \_\_\_\_\_

**CRITICAL DIMENSIONS**

A	1'-0"	N	0'-3"
B	2'-9"	O	0'-6"
C	2'-8"	P	0'-2 1/2"
D	3'-7"	Q	1'-4"
E	2'-3"	R	4'-8"
F	0'-3"	S	6'-0"
G	1'-0"	T	1'-0"
H	5'-0"	U	5'-6"
I	0'-3"	V	
J	0'-3"	W	
K	1'-0"	X	
L	0'-2"	Y	
M	4'-6"	Z	

U.S. AND FOREIGN PATENTS PENDING

**norweco** 1-29-07

SINGLAIR® BIO-KINETIC® WASTEWATER TREATMENT SYSTEM MODEL 900 - 500 GPD

DATE: 1-9-96

SCALE: NTS

PC-5-7008

NOTE: TOTAL SYSTEM CAPACITY: 1,300 GALLONS  
 RATED CAPACITY: 500 GALLONS PER DAY



# WASTEWATER TECHNOLOGY

---

Report on Evaluation of  
Norweco Inc.  
Singular® Model 960  
Wastewater Treatment System

under the provisions of  
NSF Standard 40  
on Individual Aerobic  
Wastewater Treatment Plants



*NSF International*  
3475 Plymouth Road  
PO Box 130140  
Ann Arbor, Michigan 48113-0140 USA

**Report on the Performance Evaluation of the  
Norweco Singulair® Model 960  
Wastewater Treatment System**

**Under the provisions of ANSI/NSF Standard 40  
Relating to Individual Aerobic Wastewater Treatment Plants**

**April 1996**

## EXECUTIVE SUMMARY

Testing of the Singulair® Model 960 Wastewater Treatment System was conducted under the provisions of ANSI/NSF Standard 40 for Individual Aerobic Wastewater Treatment Plants (July 1990 revision). ANSI/NSF Standard 40 was developed by the NSF Joint Committee on Wastewater Technology.

The performance evaluation was conducted at the NSF Wastewater Technology Test Facility in Chelsea, Michigan, using wastewater diverted from the Chelsea municipal wastewater collection system. The evaluation consisted of seven months of testing, during which a seven and a half week stress test was conducted. The evaluation consisted of three weeks of dosing without sampling to allow for plant start-up, sixteen weeks of dosing at design flow, seven weeks of stress test and three weeks of dosing at design flow. Sampling started in the early summer and continued through the fall and into winter, covering a full range of operating temperatures.

Standard 40, in Section H. (3) of Appendix A, provides for exclusion of up to ten percent of the effluent sample days, not to exceed one during stress testing, in completing the pass/fail determination. No sample days were excluded in the pass/fail determination for this evaluation.

Over the course of the evaluation, the average effluent BOD<sub>5</sub> was 6 mg/L, ranging between <5 and 18 mg/L, and the average effluent suspended solids was 10 mg/L, ranging between <5 and 37 mg/L. The effluent pH ranged from 7.7 to 8.2.

The Singulair® Model 960 produced an effluent that successfully met the performance requirements established by ANSI/NSF Standard 40 for Class I effluent:

The maximum arithmetic mean of seven consecutive sample days was 10 mg/L for BOD<sub>5</sub> and 19 mg/L for suspended solids, both well below the allowed maximum of 45 mg/L. The maximum arithmetic mean of 30 consecutive sample days was 8 mg/L for BOD<sub>5</sub> and 13 mg/L for suspended solids, both well below the allowed maximum of 30 mg/L. Average removal rates for 30 consecutive sample days ranged from 95 to 97 percent for BOD<sub>5</sub> and from 94 to 98 percent for suspended solids, consistently above the requirement of 85 percent.

The effluent pH during the entire evaluation ranged between 7.7 and 8.2 within the required range of 6.0 to 9.0. The plant also met the requirements for noise levels (less than 60 dbA at a distance of 20 feet) and color, threshold odor, oily film and foam.

## PREFACE

Performance evaluation of individual aerobic wastewater treatment plants is achieved within the provisions of ANSI/NSF Standard 40: Individual Aerobic Wastewater Treatment Plants (revised July 1990), prepared by the NSF Joint Committee on Wastewater Technology and adopted by the NSF Board of Trustees.

Conformance with the Standard is recognized by issuance of the NSF Mark. This is not to be construed as an approval of the equipment but rather a certification of the data provided by the test and an indication of compliance with the requirements expressed in the Standard.

Plants conforming to Standard 40 are classified as Class I or Class II plants according to the quality of effluent produced by the plant during their performance evaluation. Class I plants must also demonstrate performance consistent with the effluent color, odor, oily film and foam requirements of the Standard. Class I plants must satisfy the requirements of meeting EPA Secondary Treatment Guidelines<sup>1</sup> for five day biochemical oxygen demand, suspended solids and pH.

Permission to use the NSF Mark is granted only after the equipment has been tested and found to perform satisfactorily, and all other requirements of the Standard have been satisfied. Continued use of the Mark is dependent upon evidence of compliance with the Standard and NSF General and Program Specific Policies as determined by periodic reinspection of the equipment at the factory, distributorships and reports from the field.

NSF Standard 40 requires the testing laboratory to provide the manufacturer of an individual aerobic wastewater treatment plant a report including significant data and appropriate commentary relative to the performance evaluation of the plant. NSF policy specifies provision of performance evaluation reports to appropriate state regulatory agencies at publication. Subsequent direct distribution of the report by NSF is made only at the specific request of or by permission of the manufacturer.


The following report contains results of the entire testing program, a description of the plant, its operation and key process control equipment, and a narrative summary of the test program, including test location, procedures and significant occurrences. The plant represented herein reflects the equipment authorized to bear the NSF Mark.

## CERTIFICATION

NSF *International* has determined by performance evaluation under the provisions of ANSI/NSF Standard 40 (revised July 1990) that the Singulair® Model 960 Wastewater Treatment System manufactured by Norweco, Inc., has fulfilled the requirements of ANSI/NSF Standard 40. The Norweco Singulair® Model 960 has therefore been authorized to bear the NSF Mark so long as Norweco continues to meet the requirements of Standard 40 and NSF General and Program Specific Policies.

General performance evaluation and stress tests were performed at the Wastewater Technology Site of NSF *International*, located in Chelsea, Michigan. The raw waste utilized in the test was diverted comminuted municipal waste. The characteristics of the waste are included in the tabulated data of this report.

The observations and analyses included in this report are certified to be correct and true copies of the data secured during the performance tests conducted by NSF on the wastewater treatment plants described herein. The manufacturer has agreed to present the data in this certification in its entirety whenever it is used in advertising, prospectuses, bids or similar uses.



Thomas J. Bruursema  
General Manager  
Wastewater Treatment Unit Certification



Thomas Stevens  
Manager  
Engineering and Research Services

## TABLE OF CONTENTS

	<u>Page</u>
Executive Summary .....	2
Preface .....	3
Certification .....	4
Table of Contents .....	5
1.0 Process Description .....	7
2.0 Performance Evaluation .....	7
2.1 Description of Unit Evaluation .....	7
2.2 Test Protocol .....	8
2.3 Test Chronology .....	9
3.0 Analytical Results .....	10
3.1 Summary .....	10
3.2 Biochemical Oxygen Demand .....	10
3.3 Suspended Solids .....	14
3.4 pH .....	14
3.5 Temperature .....	17
3.6 Dissolved oxygen .....	17
3.7 Color, threshold odor, oily film, foam .....	17
3.8 Noise .....	17
4.0 References .....	17
Appendices	

- Appendix A - Plant Specifications and Drawings
- Appendix B - Standard 40 Performance Evaluation Protocol and Requirements
- Appendix C - Analytical Results

The aerator run cycle is controlled by the use of a time clock. Its design does not permit the aerator to be "off" more than thirty minutes per hour. While the time clock is adjustable, any adjustment automatically results in additional run time. The seven month test was performed at full design load (500 gpd), with the aerator running only thirty minutes per hour.

From the aeration chamber, the wastewater passes by hydraulic displacement into the clarification chamber through a cast-in-place transfer port located at the bottom of the wall between the aeration chamber and the clarification chamber. Initial separation of solids takes place in the clarification chamber. The quiescent design of the clarification chamber allows gravity settling of the solids and sludge. Three of the four side walls in the clarifier are sloped to form a hopper. These 60° sloped walls direct material down to the transfer opening. A stationary sludge return device, located in the clarifier, utilizes hydraulic currents to return settled activated sludge from the bottom of the clarifier back to the aeration chamber.

A Bio-Kinetic® System, connected to an outlet coupling cast into the concrete tank, provides the final treatment stage. The Bio-Kinetic® System is located in the center of the clarification chamber and extends down into the chamber. The outlet coupling allows for installation and service of the System from ground level. The System is made up of three filtration zones, seven settling zones and three pairs of flow equalization ports. Wastewater from the aeration chamber flows up through the clarification chamber to the Bio-Kinetic® System where it passes through the design flow filter mesh that extends around the baffled perimeter settling zone. The design flow filter mesh provides for initial filtration and entrapment of solids. Peak flow filter mesh is located above the design flow mesh. Flow control through the System is provided by two design flow equalization ports and two sustained flow equalization ports. The ports become submerged orifices as the water level in the chamber rises, equalizing the flow rate through the entire plant. Extreme hydraulic flows are handled through a pair of peak flow equalization ports, which act to return the plant to normal operating levels. All flow passing through the flow equalization ports drops to a deck that directs flow through an optional chlorine tablet feeder and vertically downward to the unbaffled perimeter settling zone. From this area, flow is displaced to the contact basin and then onto the baffled chamber plates. A continuous baffle on each of 37 plates acts as a kinetic filtration weir with a 1/16 inch opening provided between plates. A larger open area immediately downstream of the baffle provides for settling and storage of solids. The clarified water then passes to an effluent stilling well, final settling zone, adjustable outlet weir, optional dechlorination tablet feeder and discharge zone.

## 2.2 Test Protocol

The ANSI/NSF Standard 40 Performance Evaluation method and requirements are included in Appendix B. Start up of the plant is accomplished by filling one-third of the volume with raw wastewater and the remainder of the volume with fresh water. The plant is then dosed at the design loading rate (500 gpd) for three weeks. Doses were made during three dosing periods:

- 6 a.m. to 9 a.m. - 35 percent of daily rated capacity
- 11 a.m. to 2 p.m. - 25 percent of daily rated capacity
- 5 p.m. to 8 p.m. - 40 percent of daily rated capacity

After a three week start up period, the plant is subjected to the following loading sequence:

- Design loading - 16 weeks
- Stress loading - 7 weeks
- Design loading - 3 weeks

During the design loading periods, 24-hour composite samples are collected of the influent and effluent five times per week. The samples are analyzed for BOD<sub>5</sub>, suspended solids and volatile suspended solids. On-site determinations of the effluent temperature, pH and dissolved oxygen are also made five times per week. In plant measurements of aeration chamber temperature, pH, dissolved oxygen and suspended solids are also made during the evaluation.

Stress testing is designed to evaluate how the plant performs under non-ideal conditions, including high and low hydraulic loadings and electrical or system failure. The test sequence includes (1) Wash Day stress, (2) Working Parent stress, (3) Power Failure stress, and (4) Vacation stress. Detailed descriptions of the stress sequences are shown in Appendix B.

During the stress test sequences, 24 hour composite samples are collected before and for seven days after each stress dosing pattern. The analyses and on-site determinations completed on the samples are the same as described for the design load testing. Additional samples are collected during the Wash Day and Working Parent stresses for informational purposes only and are not included in the pass/fail calculations. These samples include two samples collected during the Wash Day stress, two during the Working Parent Stress, one sample collected immediately after the power is renewed to the plant during the Power Failure stress and one collected with the start of dosing in the Vacation stress.

In order for the plant to achieve Class I effluent it is required to produce an effluent which meets the EPA guidelines for secondary effluent discharge<sup>1</sup>:

BOD<sub>5</sub> and Suspended Solids: (a) the arithmetic mean of all effluent samples collected in a period of 30 consecutive sample days must be  $\leq 30$  mg/L, with  $\geq 85$  percent removal; and (b) the arithmetic mean of all effluent samples collected in a 7 consecutive sample day period must be  $\leq 45$  mg/L.

pH: Effluent values remain between 6.0 and 9.0.

Requirements are also specified for effluent color, odor, oily film and foam, as well as maximum noise levels allowed from the plant. In determining if the plant meets the effluent requirements, ten percent of the samples during the testing, not to exceed one sample during stress testing, may be excluded from the pass/fail determination. A minimum of 118 sample days, 23 during the stress test sequence, must be collected and analyzed for the test to be valid.

### 2.3 Test Chronology

The system was installed under the direction of the manufacturer on May 17, 1995. Dosing, at the rate of 500 gpd, was started on May 22, 1995. After three weeks of start up, sampling was started on June 12, 1995. The stress test sequence was started on October 2, 1995, and ended on November 22, 1995. The testing was completed on December 18, 1995, although sampling continued through January 9, 1996. No maintenance or mechanical adjustment was performed during the test.



## 3.0 ANALYTICAL RESULTS

### 3.1 Summary

Chemical analysis of samples collected during the evaluation were completed using the procedures in *Standard Methods for the Examination of Water and Wastewater*<sup>3</sup>, or U.S. Environmental Protection Agency procedures<sup>4</sup>. Copies of the data generated during the evaluation are included in Appendix C. The results of the all chemical analyses and on-site observations and measurements made during the evaluation are summarized in Table I.

Guidelines for evaluating the analytical results from the testing are described in Section 5.1 and Section H of Appendix A in ANSI/NSF Standard 40. In completing the pass/fail determination on the data generated from the testing, ten percent (a total of twelve) of the samples collected during testing (not to exceed one sample during stress testing) can be excluded from the pass/fail calculations. Samples collected for informational purposes during the stress test sequence are not included in the pass/fail determinations. During testing of the Norweco Model 960 System, no sample days were excluded from the pass/fail determination.

Section 2.9 and Section E of Appendix A of the Standard define influent wastewater characteristics as they apply to testing under the Standard. Typical domestic wastewater is defined as having a BOD<sub>5</sub> concentration between 100 and 300 mg/L and a suspended solids concentration between 100 and 350 mg/L. By the Program Specific Policies for *Wastewater Treatment Devices and Related Products and Components* (dated January 1, 1991):

When the influent Biochemical Oxygen Demand and/or Suspended Solids fall outside the ranges specified in Section 2.9 of Standard 40, the effluent samples for the two calendar days immediately following the occurrence may be excluded in the 7 and 30 sample averages.

The Policy does not require exclusion of data following a day with influent concentrations outside the defined ranges, but allows for discard should the influent strength have an apparent impact on plant performance. There were eight sample days when the influent strength fell outside the specified range, but none were determined to have an impact on plant performance.

### 3.2 Biochemical oxygen demand

The carbonaceous five day biochemical oxygen demand (BOD<sub>5</sub>) analyses were completed using the EPA Method 405.1. The results of the analyses completed on the samples collected during the testing, except those collected for informational purposes, are shown in Figure 1.

#### *Influent BOD<sub>5</sub>:*

The influent BOD<sub>5</sub> ranged from 120 to 360 mg/L during the evaluation, with an average concentration of 184 mg/L and a median concentration of 180 mg/L.

TABLE I. SUMMARY OF ANALYTICAL RESULTS

	<u>Average</u>	<u>Std. Dev.</u>	<u>Minimum</u>	<u>Maximum</u>	<u>Median</u>	<u>Interquartile Range</u>
<b>BOD<sub>5</sub> (mg/L)</b>						
<i>Influent</i>	184	35	120	360	180	160-200
<i>Effluent</i>	6	2	<5	18	5	<5-7
<b>Suspended Solids (mg/L)</b>						
<i>Influent</i>	238	57	150	450	225	200-270
<i>Aeration Chamber</i>	659	269	250	1,300	605	440-890
<i>Effluent</i>	10	6	<5	37	8	6-14
<b>Volatile Suspended Solids (mg/L)</b>						
<i>Influent</i>	204	47	120	370	200	170-220
<i>Aeration Chamber</i>	532	204	200	990	490	360-700
<i>Effluent</i>	9	4	<5	30	7	5-12
<b>pH</b>						
<i>Influent</i>	-	-	7.4	7.9	7.7	7.5-7.8
<i>Aeration Chamber</i>	-	-	7.4	7.8	7.7	7.6-7.7
<i>Effluent</i>	-	-	7.7	8.2	7.9	7.9-8.0
<b>Temperature (°C)</b>						
<i>Influent</i>	18	2	13	21	19	17-20
<i>Aeration Chamber</i>	19	4	10	23	20	17-22
<i>Effluent</i>	19	4	10	23	20	17-22
<b>Dissolved Oxygen (mg/L)</b>						
<i>Aeration Chamber</i>	5.6	1.5	2.8	9.0	5.4	4.4-6.6
<i>Effluent</i>	2.1	0.8	1.0	4.7	1.9	1.4-2.4

Notes: The median is the point where half of the values are greater and half are less.


The interquartile range is the range of values about the median between the upper and lower 25 percent of all values.

**Effluent BOD<sub>5</sub>:**


The effluent BOD<sub>5</sub> concentrations ranged from <5 to 18 mg/L over the course of the evaluation, with an average concentration of 6 mg/L. The median effluent BOD<sub>5</sub> concentration was 5 mg/L.

Standard 40 requires that over the course of the evaluation, the effluent BOD<sub>5</sub> not exceed 45 mg/L on a 7-day average and 30 mg/L on a 30-day average, and represent a reduction of not less than 85 percent of the 30-day average influent. The averages refer to seven and thirty consecutive sample averages, and not consecutive days. A plot of the 7 and 30-day average concentrations and 30-day average percent removal, is shown in Figure 2.

### Figure 1. Biochemical Oxygen Demand



### Figure 2. Effluent BOD Averages and Percent BOD Removal



The 7-day average for effluent BOD<sub>5</sub> ranged from 5 to 10 mg/L, the 30-day averages ranged from 5 to 8 mg/L and the percent removal ranged from 95 to 97 percent. As shown in Figure 2, the Norweco Model 960 System met the requirements of Standard 40 for effluent BOD<sub>5</sub>.

### 3.3 Suspended solids

Suspended solids and volatile suspended solids analyses were completed using Methods 209C and 209D of *Standard Methods*. The results of the suspended solids analyses over the entire evaluation are shown in Figure 3. The data from both analyses are summarized in Table I.

#### *Influent suspended solids:*

The influent suspended solids ranged from 150 to 450 mg/L during the evaluation, with an average concentration of 238 mg/L. The median influent suspended solids concentration during the evaluation was 225 mg/L. The influent volatile suspended solids ranged from 120 to 370 mg/L during the evaluation, with an average concentration of 204 mg/L and a median concentration of 200 mg/L.

#### *Aeration chamber suspended solids:*

The aeration chamber suspended solids ranged from 250 to 1,300 mg/L during the evaluation, with an average concentration of 659 mg/L. The aeration chamber volatile suspended solids ranged from 200 to 990 mg/L, with an average concentration of 532 mg/L. The median values for the aeration chamber were 605 mg/L suspended solids and 490 mg/L volatile suspended solids.

#### *Effluent suspended solids:*

The effluent suspended solids concentration ranged from <5 to 37 mg/L during the evaluation, with an average concentration of 10 mg/L and a median concentration of 8 mg/L.


Over the course of the evaluation, ANSI/NSF Standard 40 requires that the effluent suspended solids not exceed 45 mg/L on a 7-day average, 30 mg/L on a 30-day average and that the plant achieve not less than 85 percent reduction of the 30-day average influent suspended solids concentration. A plot of the 7-day and 30-day averages, as well as the percent removal, is shown in Figure 4.

The 7-day average suspended solids ranged from 5 to 19 mg/L, the 30-day averages ranged from 6 to 13 mg/L and the percent reduction ranged from 94 to 98 percent. As shown in Figure 4, the Norweco Model 960 System met the requirements of ANSI/NSF Standard 40 for effluent suspended solids.


### 3.4 pH

Over the entire evaluation period, the influent pH ranged from 7.4 to 7.9 (median of 7.7), while the aeration chamber pH ranged from 7.4 to 7.8 (median of 7.7). The effluent pH ranged from 7.7 to 8.2 during the evaluation (median of 7.9), within the 6 to 9 range required by ANSI/NSF Standard 40. The pH data for the evaluation are shown in Appendix C.

### Figure 3. Suspended Solids



### Figure 4. Effluent SS Averages and Percent SS Removal



**PLANT SPECIFICATIONS**  
Norweco Singulair® Model 960

Plant Capacity

Design Flow	500 gpd
Plant Hydraulic Capacity	
Pretreatment Chamber	450 gallons
Aeration Chamber	600 gallons
Settling Chamber	250 gallons
Hydraulic Retention Time (at Design Flow)	
Pretreatment Chamber	21.6 hours*
Aeration Chamber	28.8 hours*
Settling Chamber	12.0 hours*
Total Hydraulic Retention Time	62.4 hours*





\* Note: The flow equalization provided by the Bio-Kinetic® System results in an increased detention time for each chamber. The amount of flow control and exact increase in the detention time is dependent upon the specific daily flow pattern.

**Aerators and Control Centers**

Model 95 Aerator	CSA Listed
Type	Floodproof
Motor	1/6 HP, 1725 RPM, 115V, 60Hz, 1 pH, 3.6 Full Load Amps,
Output	3 CFM
Model 95 Control Center	CSA Listed
Type	115v, 60 Hz, 1 phase with visual alarm and time clock. Run setting adjustable from 30 minutes per hour <u>minimum</u> , to continuous run.
Audible Alarm	Optional
Model 93 Aerator	CSA Listed
Type	Floodproof
Motor	1/6 HP, 3450 RPM, 115V, 60Hz, 1 Ph, 4.2 Full Load Amps,
Output	3 CFM
Model 93 Control Center	CSA Listed
Type	115v, 60 Hz, 1 phase with visual alarm and (optional) time clock. Run setting adjustable from 30 minutes per hour <u>minimum</u> , to continuous run.
Audible Alarm	Optional



This report may not be reproduced in whole or in part  
without the expressed written consent of NSF International.




**GENERAL NOTES**

1. SINGULAIR® AERATOR MODEL 95, OR MODEL 93, AS TESTED AND ACCEPTED BY NSF.
2. FALL THROUGH SINGULAIR® PLANT FROM INLET INVERT TO OUTLET INVERT IS FOUR INCHES. INLET INVERT IS TWELVE INCHES BELOW TANK TOP.
3. ON DEEPER INSTALLATIONS, PRECAST RISERS MUST BE USED TO EXTEND AERATOR MOUNTING CASTING AND BIO-KINETIC SYSTEM MOUNTING CASTING TO GRADE. INSPECTION COVER ON PRETREATMENT CHAMBER MUST BE DEVELOPED TO WITHIN TWELVE INCHES OF GRADE.
4. TANK REINFORCED PER ACI STD. 318-83.
5. REMOVABLE COVERS ON RISERS WEIGH IN EXCESS OF SEVENTY FIVE POUNDS EACH TO PREVENT UNAUTHORIZED ACCESS.
6. CONTACT THE LOCAL LICENSED SINGULAIR® DISTRIBUTOR FOR ELECTRICAL REQUIREMENTS.
7. TOTAL SYSTEM CAPACITY: 1300 GAL.

<p>NORWECO NORWALK WASTEWATER EQUIPMENT COMPANY NORWALK, OHIO</p>	REVISION DATE	1-25-96	REVISION
	DRAWN BY	JMM	APPROVED BY
	DATE	1-9-96	GJS
	SCALE	NTS	
<p>SINGULAIR® BIO-KINETIC® WASTEWATER TREATMENT SYSTEM MODEL 960-500 GPD</p>		DRAWING NO.	PC-5-7006
<p><small>THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.</small></p>			

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.






NOTES:

1. UNDERGROUND POWER SUPPLY MUST BE WIRED INTO APPROVED SINGULAIR® CONTROL CENTER.
2. SINGULAIR® CONTROL CENTER MUST BE WIRED INTO A SEPARATE 10 AMP CIRCUIT BREAKER AT MAIN ELECTRICAL SERVICE PANEL IN THE FACILITY.
3. AERATOR AND AERATOR CONTROL CENTER MUST BE PROPERLY GROUNDED.
4. THE LOCAL LICENSED NORWECO DISTRIBUTOR WILL PLACE THE AERATOR INTO SERVICE WHEN THE FACILITY IS READY TO BE OCCUPIED.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING  
 ©MCMXCVI NORWECO, INC.

	REVISION DATE	REVISION
	1-25-96	
	DRAWN BY	JMM
	APPROVED BY	GJS
	DATE	1-8-95
	SCALE	NTS
MODEL 93 AND MODEL 95 SINGULAIR® AERATOR MOUNTING AND INSTALLATION DETAIL		DRAWING NO.
<small>THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.</small>		PC-5-7600





- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
  2. MATERIAL: STAINLESS STEEL.
  3. REMOVE BURRS; ENSURE NO SHARP EDGES.
  4. TOLERANCES ARE SPECIFIED IN MANUFACTURING PROCEDURE.


U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.

	REVISION DATE	REVISION
	1-25-96	
	DRAWN BY	JMM
	APPROVED BY	GJS
	DATE	1-8-95
	SCALE	NTS
	DRAWING NO.	PC-5-7506

THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.



 NORWALK WASTEWATER EQUIPMENT COMPANY NORWALK, OHIO	REVISION
	DATE 1-25-96
SINGULAIR® MODEL 93 FOAM RESTRICTOR	DRAWN BY JMM
	APPROVED BY GJS
THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.	DATE 1-8-95
	SCALE NTS
DRAWING NO.	PC-5-7508





NOTES:

1. ALL DIMENSIONS ARE IN INCHES.
2. BALANCE 0.010 IN-OZ MAXIMUM.
3. TOLERANCE: ±0.005.
4. COLOR MUST MATCH APPROVED SAMPLE.
5. FACES MUST BE FLAT WITHIN 0.010 T.I.R.
6. BORE AND CIRCUMFERENCE MUST BE CONCENTRIC AND TRACK WITHIN 0.010 T.I.R.
7. MATERIAL: ABS 911.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.

<p><b>NORWECO</b> NORWALK WASTEWATER EQUIPMENT COMPANY NORWALK, OHIO</p> <p>SINGULAIR® MODEL 95 FOAM RESTRICTOR</p>	REVISION
	DATE 1-25-96
	DRAWN BY JMM
	APPROVED BY GJS
	DATE 1-12-96
	SCALE NTS
<small>THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.</small>	
DRAWING NO. P: 5-7595	




NOTES:

1. ALL DIMENSIONS ARE IN INCHES.
2. BREAK CORNERS, REMOVE BURRS, ENSURE NO SHARP EDGES.
3. MATERIAL: 304 STAINLESS STEEL, STRESS RELIEVED AND ROLL STRAIGHTENED.
4. SHAFT TO BE STRAIGHT FULL LENGTH WITHIN 0.0040.
5. ALL DIAMETERS ARE CONCENTRIC WITHIN 0.0005.
6. PLUNGE GRIND UNTHREADED END.
7. WALL THICKNESS: 0.0830.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.


<p>NORWALK WASTEWATER EQUIPMENT COMPANY NORWALK, OHIO</p>		REVISION	REVISION
		DATE 1-25-96	
DRAWN BY JMM		APPROVED BY GJS	
DATE 1-8-95		SCALE NTS	
<p>SINGULAIR® MODEL 93 AND MODEL 95 ASPIRATOR SHAFT</p>		DRAWING NO. PC-5-7507	
<small>THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO</small>			


This report may not be reproduced in whole or in part  
without the expressed written consent of NSF International.




- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
  2. EXTERNAL DIMENSIONS ARE DEPENDENT ON MANUFACTURING PROCESS.
  3. ALL DIMENSIONS ARE INTERIOR.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.


 NORWALK WASTEWATER EQUIPMENT COMPANY NORWALK, OHIO		REVISION DATE	REVISION
		1-23-96	
DRAWN BY		JMM	
APPROVED BY		GJS	
DATE		1-9-96	
SCALE		NTS	
DRAWING NO.		PC-5-8602	
<small>THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.</small>			









CROSS-SECTION THRU HOLES SHOWN AT 45° FROM SECTION A - A SCALE 2X




TOP VIEW



PARTIAL SECTION A-A



SIDE SECTION RECEIVING FLANGE CAST IN TANK




SECTION B - B FLOW DECK PARTIALLY SECTIONED

U.S. AND FOREIGN PATENTS GRANTED AND PENDING  
 ©MCMXCVI NORWECO, INC.

 <b>BIO-KINETIC®</b> ASSEMBLY DRAWING	REVISION	REVISION
	DATE	DATE
	DRAWN BY	JMM
	APPROVED BY	GJS
DATE	1-8-95	SCALE
	NTS	DRAWING NO.
		PC-5-8600

THIS DRAWING IS THE PROPERTY OF NORWECO MASTERTANKER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO



- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
  2. TOLERANCES ARE SPECIFIED IN MANUFACTURING PROCEDURE.
  3. COMPANY AND PRODUCT NAME TO BE MOLDED ON PART.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.

<p><b>NORWECO</b> NORWALK WASTEWATER EQUIPMENT COMPANY</p>	REVISION DATE	REVISION
	1-25-95	
	DRAWN BY	JMM
	APPROVED BY	GJS
SINGULAIR® BIO-KINETIC® SIMPLEX RECEIVING FLANGE		DATE
		1-8-95
		SCALE
		NTS
THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO		DRAWING NO.
		PC-5-8014

**This page intentionally left blank.**

**APPENDIX B**

**NSF STANDARD 40 PERFORMANCE EVALUATION  
METHOD AND REQUIREMENTS**

## TEST METHOD

### A. PURPOSE

The purpose of this test method is to verify that a plant complies with the applicable class effluent requirements during a six-month period.

Performance evaluation of the plant shall be independent of design and construction. However, structural weaknesses or defects and failures of process support equipment, shall be reported in the test results.

### B. PREQUALIFICATIONS

1. **APPLICATION:** The application for performance evaluation of a particular model or model series shall include a basic description, design data, drawings, and parts and materials specifications for the plant and all equipment and appurtenances. A complete installation, operation, and maintenance manual, including a thorough discussion of process fundamentals, shall accompany the application.
2. **MODEL SERIES:** For a series of plants of the same model, varying in rated treatment capacities between 1514 and 5678 L (400 and 1500 gallons) per day, results achieved by the smallest plant in the series shall be indicative of the capabilities of all other plants in the series. The design and configurations of larger capacity plants shall be proportionally identical to the plant tested.<sup>1</sup>

### C. TESTING SEASON

The test can be carried out at any time of the year. If the test is conducted during cold weather, the plant and equipment shall be protected from freezing. If the test is conducted during warm weather, the temperature of the aeration compartment contents shall not exceed 30°C (86°F).

### D. ANALYTICAL METHODS

All sample collection and analytical methods shall be those in the seventeenth edition of Standard Methods for the Examination of Water and Wastewater, published by the American Public Health Association<sup>2</sup>, except as otherwise specified.

### E. INFLUENT WASTEWATER CHARACTERISTICS

The influent wastewater characteristics shall be equivalent to wastewater generated from a normal household complying with the following typical domestic wastewater parameters:

BOD <sub>5</sub>	100-300 mg/L
SS	100-350 mg/L

---

<sup>1</sup>When defining "proportionally identical," some of the parameters that should be considered are hydraulics, dimensions, mixing, and filtration.

<sup>2</sup>American Public Health Association, 1015 Fifteenth St., N.W., Washington, DC 20005.

## F. LOADING REQUIREMENTS

1. DESIGN LOADING: The plant shall be hydraulically loaded at its rated daily capacity<sup>3</sup> according to the following pattern of flow:

6 a.m. - 9 a.m.	35% of total daily flow
11 a.m. - 2 p.m.	25% of total daily flow
5 p.m. - 8 p.m.	40% of total daily flow

2. STRESS TESTING<sup>4</sup>: The plant shall be hydraulically loaded as indicated in the applicable figure in the following sequence:

- Wash Day (Figure A1),
- Working Parents (Figure A2),
- Equipment or Power Failure (electrical equipment off) (Figure A3),
- One week vacation followed by shock loading. Typical of a family's return from vacation (Figure A4).

## G. TEST METHOD

1. GENERAL:

- a. Should mechanical malfunctions at the test facility occur during testing (dosing interruption, comminutor failure, sampler malfunction, etc.) the testing agency shall determine the potential adverse affect on the performance of the system and determine what analytical values shall be included in the thirty- and seven-sample averages.
- b. The plant shall be installed, operated, and maintained according to the manufacturer's instructions during the test period. If these instructions conflict with provisions in this Appendix, the provisions in this Appendix shall be used.

---

<sup>3</sup>Rated daily capacity is the designed treatment of the plant. Note the example below:

### Effect of Testing at Design Loading

Assume average family = 5 persons

and average water use = 189 L/person/day (50 gals/person/day); then daily household waste = 946 Lpd (250 gpd).

Therefore, testing at rated daily capacity provides greater loading to plant than average family might be expected to contribute.

If minimum plant size = 1892 Lpd (500 gpd), then design loading simulates: Use by 10 persons @ 189 L/person/day (50 gals/person/day); or use by 5 persons @ 378 L/person/day (100 gals/person/day), or equal.

<sup>4</sup>Basis for 60% loading used to simulate working parents, equipment/power failure, and return from vacation:

Assume 5-person occupance and 1892 Lpd (500 gpd) design capacity for aerobic system; Then

2 flushes/person @ 95 L/flush (25 gals) = 189 L (50 gals)

1 shower/person @ 76 L/shower (20 gals) = 379 L (100 gals)

3 loads washing @ 132 L/load (35 gals) = 379 L (105 gals)

food preparation and dishes (est.) = 114 L (30 gals)


1079 L (285 gals)

= 60% Design Flow (approximately)

Figure A.1

Wash Day Loading

Added to plants 3 times in one 5-day week with one 24-hour period between each loading



Wash cycle contains low sudsing commercially available household detergent and household bleach at manufacturer's recommended use level

Figure A.2

Working Parents

No loading 9 am to 5 pm for 5 consecutive days




Figure A.3

Equipment or Power Failure  
 All power to plant off for 48 hours, 1 time only





Figure A.4

One Week Vacation  
 No loading over 9-day period but all power on sudden shock when family returns home





## PERFORMANCE REQUIREMENT<sup>6</sup>

- 5.0 EFFLUENT QUALITY: Plants shall be classified according to the effluent quality results obtained under the loading and operating conditions in Appendix A.
- 5.1 CLASS I EFFLUENT: Plants providing a Class I effluent shall be shown to meet EPA Secondary Treatment Guidelines<sup>7</sup> for BOD<sub>5</sub>, SS, and pH. These are as follows:
- 5.1.1 BOD<sub>5</sub> and SS
- Arithmetic mean of all effluent samples collected in a period of 30 consecutive<sup>8</sup> days shall be  $\leq 30$  mg/L and  $\geq 85$  percent removal.
  - Arithmetic mean of all effluent samples collected in a period of 7 consecutive days shall be  $\leq 45$  mg/L.
  - Individual effluent samples shall not exceed a BOD<sub>5</sub> of 60 mg/L and SS of 100 mg/L.
- 5.1.2 pH - Effluent values shall remain between 6.0 and 9.0.
- 5.1.3 Effluent shall be tested three times during the six-month evaluation period for color, odor, oily film, and foam. The effluent shall be diluted 1:1000 with distilled water. Plants tested for Class I effluent characteristics shall not exceed:
- Color - 15 units;
  - Threshold Odor - nonoffensive;
  - Oily Film - nonvisible evidence other than air bubbles;
  - Foam - none.
- 5.2 CLASS II EFFLUENT: Plants providing a Class II effluent shall be shown to meet an effluent quality level for BOD<sub>5</sub> of 60 mg/L and for SS of 100 mg/L. These maximum values shall not be exceeded more than 10 percent of the time.
- 5.3 STRESS REQUIREMENTS: Measured values for BOD<sub>5</sub> and SS of effluent composite samples collected beginning 24 hours after completion of each stressing condition (48 hours after the power outage stress), as described in Appendix A, shall not exceed the applicable class effluent requirements in Item 5.1 and 5.2.
- 5.4 NOISE: Mechanical component parts shall be installed or protected so the noise produced does not exceed 60 dbA when measured 6.0 m (20 feet) from the plant or appurtenances.
- 5.5 MODIFICATION OF TEST METHODS: The manufacturer shall follow the procedures in Appendix C to request a modification of a specific test method. A request for a modification of a test method may be needed due to the following:
- The design of the plant precludes effective testing in accordance with the Standard.
  - The manufacturer submits a design change to a previously tested plant that may not require full performance testing.

---

<sup>6</sup>The performance limits set forth in section 5 take into account limitations of the respective analytical techniques relative to precision and accuracy. The limits shall be rigidly applied in the evaluation of test data in lieu of statistical interpretation.

<sup>7</sup>Federal Register, Vol 49, September 20, 1987, Title 40 Protection of Environment, Chapter 1 - EPA, Subchapter D - Water Programs, Part 133 Secondary Treatment Information, Item 133.102 Secondary Treatment.

<sup>8</sup>For Standard 40 applications, consecutive days shall be interpreted as consecutive sampling days.

**APPENDIX C**

**ANALYTICAL RESULTS**

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: June 11, 1995

Plant Code: 6/139

Weeks Into Test: 1

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	7.5	7.8	7.2	6.8	6.4
	effluent	4.2	4.5	4.7	3.5	3.8
Temperature (°C)	influent	16	16	16	16	17
	aeration chamber	18	18	18	18	18
	effluent	18	18	18	18	18
pH	influent	7.5	7.7	7.5	7.5	7.5
	aeration chamber	7.6	7.6	7.8	7.6	7.6
	effluent	8.1	8.1	8.2	8.0	8.0
Biochemical Oxygen Demand (mg/L)	influent	210	150	200	190	190
	effluent	<5	5	7	6	7
Suspended Solids (mg/L)	influent	210	230	260	240	220
	aeration chamber	250	250	280	280	310
	effluent	7	8	8	6	8
Volatile Suspended Solids (mg/L)	influent	190	200	230	210	190
	aeration chamber	210	200	240	230	250
	effluent	6	7	8	5	6
45 Minute Settleable Solids (mL/L)	aeration chamber	300	430	350	400	360

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: June 18, 1995

Plant Code: 6/139

Weeks Into Test: 2

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	7.8	5.5	7.8	6.4	6.2
	effluent	3.2	2.8	2.7	2.5	2.9
Temperature (°C)	influent	17	17	18	18	18
	aeration chamber	18	19	20	20	20
	effluent	18	20	20	20	20
pH	influent	7.5	7.6	7.5	7.6	7.4
	aeration chamber	7.8	7.8	7.7	7.8	7.7
	effluent	8.1	8.1	8.1	8.0	8.1
Biochemical Oxygen Demand (mg/L)	influent	190	190	250	240	260
	effluent	10	12	9	5	6
Suspended Solids (mg/L)	influent	250	310	340	260	370
	aeration chamber	350	360	370	360	420
	effluent	7	5	6	<5	6
Volatile Suspended Solids (mg/L)	influent	220	260	300	230	320
	aeration chamber	300	300	320	320	360
	effluent	6	<5	<5	<5	<5
45 Minute Settleable Solids (mL/L)	aeration chamber	320	380	380	480	650

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Plant Effluent**

Week Beginning: June 25, 1995

Plant Code: 6/139

Weeks Into Test: 3

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	6.2	5.8	6.6	6.4	6.5
	effluent	2.0	2.1	2.1	2.2	2.0
Temperature (°C)	influent	18	18	18	18	19
	aeration chamber	21	21	21	21	20
	effluent	21	21	21	21	20
pH	influent	7.4	7.5	7.6	7.5	7.5
	aeration chamber	7.7	7.8	7.8	7.7	7.7
	effluent	8.0	7.9	7.9	7.9	8.0
Biochemical Oxygen Demand (mg/L)	influent	210	210	170	120	210
	effluent	<5	<5	<5	<5	<5
Suspended Solids (mg/L)	influent	370	370	270	210	310
	aeration chamber	450	440	410	420	400
	effluent	<5	<5	<5	<5	<5
Volatile Suspended Solids (mg/L)	influent	290	290	210	180	270
	aeration chamber	360	360	350	350	360
	effluent	<5	<5	<5	<5	<5
45 Minute Settleable Solids (mL/L)	aeration chamber	480	550	500	600	700

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Plant Effluent**

Week Beginning: July 2, 1995

Plant Code: 6/139

Weeks Into Test: 4

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	5.9	5.4	5.9	5.2	3.9
	effluent	1.3	1.0	1.3	1.2	1.1
Temperature (°C)	influent	18	18	19	19	19
	aeration chamber	20	20	20	20	20
	effluent	20	20	20	20	20
pH	influent	7.8	7.8	7.8	7.6	7.7
	aeration chamber	7.5	7.7	7.7	7.6	7.6
	effluent	8.0	7.9	7.9	8.0	8.0
Biochemical Oxygen Demand (mg/L)	influent	160	170	170	150	160
	effluent	5	<5	<5	<5	<5
Suspended Solids (mg/L)	influent	160	180	180	180	190
	aeration chamber	460	480	490	460	480
	effluent	6	<5	<5	<5	<5
Volatile Suspended Solids (mg/L)	influent	140	150	150	150	170
	aeration chamber	380	420	430	380	410
	effluent	<5	<5	<5	<5	<5
45 Minute Settleable Solids (mL/L)	aeration chamber	800	950	900	850	1000

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Plant Effluent**

Week Beginning: July 23, 1995

Plant Code: 6/139

Weeks Into Test: 7

Weekend Dosing: Sunday - 269 gallons

Saturday - 125 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		469	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	6.8	6.4	5.9	5.6	5.4
	effluent	(1)	2.3	3.0	2.8	2.4
Temperature (°C)	influent	20	20	20	20	19
	aeration chamber	22	22	22	22	22
	effluent	(1)	22	22	22	22
	influent	7.5	7.6	7.4	7.5	7.5
pH	aeration chamber	7.5	7.6	7.5	7.5	7.6
	effluent	(1)	7.9	7.8	7.8	8.0
Biochemical Oxygen Demand (mg/L)	influent	220	150	150	160	150
	effluent	(1)	5	<5	<5	5
Suspended Solids (mg/L)	influent	180	240	160	190	150
	aeration chamber	(1)	300	280	310	310
	effluent	(1)	15	8	9	9
Volatile Suspended Solids (mg/L)	influent	150	190	140	170	140
	aeration chamber	(1)	260	240	270	260
	effluent	(1)	13	7	8	8
45 Minute Settleable Solids (mL/L)	aeration chamber	160	120	100	125	130

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes: Low dosing on 7/23 and 7/24 caused by problem with float in dosing tank; low doses on 7/30 caused by problem with influent pump. No final effluent sample on 7/25 because of sampler problem.

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Plant Effluent**

Week Beginning: July 30, 1995

Plant Code: 6/139

Weeks Into Test: 8

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	450	500
Dissolved Oxygen (mg/L)	aeration chamber	5.7	5.4	5.7	5.0	5.4
	effluent	2.4	2.1	2.4	2.2	2.1
Temperature (°C)	influent	20	20	20	20	20
	aeration chamber	22	22	22	22	22
	effluent	22	22	22	23	23
	influent	7.7	7.5	7.5	7.5	7.4
pH	aeration chamber	7.7	7.7	7.7	7.6	7.7
	effluent	7.9	7.9	7.8	7.8	7.8
Biochemical Oxygen Demand (mg/L)	influent	190	150	150	150	120
	effluent	5	<5	8	6	6
Suspended Solids (mg/L)	influent	200	230	280	220	150
	aeration chamber	280	320	310	330	300
	effluent	10	23	16	13	11
Volatile Suspended Solids (mg/L)	influent	160	210	210	170	120
	aeration chamber	240	270	250	280	260
	effluent	10	18	14	11	10
45 Minute Settleable Solids (mL/L)	aeration chamber	150	150	210	120	50

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes: Dosing shortage on 8/3 caused by float problem in the Chelsea site dosing system.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: August 6, 1995

Plant Code: 6/139

Weeks Into Test: 9

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	5.0	4.4	4.6	4.8	5.3
	effluent	1.9	1.5	1.6	1.5	1.4
Temperature (°C)	influent	20	20	20	20	20
	aeration chamber	22	22	22	22	22
	effluent	22	22	22	22	22
pH	influent	7.4	7.5	7.6	7.7	7.5
	aeration chamber	7.7	7.7	7.7	7.7	7.6
	effluent	7.9	7.9	7.9	8.0	7.9
Biochemical Oxygen Demand (mg/L)	influent	150	160	190	360	160
	effluent	6	<5	<5	<5	<5
Suspended Solids (mg/L)	influent	150	200	220	280	180
	aeration chamber	430	510	470	510	500
	effluent	6	7	<5	5	<5
Volatile Suspended Solids (mg/L)	influent	130	170	190	240	160
	aeration chamber	360	430	400	340	440
	effluent	<5	7	<5	<5	<5
45 Minute Settleable Solids (mL/L)	aeration chamber	280	500	580	500	600

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes:

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: August 13, 1995

Plant Code: 6/139

Weeks Into Test: 10

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	4.3	3.9	3.7	4.0	3.6
	effluent	1.1	1.0	1.1	1.3	1.3
Temperature (°C)	influent	20	20	20	20	20
	aeration chamber	23	23	23	23	23
	effluent	23	23	23	23	23
pH	influent	7.6	7.5	7.5	7.7	7.7
	aeration chamber	7.7	7.6	7.6	7.7	7.7
	effluent	7.9	7.8	7.9	8.0	7.9
Biochemical Oxygen Demand (mg/L)	influent	210	190	190	190	140
	effluent	<5	<5	6	5	6
Suspended Solids (mg/L)	influent	240	290	260	210	280
	aeration chamber	630	630	610	580	620
	effluent	6	6	6	8	8
Volatile Suspended Solids (mg/L)	influent	210	250	230	180	210
	aeration chamber	520	520	510	490	510
	effluent	5	<5	6	7	7
45 Minute Settleable Solids (mL/L)	aeration chamber	580	460	510	620	500

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes:

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: August 20, 1995

Plant Code: 6/139

Weeks Into Test: 11

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		463	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	4.3	4.3	3.7	4.6	4.1
	effluent	1.3	1.7	1.0	1.0	1.2
Temperature (°C)	influent	20	20	20	20	20
	aeration chamber	23	23	23	23	23
	effluent	23	23	23	23	23
pH	influent	7.7	7.7	7.7	7.6	7.5
	aeration chamber	7.7	7.7	7.7	7.7	7.7
	effluent	7.9	7.9	7.9	7.9	7.8
Biochemical Oxygen Demand (mg/L)	influent	190	190	180	200	200
	effluent	<5	<5	<5	<5	<5
Suspended Solids (mg/L)	influent	290	240	210	270	290
	aeration chamber	620	590	620	660	660
	effluent	7	6	5	7	7
Volatile Suspended Solids (mg/L)	influent	250	210	200	240	250
	aeration chamber	500	480	510	540	540
	effluent	7	<5	<5	6	6
45 Minute Settleable Solids (mL/L)	aeration chamber	800	800	900	790	700

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Dosing shortage on 8/21 due to a problem with the Chelsea site dosing system.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: August 27, 1995

Plant Code: 6/139

Weeks Into Test: 12

Weekend Dosing: Sunday - 263 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	4.5	4.0	4.2	3.3	3.9
	effluent	1.5	1.2	1.1	1.0	1.5
Temperature (°C)	influent	20	21	20	21	20
	aeration chamber	23	23	23	23	23
	effluent	23	23	23	23	23
pH	influent	7.5	7.6	7.7	7.7	7.7
	aeration chamber	7.7	7.7	7.7	7.6	7.7
	effluent	8.0	7.9	7.9	8.0	7.9
Biochemical Oxygen Demand (mg/L)	influent	230	200	200	250	160
	effluent	5	5	5	<5	5
Suspended Solids (mg/L)	influent	440	250	330	450	270
	aeration chamber	720	680	640	760	700
	effluent	9	14	10	8	7
Volatile Suspended Solids (mg/L)	influent	370	200	280	360	200
	aeration chamber	600	540	510	610	540
	effluent	8	10	8	6	6
45 Minute Settleable Solids (mL/L)	aeration chamber	800	560	700	500	780

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Dosing shortage on 8/27 due to a plugged Chelsea site influent pump.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: September 3, 1995

Plant Code: 6/139

Weeks Into Test: 13

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	481	500
Dissolved Oxygen (mg/L)	aeration chamber	4.3	3.6	3.9	3.3	2.8
	effluent	1.1	1.3	1.1	1.0	1.4
Temperature (°C)	influent	19	20	20	21	20
	aeration chamber	23	23	23	23	23
	effluent	23	23	23	23	23
pH	influent	7.7	7.7	7.7	7.6	7.7
	aeration chamber	7.6	7.7	7.6	7.7	7.6
	effluent	7.8	8.0	7.9	8.0	7.8
Biochemical Oxygen Demand (mg/L)	influent	(4)	190	220	250	220
	effluent	(4)	<5	5	7	8
Suspended Solids (mg/L)	influent	(4)	380	320	350	310
	aeration chamber	(4)	810	810	880	900
	effluent	(4)	7	8	13	12
Volatile Suspended Solids (mg/L)	influent	(4)	330	270	310	260
	aeration chamber	(4)	660	640	700	720
	effluent	(4)	6	6	11	12
45 Minute Settleable Solids (mL/L)	aeration chamber	680	600	520	800	700

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: September 10, 1995

Plant Code: 6/139

Weeks Into Test: 14

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	4.2	3.2	4.1	3.4	4.4
	effluent	1.8	1.7	1.6	1.5	1.6
Temperature (°C)	influent	20	20	20	20	20
	aeration chamber	22	22	21	21	21
	effluent	22	21	21	21	21
pH	influent	7.7	7.7	7.7	7.6	7.6
	aeration chamber	7.6	7.6	7.5	7.5	7.5
	effluent	7.9	7.9	7.8	7.9	7.9
Biochemical Oxygen Demand (mg/L)	influent	190	160	160	180	170
	effluent	8	6	7	9	8
Suspended Solids (mg/L)	influent	230	250	210	180	200
	aeration chamber	890	910	920	980	880
	effluent	14	13	16	20	16
Volatile Suspended Solids (mg/L)	influent	190	230	180	160	170
	aeration chamber	700	720	730	770	710
	effluent	12	12	13	16	12
45 Minute Settleable Solids (mL/L)	aeration chamber	490	500	700	500	570

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

TGS/3-92



NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: September 17, 1995

Plant Code: 6/139

Weeks Into Test: 15

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	3.8	4.4	4.4	4.3	5.0
	effluent	1.4	1.7	1.5	1.9	1.5
Temperature (°C)	influent	20	20	20	20	20
	aeration chamber	21	21	21	21	20
	effluent	21	21	21	21	20
pH	influent	7.6	7.6	7.7	7.6	7.7
	aeration chamber	7.6	7.7	7.6	7.8	7.6
	effluent	7.9	7.8	7.9	7.9	7.9
Biochemical Oxygen Demand (mg/L)	influent	210	160	160	140	160
	effluent	6	7	7	5	6
Suspended Solids (mg/L)	influent	240	190	180	200	200
	aeration chamber	1000	1000	1100	1100	1200
	effluent	14	20	14	15	16
Volatile Suspended Solids (mg/L)	influent	240	170	160	170	170
	aeration chamber	800	810	840	840	920
	effluent	10	18	11	12	12
45 Minute Settleable Solids (mL/L)	aeration chamber	540	500	650	620	550

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: September 24, 1995

Plant Code: 6/139

Weeks Into Test: 16

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	4.4	4.6	4.0	5.0	4.4
	effluent	1.4	2.0	1.4	1.4	1.9
Temperature (°C)	influent	19	19	19	19	19
	aeration chamber	19	19	19	19	19
	effluent	19	19	19	19	19
pH	influent	7.7	7.7	7.8	7.7	7.7
	aeration chamber	7.7	7.6	7.6	7.7	7.7
	effluent	8.0	8.0	7.9	7.8	7.9
Biochemical Oxygen Demand (mg/L)	influent	160	160	180	200	210
	effluent	7	6	7	7	9
Suspended Solids (mg/L)	influent	220	250	240	220	200
	aeration chamber	1000	1000	1000	1100	1100
	effluent	20	18	19	18	18
Volatile Suspended Solids (mg/L)	influent	190	220	210	200	180
	aeration chamber	810	830	820	880	880
	effluent	16	16	16	16	14
45 Minute Settleable Solids (mL/L)	aeration chamber	540	450	330	400	590

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Stress Test Evaluation**

Week Beginning: October 1, 1995

Plant Code: 6/139

Weeks Into Test: 17

		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)		431	463	431	463	431	463	506
Dissolved Oxygen (mg/L)	aeration chamber		4.5					
	effluent		1.5					
Temperature (°C)	influent		19					
	aeration chamber		20					
	effluent		19					
pH	influent		7.6					
	aeration chamber		7.7					
	effluent		7.9		8.0		7.9	
Biochemical Oxygen Demand (mg/L)	influent		220		170		150	
	effluent		7		6		8	
Suspended Solids (mg/L)	influent		260		240		260	
	aeration chamber		1100					
	effluent		15		12		18	
Volatile Suspended Solids (mg/L)	influent		220		210		220	
	aeration chamber		840					
	effluent		12		12		12	
45 Minute Settleable Solids (mL/L)	aeration chamber		450					

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Wash day stress 10/2 through 10/6.

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Stress Test Evaluation**

Week Beginning: October 8, 1995

Plant Code: 6/139

Weeks Into Test: 18

		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)		500	500	500	500	500	500	463
Dissolved Oxygen (mg/L)	aeration chamber	5.5	5.0	5.2	4.5	5.0	5.5	5.8
	effluent	2.0	2.2	2.0	2.2	2.2	2.5	2.0
Temperature (°C)	influent	18	19	19	19	19	18	18
	aeration chamber	19	18	18	18	18	19	19
	effluent	18	18	18	18	18	18	18
pH	influent	7.8	7.5	7.5	7.5	7.5	7.6	7.5
	aeration chamber	7.6	7.6	7.5	7.5	7.5	7.5	7.5
	effluent	7.9	7.9	7.8	7.9	7.8	8.0	7.9
Biochemical Oxygen Demand (mg/L)	influent	140	190	200	180	170	150	180
	effluent	<5	<5	<5	<5	<5	<5	<5
Suspended Solids (mg/L)	influent	140	220	220	240	200	180	210
	aeration chamber	820	880	960	980	1000	1100	1100
	effluent	8	10	8	10	11	9	7
Volatile Suspended Solids (mg/L)	influent	120	200	190	210	170	160	190
	aeration chamber	620	680	760	780	810	880	860
	effluent	6	8	8	8	9	8	6
45 Minute Settleable Solids (mL/L)	aeration chamber	520	340	380	400	510	440	450

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Working parent stress started 10/14.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Stress Test Evaluation

Week Beginning: October 15, 1995

Plant Code: 6/139

Weeks into Test: 19

Dosed Volume (gallons)		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dissolved Oxygen (mg/L)	aeration chamber						4.7	4.2
	effluent						1.6	1.2
Temperature (°C)	influent						18	17
	aeration chamber						18	18
	effluent						18	18
pH	influent						7.7	7.9
	aeration chamber						7.6	7.5
	effluent		7.9		8.0		7.9	7.9
Biochemical Oxygen Demand (mg/L)	influent		170		170		160	180
	effluent		<5		5		<5	<5
Suspended Solids (mg/L)	influent		170		230		260	250
	aeration chamber						1100	1200
	effluent		9		12		12	8
Volatile Suspended Solids (mg/L)	influent		180		210		220	210
	aeration chamber						860	900
	effluent		8		10		10	6
45 Minute Settleable Solids (mL/L)	aeration chamber						640	680

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Working parent stress ended 10/18.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Stress Test Evaluation

Week Beginning: October 22, 1995

Plant Code: 6/139

Weeks into Test: 20

Dosed Volume (gallons)		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dissolved Oxygen (mg/L)	aeration chamber	4.4	6.0	4.7	5.1	5.8		
	effluent	1.3	1.5	1.4	1.4	1.5		
Temperature (°C)	influent	17	18	18	18	17		
	aeration chamber	17	17	17	17	17		
	effluent	17	17	17	17	17		
pH	influent	7.9	7.5	7.9	7.7	7.8		
	aeration chamber	7.6	7.6	7.6	7.5	7.6		
	effluent	8.0	8.0	8.0	7.8	7.9		
Biochemical Oxygen Demand (mg/L)	influent	140	170	170	180	180		
	effluent	<5	<5	<5	<5	6		
Suspended Solids (mg/L)	influent	150	220	270	320	280		
	aeration chamber	1000	1100	1300	1200	1100		
	effluent	8	8	8	10	9		
Volatile Suspended Solids (mg/L)	influent	130	190	220	250	210		
	aeration chamber	820	840	990	930	880		
	effluent	8	6	7	8	8		
45 Minute Settleable Solids (mL/L)	aeration chamber	500	640	590	580	520		

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Power failure stress 10/26 through 10/28.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Stress Test Evaluation

Week Beginning: October 29, 1995

Plant Code: 6/139

Weeks Into Test: 21

		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)		500	500	500	500	506	500	500
Dissolved Oxygen (mg/L)	aeration chamber		6.2	5.9	6.4	5.9	5.9	4.1
	effluent		1.6	1.5	1.9	1.4	1.9	1.5
Temperature (°C)	influent		18	17	18	17	17	16
	aeration chamber		16	15	16	16	16	16
pH	influent		7.7	7.9	7.8	7.6	7.6	7.8
	aeration chamber		7.7	7.5	7.7	7.6	7.5	7.4
Biochemical Oxygen Demand (mg/L)	influent	7.9	8.0	7.9	8.0	8.0	7.9	7.7
	effluent	160	200	160	150	170	140	160
Suspended Solids (mg/L)	influent	10	5	<5	<5	<5	5	7
	aeration chamber	180	220	170	200	250	200	160
Volatle Suspended Solids (mg/L)	influent		930	880	880	890	940	940
	effluent	18	9	9	8	10	8	6
45 Minute Settleable Solids (mL/L)	influent	160	190	160	170	210	160	140
	aeration chamber		730	700	680	690	730	750
45 Minute Settleable Solids (mL/L)	influent	15	6	7	6	6	6	<5
	aeration chamber		540	350	500	330	490	460

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes:

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Stress Test Evaluation

Week Beginning: November 5, 1995

Plant Code: 6/139

Weeks Into Test: 22

		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)		325	0	0	0	0	0	0
Dissolved Oxygen (mg/L)	aeration chamber	4.5						
	effluent	1.8						
Temperature (°C)	influent	16						
	aeration chamber	16						
pH	influent	15						
	aeration chamber	7.8						
Biochemical Oxygen Demand (mg/L)	influent	7.5						
	effluent	7.7						
Suspended Solids (mg/L)	influent	170						
	effluent	<5						
Volatle Suspended Solids (mg/L)	influent	150						
	aeration chamber	1000						
45 Minute Settleable Solids (mL/L)	influent	7						
	aeration chamber	140						
45 Minute Settleable Solids (mL/L)	influent	800						
	aeration chamber	6						
45 Minute Settleable Solids (mL/L)	influent	580						
	aeration chamber							

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Vacation stress started 11/5.

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Stress Test Evaluation**

Week Beginning: November 12, 1995

Plant Code: 6/139

Weeks Into Test: 23

		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)		0	0	369	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber					8.4	8.7	8.1
	effluent					3.0	4.1	3.4
Temperature (°C)	influent					16	16	15
	aeration chamber					13	13	13
	effluent					12	13	12
pH	influent					7.7	7.7	7.8
	aeration chamber					7.8	7.7	7.7
	effluent				8.0	8.0	7.8	8.0
Biochemical Oxygen Demand (mg/L)	influent				160	150	150	150
	effluent				14	20	15	14
Suspended Solids (mg/L)	influent				190	180	180	200
	aeration chamber					640	600	600
	effluent				31	33	26	18
Volatile Suspended Solids (mg/L)	influent				160	160	160	160
	aeration chamber					480	440	480
	effluent				22	25	18	16
45 Minute Settleable Solids (mL/L)	aeration chamber					160	160	200

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Vacation stress ended 11/14/95.

TGS/3-92

**NSF International**  
**Standard 40 - Individual Wastewater Treatment Plants**  
**Stress Test Evaluation**

Week Beginning: November 19, 1995

Plant Code: 6/139

Weeks Into Test: 24

		Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)		500	500	500	500	450	500	500
Dissolved Oxygen (mg/L)	aeration chamber	6.8	5.5	6.8	7.0	7.8	7.8	
	effluent	2.7	2.4	2.2	2.2	2.1	2.4	
Temperature (°C)	influent	14	15	16	15	15	14	
	aeration chamber	12	13	13	13	12	12	
	effluent	12	12	12	12	12	12	
pH	influent	7.8	7.7	7.8	7.9	7.8	7.8	
	aeration chamber	7.7	7.7	7.6	7.8	7.7	7.6	
	effluent	7.9	8.0	8.0	7.9	8.0	7.9	
Biochemical Oxygen Demand (mg/L)	influent	130	170	170	180	150	260	
	effluent	9	7	6	5	6	7	
Suspended Solids (mg/L)	influent	170	220	230	220	170	300	
	aeration chamber	570	810	770	560	580	570	
	effluent	13	10	9	8	10	8	
Volatile Suspended Solids (mg/L)	influent	150	200	210	190	160	270	
	aeration chamber	480	640	600	420	460	470	
	effluent	12	8	8	6	8	8	
45 Minute Settleable Solids (mL/L)	aeration chamber	200	280	260	180	150	200	

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Dosing shortage on 11/23 due to a problem with the Chelsea site dosing system.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: November 26, 1995

Plant Code: 6/139

Weeks Into Test: 25

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	238
Dissolved Oxygen (mg/L)	aeration chamber	7.9	9.0	7.5	7.1	7.8
	effluent	2.1	2.5	2.4	2.5	2.7
Temperature (°C)	influent	15	15	15	15	15
	aeration chamber	12	12	12	12	12
	effluent	12	12	12	12	12
pH	influent	7.8	7.7	7.8	7.8	7.8
	aeration chamber	7.6	7.7	7.6	7.7	7.7
	effluent	8.0	8.0	7.9	8.0	7.9
Biochemical Oxygen Demand (mg/L)	influent	200	200	170	150	160
	effluent	7	11	10	6	6
Suspended Solids (mg/L)	influent	270	260	290	230	200
	aeration chamber	660	700	670	680	580
	effluent	9	12	8	10	10
Volatile Suspended Solids (mg/L)	influent	230	210	240	190	180
	aeration chamber	640	530	540	530	470
	effluent	7	8	7	8	8
45 Minute Settleable Solids (mL/L)	aeration chamber	200	190	200	200	180

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes: Dosing shortage on 12/1 caused by a clogged Chelsea site influent pump.

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: December 3, 1995

Plant Code: 6/139

Weeks Into Test: 26

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	8.1	7.6	8.4	7.6	8.0
	effluent	2.6	2.3	2.8	3.0	3.1
Temperature (°C)	influent	15	15	15	15	14
	aeration chamber	12	12	12	12	11
	effluent	12	12	12	11	11
pH	influent	7.6	7.8	7.8	7.7	7.8
	aeration chamber	7.7	7.7	7.7	7.7	7.7
	effluent	7.9	7.9	8.0	7.9	8.0
Biochemical Oxygen Demand (mg/L)	influent	230	160	210	220	190
	effluent	7	7	10	18	10
Suspended Solids (mg/L)	influent	220	240	230	270	200
	aeration chamber	600	730	720	650	620
	effluent	12	18	16	37	14
Volatile Suspended Solids (mg/L)	influent	200	200	200	240	170
	aeration chamber	480	580	570	520	490
	effluent	10	14	12	30	12
45 Minute Settleable Solids (mL/L)	aeration chamber	150	200	190	150	160

- (1) Site problem
- (2) Malfunction of system under test
- (3) Weather problem
- (4) Other

Notes:

TGS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: December 10, 1995

Plant Code: 6/139

Weeks Into Test: 27

Weekend Dosing: Sunday - 500 gallons

Saturday - 506 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	8.6	8.4	8.8	8.8	8.4
	effluent	3.3	3.4	3.4	3.1	3.5
Temperature (°C)	influent	14	13	14	14	13
	aeration chamber	11	10	10	10	10
	effluent	10	11	10	10	10
	pH	influent	7.8	7.8	7.9	7.8
aeration chamber		7.7	7.7	7.7	7.6	7.6
	effluent	7.9	7.9	7.9	7.9	7.8
	Biochemical Oxygen Demand (mg/L)	influent	190	170	170	180
effluent		8	8	10	9	10
Suspended Solids (mg/L)	influent	210	210	230	210	250
	aeration chamber	540	560	580	550	580
	effluent	16	15	18	16	17
Volatile Suspended Solids (mg/L)	influent	190	180	200	180	210
	aeration chamber	460	460	480	440	470
	effluent	16	12	14	13	12
45 Minute Settleable Solids (mL/L)	aeration chamber	130	130	125	120	130

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TOS/3-92

NSF International  
Standard 40 - Individual Wastewater Treatment Plants  
Plant Effluent

Week Beginning: December 17, 1995

Plant Code: 6/139

Weeks Into Test: 28

Weekend Dosing: Sunday - 500 gallons

Saturday - 500 gallons

		Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)		500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	8.5	8.5	7.7	8.3	7.6
	effluent	3.9	3.4	3.3	3.5	3.0
Temperature (°C)	influent	14	14	13	13	13
	aeration chamber	10	10	10	10	10
	effluent	10	10	10	10	10
	pH	influent	7.8	7.8	7.8	7.9
aeration chamber		7.7	7.7	7.7	7.7	7.7
	effluent	7.8	7.9	7.8	7.9	7.9
	Biochemical Oxygen Demand (mg/L)	influent	210	200	230	200
effluent		11	10	10	10	12
Suspended Solids (mg/L)	influent	200	300	290	260	210
	aeration chamber	540	570	560	580	650
	effluent	27	23	18	19	23
Volatile Suspended Solids (mg/L)	influent	180	250	260	230	180
	aeration chamber	440	460	480	480	520
	effluent	23	18	17	16	17
45 Minute Settleable Solids (mL/L)	aeration chamber	130	120	120	120	130

- (1) Site problem  
(2) Malfunction of system under test  
(3) Weather problem  
(4) Other

Notes:

TOS/3-92