

**Arkansas Department of Health
Environmental Health Protection**

Receipt Number
17164014

Individual Onsite System Permit Application

Permit Type New Installation
 Alteration / Repair

Fee Schedule for Structures		√
Structures 1500 sq ft or less	\$ 30.00	<input type="checkbox"/>
Structures more than 1500 sq ft and up to 2000 sq ft	\$ 45.00	<input type="checkbox"/>
Structures more than 2000 sq.ft and up to 3000 sq ft	\$ 90.00	<input checked="" type="checkbox"/>
Structures more than 3000 sq ft and up to 4000 sq ft	\$120.00	<input type="checkbox"/>
Structures more than 4000 sq ft	\$150.00	<input type="checkbox"/>
Alteration and Repair	\$ 30.00	<input type="checkbox"/>

DR Environmental I.D. #

0	7	6	0	1	0	7	0	2	8	0
---	---	---	---	---	---	---	---	---	---	---

**PERMIT VALID FOR ONE YEAR
FROM DATE OF
HEALTH AUTHORITY APPROVAL**
Arkansas Department of Health

Part 1 Treatment Type (check one)

Disposal Method (check one)

<input type="checkbox"/> STD = Standard Septic Tank	<input checked="" type="checkbox"/> ATU = Aerobic Treatment Plant	<input type="checkbox"/> STD = Standard Absorption Field	<input type="checkbox"/> LPD = Low Pressure Distribution
<input type="checkbox"/> ISF = Intermittent Sand Filter	<input type="checkbox"/> RSF = Re-circulating Sand Filter	<input checked="" type="checkbox"/> SUR = Surface Discharge	<input type="checkbox"/> HLD = Holding Tank
<input type="checkbox"/> PMF = Proprietary Media Filter	<input type="checkbox"/> RGF = Re-circulating Gravel Filter	<input type="checkbox"/> CPF = Capping Fill	<input type="checkbox"/> SRL = Serial Distribution
<input type="checkbox"/> OTH = Other (Describe)	<input type="checkbox"/> HLD = Holding Tank	<input type="checkbox"/> OTH = Other	<input type="checkbox"/> DRP = Drip Irrigation

1. Owner's/Applicant's Name Nancy Pinson		2. Phone Number 501-676-6796	
Mailing Address PO Box 471, Lonoke, Ark. 72086		4. County Lonoke	
5. Address of Proposed System (If a 911 address is not available, attach detailed directions or map.) 543 Wattensaw Road, Lonoke, Ark. 72086			
6. Subdivision Name N/A	7. Approval Date N/A	8. Date Recorded N/A	9. Lot Number N/A
10. Lot Dimensions 668' x 90' x 915' x 723'	11. Total Area (Acres) 6.294	12. # Bedrooms # People Three	13. Daily Flow (GPD) 370
14. Brief Legal Description of Property (Attach a separate sheet of paper if necessary.) S3, T3N, R8W			
15. Water Supply (Specify supplier if Public Water.) Grand Praire		16. GPS Coordinates At discharge outlet: 34.915494, -91.846914	
17. Soil Determination (Primary Area) Indicate the depth to items a-f if observed in the soil (designate inches).			
a. Bedrock >48	b. BSWT Surface	c. MSWT 23	d. LSWT 31
e. Adj. MSWT No Load	f. Adj. LSWT No Load	g. H.C./Depth Mod/0-23	h. Loading Rate (GPD/ft²) No Load
18. Soil Determination (Secondary Area) Indicate the depth to items a-f if observed in the soil (designate inches).			
a. Bedrock	b. BSWT	c. MSWT	d. LSWT
e. Adj. MSWT	f. Adj. LSWT	g. H.C./Depth	h. Loading Rate (GPD/ft²)
19. Percolation Test (min/in)		20. System Size	
Rate for Hole 1	N/A	a. Size of Septic Tank	500 gpd atu
Rate for Hole 2	N/A	b. Size of Dose Tank	N/A
Rate for Hole 3	N/A	c. Absorption Area	N/A
Alt Area Perc.	N/A	d. Number of Field Lines	N/A
Average Perc. (1-3)	N/A	e. Length of Field Lines	N/A
f. Trench Depth		N/A	
g. Trench Spacing		N/A	
h. Trench Media		N/A	
Trench Width		N/A	

Comments: STUB OUT ON GRADE AT FLAGGED LOCATION. This site is unsuitable for a standard septic system. We are requesting approval to apply for a discharge permit through ADEQ.

**NOTE TO INSTALLER: CONTACT
SANITARIAN AT 843-7561-4845
PRIOR TO BEGINNING INSTALLATION**

21. I certify that I have conducted the above tests and that the above listed information is in accordance with the latest requirements of the Arkansas Department of Health Rules and Regulations Pertaining to Onsite Wastewater Systems, Designated Representatives and Installers. Without Prejudice!

Signature: Wayne Long D.R. / Owner: _____ Title: _____ Soil Certified Yes No

Typed Name: Wayne Long /AMAX Services LLC Date: 04/29/11 Phone Number: 501-681-7971

22. Approval of Health Authority: The information above has been reviewed and found to meet the requirements of the Arkansas Department of Health for Onsite Wastewater Systems, Designated Representatives and Installers.

A PERMIT FOR CONSTRUCTION is hereby issued.

Environmental Health Specialist: [Signature] Date: 5-5-11

Owner's/Applicant's Name	Receipt Number
--------------------------	----------------

23. Utilization Verification:
 I hereby attest that item 12, the number of bedrooms (number of persons for commercial) and square footage of the structure that will utilize the designed individual onsite wastewater system in this permit application, is accurate.

Owner/Applicant: X Nancy Purin Date 2/23/11

Part 2 Installation Inspection

Septic tank manufacturer	Other information
Septic tank material	Trench media and width
Dose tank manufacturer	Depth of interceptor drain
Dose tank material	Depth of settled fill
Pump Information	
Name of Installer	License Number
Environmental Health Specialist	Date

Part 3 Permit for Operation

The information contained in Part 1 and Part 2 of this form has been reviewed and found to meet the requirements of the Arkansas Department of Health. THE PERMIT FOR OPERATION of this system is hereby issued.

Environmental Health Specialist _____ Date _____

Comments

TO THE OWNER

The permit for construction may be deemed invalid by the local Environmental Health Specialist before construction if the site and/or soil conditions have changed after approval of the permit or if the information on the permit is inaccurate.

Approval for operation does not constitute a guarantee that the system will function properly. The approval states that the system was designed and installed according to the Arkansas Department of Health Rules and Regulations Pertaining to Onsite Wastewater Systems, Designated Representatives and Installers, unless there are exceptions or deviations noted in the comments.

A permit is valid for one (1) year from the date of approval. A permit more than one (1) year old must be revalidated by the authorized agent prior to the start of any construction.

Site Revalidation Conducted by	<input type="checkbox"/> Designated Representative	<input type="checkbox"/> Environmental Health Specialist
_____		Date _____
Site Revalidation Conducted by	<input type="checkbox"/> Designated Representative	<input type="checkbox"/> Environmental Health Specialist
_____		Date _____

System Specification

Designed by D. R. Services Inc.
D.R. #07601070280
Ph.# 501-681-7971

For : Nancy Pinson

This site is unsuitable for subsurface disposal. This system was designed to be a Norweco Model 960 treatment unit with a U.V. disinfection device. Discharge into a 137' tail line. Stub out at grade.

Ground Rod/Flow Line Readings in inches:

Stub Out 51

Model 960 inlet 50/70

Model 960 outlet 50/73

Tail line discharge outlet 77/77

Bench Mark 24.75 on nail in a tree SSW of discharge outlet.

Pipe Specifications:

Schedule 40 PVC from house and between all parts of the system.

Tail line must be at least 1.5" schedule 40.



Scale
1:30

90'

Existing Driveway

Proposed Driveway

915' Not to scale

668'

Propose Home

W Proposed waterline

stub out

clear out

Norweco 960
with UV disinfection

137' Tail line


Slope
3%

202'
TO P/L

319'

150'

Nancy Pinson



S 89°52'16" E

90.19'

S 44°21'30" E 190.08'


F.I.P. W/CAP
1333 SAM SMITH

F.I.P. W/CAP
1333 SAM SMITH

S 42°47'18" E 320.03'

WATTENSAW ROAD

N 00°48'05" E 668.04'



SCALE: 1"=100'

PROPOSED 3150 S.Q.
(UNDER ROOF)
RESIDENCE

F.I.P. W/CAP
1333 SAM SMITH

209.0

180.1

PART OF THE SW 1/4 OF THE NE 1/4
SECTION 3, T-3-N, R-8-W
(6.294 ACRES)

N 52°52'16" W 723.45'

F.I.P. W/CAP
1333 SAM SMITH

LEGAL DESCRIPTION: (AS PROVIDED)

A 6.294 -acre parcel of land being part of the Southwest Quarter (SW/4) of the Northeast Quarter (NE/4) of Section 03, Town ship 03 North, Range 08 West of the Fifth Principal Meridian, Lonoke County, Arkansas, more particularly described as follows:

BEGINNING at a found 1000 nail at the Southwest corner of the Southwest Quarter (SW/4) of the Northeast Quarter (NE/4) of said section 03; THENCE North 00 degrees 48 minutes 05 seconds East, 668.04 feet along the West line of said Southwest Quarter (SW/4) of the Northeast Quarter (NE/4); THENCE South 89 degrees 52 minutes 16 seconds East, crossing a set one-half inch diameter rebar at 20.45 feet, in all 90.19 feet to a set one-half inch diameter rebar; THENCE South 44 degrees 21 minutes 30 seconds East, 190.08 feet to a set one-half inch diameter rebar; THENCE South 42 degrees 47 minutes 18 seconds East, 320.03 feet to a set of one-half inch diameter rebar; THENCE South 42 degrees 29 minutes 50 seconds East, 405.04 feet to a set one-half inch diameter rebar on the South line of said Southwest Quarter (SW/4) of the Northeast Quarter (NE/4); THENCE North 89 degrees 52 minutes 16 seconds West, crossing a set of one-half inch rebar at 700.24 feet, in all 723.45 feet to the POINT OF BEGINNING.

Basis of Bearings: Grid North, Arkansas State Plane Coordinate System, South Zone, North American Datum of 1983 (NAD 83).

NO ATTEMPT HAS BEEN MADE AS PART OF THIS SURVEY TO OBTAIN OR SHOW DATA CONCERNING EXISTENCE, SIZE, DEPTH, CONDITION, CAPACITY, OR LOCATION OF ANY LOCAL OR MUNICIPAL/PUBLIC FACILITIES, EXCEPT AS SHOWN. FOR INFORMATION REGARDING THESE UTILITIES PLEASE CONTACT THE APPROPRIATE AGENCIES OR OTHER SURVEYORS.

NO STATEMENT CONCERNING FLOOD PLAIN LOCATION OR DETERMINATION ARE INCLUDED WITH THIS SURVEY.

SURVEYOR CODE
500-03N-08W-0-03-130-43-1493

FOR USE AND BENEFIT OF:
NANCY PINSON

WATTENSAW ROAD
LONOKE, AR. 72085

I HEREBY CERTIFY THAT THE ABOVE PLAT REPRESENTS A SURVEY MADE BY ME ON THIS DAY, AND ALL EASEMENTS, ENCROACHMENTS, AND IMPROVEMENTS DISCLOSED BY THIS SURVEY ARE SHOWN. NO INDEPENDENT SEARCH FOR EASEMENTS, COVENANTS, ENCUMBRANCES, OR ANY OTHER FACTS WHICH AN ACCURATE TITLE SEARCH MAY DISCLOSE WAS PERFORMED.

VANCE J. HARPER
VANCE J. HARPER, PROFESSIONAL LAND SURVEYOR
ARKANSAS LICENSE No. 1493



NUMBER	DATE

BOUNDARY SURVEY
WATTENSAW ROAD
PART OF THE SW 1/4 OF THE NE 1/4
SECTION 3, TOWNSHIP 3 NORTH, RANGE 8 WEST
LONOKE COUNTY, ARKANSAS

VANCE JAY HARPER
492 BIZZELL ROAD AUSTIN, AR. 72007
(501)-605-8541

DATE	SCALE
04-28-2011	1"=100'

SWC, SW, NE
FND MAG NAIL
CORNER REFERENCE

1. N88°E 11.3' FND NAIL IN WEST FACE FENCE CORNER.
2. N77°W 22.5' FND 60 Ø NAIL IN SE FACE CROSS TIE.
3. N28°W 50' TO FND NAIL IN SE FACE 10" OAK TREE.

ADH POLICIES AND PROCEDURES

EHP Vol. 1

Transmittal No.: 03-30

APPENDICES

Page: APP-1

Effective Date: 10-31-03

MEMORANDUM OF AGREEMENT

SUBJECT: HOME SEWAGE TREATMENT SYSTEM

This is an agreement that the alternative/experimental sewage system installed on this property has been permitted under authority of Act 402 of 1977 and by the Arkansas Department of Health with the understanding that the following provisions are met:



1. The property owner assumes all responsibility for the proper operation of the system and the maintenance of a valid service contract with a Certified Maintenance Personnel approved to service and monitor such home sewage treatment systems. The service contract shall include provisions for the monitoring of free chlorine and PH and reporting to ADH as required.
2. The Arkansas Department of Health has no responsibility in the operation and maintenance of such systems.
3. That the Arkansas Department of Health may monitor the system as to its operation capabilities.
4. That the Arkansas Department of Health is granted permission to make such inspections as deemed necessary.
5. That, on the sale of the property, the perspective buyer will be notified of this agreement, and both the buyer and seller are to sign such memoranda and contracts.
6. Any participation in the design or construction of such experimental systems by the Arkansas Department of Health shall not be considered as a conflict of interest with other parties, and such participation shall not place the Arkansas Department of Health as a responsible party if malfunctions occur.
7. The owner may be required to file an application to the Arkansas Department of Environmental Quality (ADEQ) for a National Point Discharge Elimination System (NPDES) permit. The Arkansas Department of Health will notify the ADEQ of all permits issued for systems that discharge sewage, when applicable.

SIGNED: X Nancy Purson
(Property Owner)

SIGNED: [Signature]
(Health Department)


DATE: 2/23/11

DATE: 5-5-11



GENERAL NOTES

1. SINGULAR® AERATOR, AS TESTED AND ACCEPTED BY NSF.
2. FALL THROUGH SINGULAR® PLANT FROM INLET INVERT TO OUTLET INVERT IS FOUR INCHES. INLET INVERT IS TWELVE INCHES BELOW TANK TOP.
3. ON DEEPER INSTALLATIONS, PRECAST RISERS MUST BE USED TO EXTEND AERATOR MOUNTING CASTING AND BIO-KINETIC® SYSTEM MOUNTING CASTING TO GRADE. INSPECTION COVER ON PRETREATMENT CHAMBER MUST BE DEVELOPED TO WITHIN TWELVE INCHES OF GRADE.
4. TANK REINFORCED PER ACI STD. 318-83.
5. REMOVABLE COVERS ON RISERS W/CH IN EXCESS OF SEVENTY FIVE POUNDS EACH TO PREVENT UNAUTHORIZED ACCESS.
6. CONTACT THE LOCAL LICENSED SINGULAR® DISTRIBUTOR FOR ELECTRICAL REQUIREMENTS.
7. TOTAL SYSTEM CAPACITY: 1300 GAL.



U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVII NORWECO, INC.

NORWECO SINGULAR® BIO-KINETIC® WASTEWATER TREATMENT SYSTEM MODEL 960-500 GPD	REVISION DATE 2-10-87	REVISION JMM
	APPROVED BY GJS	DATE 1-9-96
SCALE NTS	DRAWING NO. PC-5-7006	

THIS DRAWING IS THE PROPERTY OF NORWECO WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.

Certified Maintenance Personnel Contract

Onsite Maintenance Program

Property Address: 543 Wattenstein Road
Lunoke, Ark. 72086

Homeowner Name: Nancy Pinson

The following items will be conducted each (6) month interval.

Chlorine residual analysis

PH analysis


Evaluation of system components and their working condition.

File appropriate paperwork with Department of Health to comply with Onsite Maintenance Program.

This Onsite Maintenance Personnel Contract does not include the cost of chlorine tablets, or replacement of any non-working components of the septic system.

This Onsite Maintenance Personnel Contract does not replace the maintenance contract provided by the Distributor of the aerobic treatment plant.

This contract is good for (2) years from time of installation, and can be renewed or canceled at the homeowners discretion.


Certified Maintenance Personnel - Mike O'Connor

Date

4/29/11

Date: 5/3/2011



Arkansas
Department of Health
Keeping Your Hometown Healthy

SEPTIC TANK PERMIT

Customer Name: LONKE WAYNE

Customer No: 1501109692

Transaction Date: 5/3/2011

Transaction No: 17184016

Created By: cdgully

Amount Received: \$90.00

Payment Method: Check No. 1421

Customer: Pincus, Nancy

Customer Name: Pincus, Nancy

Street Address: 543 Water Saw Road Lonoke Ar

Business: n/a

Phone: n/a

Ref Rec

Customer: Christenson, Ryan

Thank you for your payment

County Health Unit - Cabot

1st St

County: AR 72023

CLEAR FLOW *A WASTEWATER MANAGEMENT COMPANY*

Mike O'Connor
P.O. Box 992
Cabot, AR 72023

Michael@ArkansasSeptic.com
Office 501-517-7198
Fax 501-843-2546

May 23, 2011

Adeq
Water Div.

To whom it may concern;

The treatment plant proposed for Nancy Pinson will use the Norweco model 960 as submitted
By Strider Consulting Feb 25, 2010.

Sincerely,
Clear Flow


A handwritten signature in black ink, appearing to read "Mike O'Connor". The signature is written in a cursive, flowing style.

Mike O'Connor
DR # 60-37



Map of:
Little Rock, AR 72223

Notes



All rights reserved. Use subject to [License/Copyright](#) |

Directions and maps are informational only. We make no warranties on the accuracy of their content, road conditions or route usability or expeditiousness. You assume all risk of use. MapQuest and its suppliers shall not be liable to you for any loss or delay resulting from your use of MapQuest. Your use of MapQuest means you agree to our [Terms of Use](#)

ARG550000 Checklist

ARG55 0382 New Renewal Modification
 Business Individual Homeowner
 Submitted Permit Fee: Yes No Not Required

Discharges to Wattensaw Bayou

Ecologically Sensitive Waterbody: Yes No
 303(d) list? Pathogens Nutrients DO
 None Other _____

Name of Operator: Mike O'Connor License Number 010202

Class of municipal wastewater operator: I II III IV

ADH Approval (EHP-19 Form): Yes No

Approved System:

	Company Name	System Name
<input type="checkbox"/>	Oreco Systems, Inc.	Advantex AX20
<input type="checkbox"/>	Ecological Tank, Inc.	AquaSafe 500
<input checked="" type="checkbox"/>	Norweco, Inc.	Norweco (Singular) 960
<input type="checkbox"/>	Norweco, Inc.	Norweco (Singular) TNT-500
<input type="checkbox"/>	Clearstream Wastewater Systems, Inc.	Clearstream 500N+1100 Effluent Filter or a post aeration tank
<input type="checkbox"/>	Consolidated Treatment Systems, Inc.	MultiFlo FTB-0.5
<input type="checkbox"/>	EnviroGuard	ENV-0.75
<input type="checkbox"/>	Consolidated Treatment Systems, Inc.	Nyadic M6-A
<input type="checkbox"/>	Bio-Microbics, Inc.	MicroFast @ 0.5/With UV Disinfection and Post Aeration

Additional Treatment: _____

Other Comments: Facility location is 2.2 miles from discharge into Wattensaw Bayou. Will not have negative impact on it for DO.

Design Notes

Prepared for:

Arkansas Department
Of Environmental Quality
General Permit ARG 550000

Project:

Norweco®
Singular® Bio-Kinetic®
Wasterwater Treatment System
Model 960
Design Flow 500 GPD
Revision 02/09/2010

Prepared by:



1029 Hwy 201 N
Mountain Home, AR 72653



DESIGN NOTES

Treatment System:

These design notes are prepared specifically for the Norweco® Singular® Model 960 individual treatment system. The purposes of these design notes are to show this system meets the Individual Treatment System General Permit ARG550000 discharge limits. The Singular® Model 960 is for an individual residence only. Specific site applications will need to be evaluated before installation of the Norweco® Singular® Model 9600.

Treatment Process:

The Singular® Model® 9600 is a self-contained treatment system. The system is contained in a precast concrete tank. The tank is baffled in a configuration to separate the process into four treatment components.

Pretreatment Chamber:

The chamber accepts the household waste stream through an inlet. The inlet is precast into the side of the concrete wall. The chamber has a capacity of 60 cubic feet or approximately 448 gallons. This equates to 21.5 hrs of retention time. The outlet of the chamber has a tee which will pull the preconditioned liquid from the vertical center of the section. This will prevent "short circuiting" of the chamber as well as reduce the solids moving into the next phase of treatment.

Extended Aeration Chamber:

The liquid passes through a submerged orifice into the extended aeration chamber. The orifice is precast into a 2" concrete baffling wall. This chamber has a capacity of 80.6 cubic feet which is approximately 600 gallons. With 600 gallons of capacity there is slightly less than 29 hours of retention time in the extended aeration chamber.

Any suspended solids entering the extended aeration chamber will be broken down during this phase of treatment. Bacteria will attach themselves to and consume the organics suspended in the liquid. A Singular Aerator which is tested and accepted by the National Sanitary Federation will be utilized. Only non-corrosive parts will be in contact with the liquid. The aerator will deliver 3 cubic feet per minute of air into the liquid and will run 30 minutes every hour for a total dose of air of 90 cubic feet of air.

Final Clarification Chamber:

Liquid from the extended aeration chamber will pass through a Bio-Static® sludge return into the final clarification chamber. The clarification chamber has a capacity of 213 gallons which is approximately 10.2 hours of retention.

The sides of the clarification chamber are tapered to allow the final setting of solids into the hopper. The hydraulics from the Bio-Static® sludge return will push the sludge back into the aeration chamber.

Bio-Kinetic[®] System:

The final phase of treatment is the Bio-Kinetic[®] system. This phase of treatment provides the polishing of the water. The liquid passes through a filter which is made up of non-corrosive material. Chlorination and de-chlorination is performed in the Bio-Kinetic[®] as required. Additionally, the flow is controlled through orifice plates and can be measured through the discharge weir. Ultimately the treated water is released through a cast-in-place 4" effluent line.

The following are the design calculations for the proposed system. Inflow and infiltration are not considered because pipes are generally glued joints and relatively close to the house.

Design Calculations:

Total Design Flow = 500 gpd

Expected Incoming Effluent Strength:

BOD₅ = 150 mg/l = .0013 lbs/gal

BOD₅ total load = .0013 lbs/gal x 500 gal = .626 lbs per day

TSS = 200 mg/l

Targeted Treatment Quality:

BOD₅ = 10 mg/l

TSS = 15 mg/l

Fecal Coliform = 10,000 N/100 ml

pH: 6 to 9 S.U.

Disinfection Calculations:

Max. flow daily = 500 gpd

Flow rate = 500 gpd / 24 hr day / 60 min = .35 gpm

.35 gpm x 15 min = 5.25 gallons

Bio-Kinetic[®] Container 15 gal > 5.25 gal OK

BOD₅ Reduction Calculations:

Influent BOD strength = 150 mg/l

Pretreatment reduction:

20% to 30% = 120 mg/l to 105 mg/l

Extended Aeration Reduction:

85% to 95% = 18 mg/l to 5.25 mg/l

Final Clarifier Reduction:


45% to 50% = 9.9 mg/l to 2.6 mg/l

Bio-Kinetic[®] System:


~ 6 mg/l removal = 3.9 mg/l to < 1 mg/l

Following is a list of the supporting documentation.

- Singulair Drawing
- Singulair Specifications
- Singulair Aerator
- Bio-Kinetic Specifications
- Singulair Brochure



- GENERAL NOTES:**
- 1 SINGULAIR® AERATOR, AS TESTED AND ACCEPTED BY NSF.
 - 2 FALL THROUGH SINGULAIR® PLANT FROM INLET INVERT TO OUTLET INVERT IS FOUR INCHES. INLET INVERT IS TWELVE INCHES BELOW TANK TOP.
 - 3 ON DEEPER INSTALLATIONS, PRECAST RISERS MUST BE USED TO EXTEND AERATOR MOUNTING CASTING AND BIO-KINETIC® SYSTEM MOUNTING CASTING TO GRADE. INSPECTION COVER ON PRETREATMENT CHAMBER MUST BE DEVELOPED TO WITHIN TWELVE INCHES OF GRADE.
 - 4 TANK REINFORCED PER ACI STD. 318-05.
 - 5 REMOVABLE COVERS ON RISERS WEIGH IN EXCESS OF SEVENTY-FIVE POUNDS EACH TO PREVENT UNAUTHORIZED ACCESS.
 - 6 CONTACT THE LOCAL, LICENSED SINGULAIR® DISTRIBUTOR FOR ELECTRICAL REQUIREMENTS.



PROJECT ENGINEER'S APPROVAL:
 I (WE) HEREBY CERTIFY THAT THIS DRAWING HAS BEEN CHECKED AND IS APPROVED FOR USE IN CONFORMITY WITH THE CONTRACT DOCUMENTS.
 DATE: _____

CONTRACTOR'S CERTIFICATION:
 I (WE) HEREBY CERTIFY THAT THIS DRAWING HAS BEEN CHECKED AND IS APPROVED FOR USE IN CONFORMITY WITH THE CONTRACT DOCUMENTS.
 DATE: _____
 NAME: _____

CRITICAL DIMENSIONS

A	1'-0"	N	0'-3"
B	2'-9"	O	0'-6"
C	2'-8"	P	0'-2 1/2"
D	3'-7"	Q	1'-4"
E	2'-3"	R	4'-8"
F	9'-3"	S	6'-0"
G	1'-0"	T	1'-0"
H	5'-0"	U	5'-6"
I	0'-3"	V	
J	0'-3"	W	
K	1'-0"	X	
L	0'-2"	Y	
M	4'-6"	Z	

U.S. AND FOREIGN PATENTS PENDING

norweco 1-29-07 J

SINGULAIR® BIO-KINETIC® WASTEWATER TREATMENT SYSTEM MODEL 950 - 500 GPD

DESIGNED BY: BDS
 CHECKED BY: JMM
 DATE: 1-9-96
 DRAWN BY: NTS

© MMVII

PC-5-7006


NOTE: TOTAL SYSTEM CAPACITY: 1,300 GALLONS
 RATED CAPACITY: 500 GALLONS PER DAY

norweco[®]

**SINGULAIR[®] BIO-KINETIC[®]
WASTEWATER TREATMENT SYSTEM
MODEL 960**

GENERAL SPECIFICATIONS

The contractor shall furnish and install one complete Singulair Bio-Kinetic wastewater treatment system with all necessary parts and equipment as described in the following specifications. Treatment of the domestic wastewater shall be accomplished by the extended aeration process with non-mechanical flow equalization, pretreatment of the influent, and filtration of the final effluent. The treatment system shall provide primary, secondary, and tertiary treatment of the wastewater flow, and if required, chlorination and dechlorination of the effluent prior to discharge. All treatment processes shall be contained within reinforced precast concrete tankage meeting the requirements of ACI Standard 318. The wastewater treatment system shall be a Singulair Model 960 as manufactured by Norweco, Inc., Norwalk, Ohio, USA. Systems utilizing fiberglass, steel, or plastic tankage are subject to floatation when dewatered and shall not be considered for this application.



The wastewater treatment system shall include precast concrete tankage providing separate pretreatment, aeration and final clarification chambers. The tankage shall be furnished with cast-in-place inlets, submerged transfer ports, aerator mounting casting with removable cover, cast-in-place molded plastic vent assembly, cast-in-place outlet coupling and Bio-Kinetic system mounting casting with removable cover. Principal items of electro-mechanical equipment supplied with the Singulair system shall be a 1725 RPM mechanical aerator, UL Listed Service Pro electrical control center with MCD technology, Bio-Static sludge return and Bio-Kinetic tertiary treatment device for flow equalization and final filtration of system effluent.

SPECIFICATIONS


SINGULAIR®

OPERATING CONDITIONS

Total holding capacity of the system shall provide a minimum of 48 hour retention of the daily flow. The pretreatment chamber shall provide at least 18 hour retention, the extended aeration chamber shall provide at least 24 hour retention, and the clarification chamber shall provide at least 6 hour retention. The non-mechanical flow equalization device shall increase each individual chamber and total system retention time in direct proportion to loading. Design of the system shall include a compartmented tank and non-mechanical flow equalization device to insure successful treatment performance without upset even when the significant runoff period is six hours. Hydraulic design considerations of the system and flow equalization device shall be such that intermittent peak flow factors as high as four shall not upset hydraulic reliability within the system. Capability of the system to perform as outlined, when built by an approved manufacturer, shall be certified by an independent testing laboratory and approved for use by the local governing regulatory agency.

PRETREATMENT CHAMBER

The pretreatment chamber shall be an integral part of the wastewater treatment system. All domestic wastewater shall be preconditioned and flow equalized while passing through the pretreatment chamber prior to being introduced to the extended aeration chamber. The outlet of the pretreatment chamber shall be equipped with a discharge tee that extends vertically into the liquid so that only the preconditioned equalized flow from the center area of the chamber is displaced to the extended aeration chamber. The discharge tee and transfer port shall be of adequate size to handle a peak flow factor of four without restricting the outlet and disturbing hydraulic displacement to the extended aeration chamber. A removable inspection cover shall be cast into the top of the pretreatment chamber to allow tank and transfer tee inspection. As a safety measure, the uncovered opening shall be small enough to insure that the tank cannot be entered for inspection or service.



AERATION CHAMBER


The extended aeration chamber shall provide in excess of 24 hour retention of the equalized daily flow. The chamber shall be of sufficient size to provide a minimum of 80 cubic feet of tank capacity per pound of applied BOD. The aeration chamber length-width-depth ratio shall be designed to insure uniform tank mixing and provide optimum treatment. The aeration chamber(s) shall be an integral part of the system flow path and constructed of properly reinforced 5,000 PSI, 28 day compression strength precast concrete. All castings used to construct the precast concrete tankage shall be monolithic units with external and internal walls incorporated into each section.

FINAL CLARIFICATION CHAMBER

The final clarification chamber shall consist of 5 functionally independent zones operating together to provide satisfactory settling and clarification of the equalized flow. An inlet zone shall be provided and shall dissipate transfer turbulence at the flow inlet of the clarification chamber. Its performance shall also eliminate turbulence in other zones of the clarifier. Liquid shall be hydraulically displaced from the inlet zone to the sludge return zone. Hydraulic currents shall sweep settled sludge from the hopped walls and return these solids via the inlet zone to the aeration chamber. As solids are removed, liquid is displaced to the hopper zone of the clarifier. In this zone, settling by gravity takes place. Three of the four sidewalls are slanted to form a hopper which directs all settled material back to the sludge return zone. Clarified liquid from the hopper zone shall be displaced into the final settling zone to provide additional clarification of the liquid. The liquid is finally displaced to the outlet zone for final filtration and discharge from the system. Non-mechanical equalization of the flow, through all 5 independent zones, shall provide optimal settling and clarification.


BIO-STATIC® SLUDGE RETURN

A Bio-Static sludge return shall be installed into the cast-in-place opening(s) in the aeration/clarification chamber wall to provide positive return of settled solids. Aeration chamber hydraulic currents shall enter the sludge return(s) and be directed into the sludge return zone of the clarification chamber. The Bio-Static sludge return shall accomplish resuspension and return of settled solids without disturbing the clarified liquid in the final settling zone and outlet zone.



MECHANICAL AERATOR


Each Singulair aerator shall be installed in a concrete aerator mounting casting above the aeration chamber. Fresh air shall be supplied through a molded plastic vent assembly cast into the concrete access cover above the aerator. The Singulair aerator shall include plated mounting brackets, NEMA 6 rated electrical connector, UL recognized fractional horsepower motor, molded plastic lifting handle, molded plastic air intake screens, molded plastic foam restrictor, stainless steel aspirator shaft and molded glass-filled nylon aspirator tip. The motor shall contain precision manufactured o-ring type seals installed between the motor shell and the machined aluminum endbells to insure watertight integrity is maintained. Molded Viton elastomer shaft seals shall be utilized to protect the bearings from contamination. Only the stainless steel aspirator shaft and glass-filled nylon aspirator tip shall be installed in contact with the liquid. There shall be no submerged electrical motors, bearings, or fixed air piping in the aeration system. Singulair aerator motors shall be designed not to exceed the motor nameplate rating when installed and operated as recommended for the system. The fractional horsepower aerator motor shall be equipped with a foam restrictor to protect the motor against high water and foam. The motor shall be 4 pole, 1725 RPM, 115 volt, 60 Hertz, single phase, ball bearing constructed with a 1.0 service factor. It shall draw less than 4.0 amps when operating at the rated nameplate voltage. Aerator motors without UL recognition have not demonstrated compliance with international electrical standards for safety and reliability and shall not be considered for this application.



BIO-KINETIC®


SERVICE PRO® ELECTRICAL CONTROL CENTER

The Service Pro electrical control center with MCD technology shall provide Monitoring, Compliance and Diagnostic functions for the Singulair treatment plant using a microprocessor based platform. The Service Pro control center shall contain nonvolatile memory to prevent loss of programming in the event of a power failure. The pre-wired controls shall be mounted in a lockable NEMA rated enclosure designed specifically for outdoor use. Each Service Pro control center shall be a UL Listed assembly and shall include a time clock, alarm light, reset button, power switch, power light, phone light, aerator alarm light and three auxiliary alarm lights. The control center shall monitor all treatment system operating conditions including aerator over current, aerator under current and open motor circuit. In the event the control center detects one of these conditions, power to the aerator shall be interrupted, a diagnostic sequence shall begin and the visual alarm shall activate. After a programmed recovery interval, an automatic restart attempt shall be initiated. If normal aerator operation does not resume during 24 programmed recovery and restart cycles, the audible alarm shall activate and the telemetry system shall report the specific condition to the Service Pro monitoring center. In the event that any of the auxiliary inputs detect abnormal operation of the treatment system auxiliary equipment, the audible and visual alarms shall immediately activate and the telemetry system shall report the alarm condition to the monitoring center. The service provider shall automatically be notified by the Service Pro monitoring center of the specific alarm condition using phone, fax or email.



TIME CLOCK

The aerator run cycle shall be controlled by an adjustable, pre-wired time clock. The minimum setting shall not permit the aerator to be "off" for more than 30 minutes per hour. It shall be adjustable in 5 minute increments and designed such that any adjustment results in additional run time up to "continuous" operation (60 minutes per hour). Use of a time clock can seriously affect system performance and operating cost. Systems that have not been performance certified at the minimum time clock setting by an independent testing laboratory shall not be considered for this application.




SERVICE PRO® MONITORING CENTER

The Service Pro monitoring center shall include a 128 bit encrypted password protected website for interface with the monitoring center database. Access to the secure website shall be obtained through a unique user name and password that provides tiered access to data from monitored treatment systems. Access level tiers shall include distributors, service providers, regulatory agencies and individual system owners. Distributors and service providers shall be able to create accounts, maintain service records and grant regulatory agencies access to the information. Individual system owners shall be able to view information regarding their own systems, as well as download instructional information. Integrity of stored data shall be maintained through the use of multiple servers operating in geographically isolated locations.

SPECIFICATIONS

BIO-KINETIC® SYSTEM

A Bio-Kinetic system shall be installed in the mounting casting(s) above the clarification chamber. Each Bio-Kinetic system shall provide non-mechanical flow equalization through all plant processes including pretreatment, aeration, clarification, tertiary filtration, chlorination and dechlorination. The assembly shall be supplied with locking lugs and removable moisture/vapor shield and shall consist of a design flow and peak flow micronically molded filter, baffled perimeter settling zone, flow distribution deck, lifting handles, level indicator, adjustment lugs, optional chlorination feed tube, unbaffled perimeter settling zone, solids contact zone, vertical inlet zone, compartmented settling zone consisting of 42 baffled chamber plates, effluent stilling well, final discharge zone, adjustable outlet weir, optional dechlorination feed tube, outlet zone and gasketed discharge flange. All components shall be manufactured from inert synthetic materials or rubber, assembled in circular fashion and connected to a plastic outlet coupling. The outlet coupling shall accept a 4" diameter, Schedule 40, PVC pipe. Each Bio-Kinetic system shall be installed with the inverts of the design flow equalization ports located at the normal liquid level of the clarifier. If intermittent flow rates exceed the capacity of the design flow ports, flow shall be held upstream until the intermittent flow dissipates. If the intermittent flow continues to increase, the liquid level may reach a pair of sustained flow equalization ports. With four ports in use, flow through the system increases while continuing to provide flow equalization to all upstream and downstream processes. Peak flow equalization ports are supplied but should not be required in a properly sized system. Optional Blue Crystal and Bio-Neutralizer tablet feed tubes shall be positioned such that the flow-activated chemical cannot make contact with the liquid upstream of the feed tubes.



FLOW EQUALIZATION

The wastewater treatment system shall include a non-mechanical, demand use, flow equalization device. The device shall control normal residential flow rates and reduce typical residential flow surges. The flow equalization rate shall be dependent upon the specific loading pattern and the duration of flow surges. At the 600 gallon per day NSF Standard 40 design loading schedule, minimum performance of the device shall equalize daily flow an average of 50%.

BLUE CRYSTAL® CHLORINATION SYSTEM (Optional)

The Singlair system shall be furnished complete with a tablet feeder and a six month supply of Blue Crystal disinfecting tablets. Blue Crystal tablets shall be specifically formulated for consistent chlorine dosage and effluent disinfection to the sustained, variable and intermittent flows that are typical of domestic wastewater treatment systems. The tablets shall be manufactured from pure calcium hypochlorite and contain a minimum of 70% available chlorine. Each tablet shall be 2⁵/₈" diameter, compressed to a 1" thickness, weigh approximately 5 ounces and be white in color with blue crystals for easy identification. The tablets shall dissolve in direct proportion to the flow rate, releasing controlled amounts of chlorine.

BIO-NEUTRALIZER® DECHLORINATION SYSTEM (Optional)

The Singlair system shall be furnished complete with a tablet feeder and a six month supply of Bio-Neutralizer dechlorination tablets. The dechlorination tablets shall contain active ingredients specially formulated to chemically neutralize both free and combined chlorine. Each tablet shall be 2⁵/₈" diameter, compressed to a 1³/₁₆" thickness, weigh approximately 5 ounces and be green in color for easy identification. The tablets shall dissolve slowly, releasing controlled amounts of chemical for the instantaneous removal of residual chlorine from the system effluent.

WARRANTY AND EXCHANGE PROGRAM

The manufacturer shall provide a two year limited warranty for each Singulair aerator, Service Pro control center, Bio-Kinetic system and any other Singulair components purchased from the manufacturer. A comprehensive exchange program offers Singulair owners an additional forty-eight years of equipment protection. The distributor shall provide warranty and exchange program details to the regulatory agency, contractor and customer as required.



EQUIPMENT MANUFACTURER

The equipment specified herein shall be the product of a manufacturer having a minimum of seven years experience in the construction of prefabricated wastewater treatment equipment and systems. Bids shall be prepared on the basis of the equipment and material specified herein for purposes of determining the low bid. This is not done, however, to eliminate other products or equipment of equal quality and efficiency. If equipment is to be substituted, approval of such substitution must be made prior to execution of any order. It is assumed that substitution will result in a reduction of cost to the contractor and that if accepted, these savings will be passed along by a reduction in the base bid.

SINGULAIR® MODEL 960 DATA CHART

Designation: Model 960-	500 GPD	750 GPD	1000 GPD	1250 GPD	1500 GPD
Daily Treatment Capacity (Gallons Per Day)	500/600	750/800	1000	1250	1500
Total System Capacity (Gallons)	1300	1600	2300	2850	3400
Number of Singulair Aerators	1	1	2	2	2
Number of Bio-Kinetic Systems	1	2	2	3	3
Number of Bio-Static Sludge Returns	1	1	1	2	2
Drawing Number (PC-5-)	7006	7007	7008	7009	7010

PROGRESS THROUGH SERVICE SINCE 1906

norweco®

*Engineering the future of water
and wastewater treatment*

220 REPUBLIC STREET
NORWALK, OHIO, USA 44857-1156
TELEPHONE (419) 668-4471
FAX (419) 663-5440
www.norweco.com

DISTRIBUTED LOCALLY BY:

Norweco®, Norweco.com®, Singulair®, Modulair®, Travalair®, Lift-Rail®, Microsonic®, Bio-Dynamic®, Bio-Sanitizer®, Bio-Neutralizer®, Bio-Kinetic®, Bio-Static®, Bio-Gem®, Bio-Regeneration®, Bio-Perc®, Blue Crystal®, ClearCheck®, ChemCheck®, Service Pro®, Grease Buster® and "BUSTER" logo® are registered trademarks of Norwalk Wastewater Equipment Company, Inc.

©MMVII NORWECO, INC.

WE HAVE REVOLUTIONIZED AIR DELIVERY


THE SINGULAIR MODEL 206C AERATOR FLOODPROOF CONSTRUCTION DEPENDABLE PERFORMANCE EASILY MAINTAINED

The Model 206C Singulair aerator delivers performance worth talking about. Built with improved watertight integrity, state-of-the-art ball bearings, radial air intake openings and waterproof electrical connections, this Singulair air delivery system outperforms and outlasts all others.

TECHNOLOGY YOU CAN COUNT ON ENGINEERED FOR EXTENDED LIFE


Combining advanced electro-mechanical components with energy efficiency, the Model 206C aerator masters the competition. Designed specifically for use in the rigorous environment of an aeration chamber, this aerator runs cooler, cleaner, quieter and longer than any other air delivery system on the market today.

THE PERFORMANCE YOU NEED THE QUALITY YOU CAN TRUST



SINGULAIR MODEL 206C AERATOR FEATURES

- Lowest electrical usage in the industry
- Technologically advanced ball bearings
- NEMA 6P electrical connector
- Floodproof design
- Proprietary bearing protection system
- Radial air intake openings
- Quieter, cleaner operation
- Certified to UL standard
- Made in the U.S.A.



norweco®

*Engineering the future of water
and wastewater treatment*


220 REPUBLIC STREET
NORWALK, OHIO, USA 44857-1156
TELEPHONE (419) 668-4471
FAX (419) 663-5440
www.norweco.com

BIO-KINETIC®

WASTEWATER MANAGEMENT SYSTEM MODEL BK 2000

GENERAL SPECIFICATIONS

The contractor shall furnish and install one complete Bio-Kinetic wastewater management system with Bio-Kinetic tertiary device, including all applicable equipment, as described in the following specifications. All domestic wastewater shall pass through the Bio-Kinetic wastewater management system for advanced treatment prior to being returned to the environment. Settling and storage of suspended solids, flow equalization, filtration and chemical addition shall be accomplished for the wastewater treatment facility by the Bio-Kinetic wastewater management system. The advanced treatment system shall be a Bio-Kinetic Model BK 2000 wastewater management system, as manufactured by Norweco, Inc., Norwalk, Ohio, USA. The wastewater management system shall be serviceable from grade and shall include a solids settling and retention basin, Bio-Kinetic tertiary device, anti-shear inlet and outlet couplings, safety/service guard, lockable access cover, compression clamp, system mounting casting and extension risers as required.



OPERATING CONDITIONS


The Bio-Kinetic wastewater management system shall be an integral part of the overall wastewater treatment and disposal facility. The system shall be rated to accommodate domestic wastewater flows up to 2,000 gallons per day when used downstream of a properly sized treatment facility. Total holding capacity of the wastewater treatment facility shall provide a minimum of 24 hour retention of the average design daily flow. Design of the wastewater treatment facility, including primary/secondary treatment and wastewater management system, shall insure reliable, long term performance without upset even when the significant runoff period is six hours. Hydraulic design considerations of the treatment facility and wastewater management system shall be such that intermittent peak flow factors as high as four shall not upset hydraulic reliability within the facility. Use of the Bio-Kinetic wastewater management system, when installed by an authorized agent, shall be approved by the local governing regulatory agency.

SPECIFICATIONS

BIO-KINETIC®

SETTLING AND RETENTION BASIN

The settling and retention basin shall be designed to remove biosolids from domestic wastewater. Total holding capacity of the retention basin below the outlet invert shall be 52 gallons. For special applications, additional ring sections are available to increase the liquid and solids retention capacity. The retention basin shall be manufactured to be watertight at burial depths of up to 12 feet. The inlet and outlet couplings of the basin shall contain 4" diameter Schedule 40 PVC pipe couplings to permit a solvent weld connection of inlet and discharge piping. Fall through the retention basin and internal components from inlet invert to outlet invert shall be a total of one inch. A system mounting casting to allow access to the retention basin, Bio-Kinetic tertiary device and all internal components shall be provided. The mounting casting shall be equipped with a molded, one-piece, heavy duty, ribbed, removable access cover with moisture drip lip. The access cover shall be securely installed such that the moisture drip lip is 3" above finished grade. The cover shall be secured to the retention basin by an injection molded compression clamp with lock tab to prevent unauthorized access. The retention basin shall be equipped with a safety/service guard. The safety/service guard shall be installed below the retention basin cover and securely connected to the mounting casting by a retainer cable. The internal safety/service guard shall be designed to prevent accidental entry and be supported by the uppermost internal rib of the mounting casting. To prevent loss or theft, the safety/service guard shall be permanently connected to the retention basin by stainless steel cable. The retention basin, optional ring sections, safety/service guard, access cover and system mounting casting shall be constructed of corrosion resistant, UV stabilized polyethylene. All joints within the retention basin shall be sealed with a polyisoprene gasket and injection molded compression clamp secured with bolted lock tab. The retention basin shall be an integrally molded, heavy duty, one-piece unit, with only one clamp required to attach the access cover. For deeper installations, additional clamps shall be used to connect ring sections and extension risers to the retention basin. Where special shipping considerations apply, the retention basin may be shipped in individual sections for field assembly with compression clamp.



BK 2000 SYSTEM


EXTENSION RISERS

For installations where the inlet invert of the retention basin is more than 28" below finished grade, optional extension risers shall be installed. Extension risers shall be constructed of the same material as the retention basin, optional ring sections and mounting casting. To permit maximum installation flexibility and to accommodate various treatment system elevations, individual extension risers shall be available in 6" increments from 6" up to 72" in height. When an extension riser is used, the internal safety/service guard shall be mounted in the uppermost rib of the riser, directly below the access cover. Extension risers shall be connected to the mounting casting and sealed with a polyisoprene gasket and injection molded compression clamp.

MODEL BK 2000

BIO-KINETIC® TERTIARY DEVICE

A Bio-Kinetic tertiary device shall be connected to the outlet coupling within each retention basin. Suspended and settleable solids and BOD shall be removed from the wastewater flow and retained within the basin and/or the three separate filtration zones and eight independent settling zones of the Bio-Kinetic tertiary device. Each Bio-Kinetic tertiary device shall provide non-mechanical flow equalization through all gravity flow treatment processes of the upstream and downstream wastewater facility, including (as applicable) pretreatment, anaerobic treatment, aerobic treatment, clarification, filtration, chlorination, dechlorination and surface or subsurface effluent disposal systems. The Bio-Kinetic device shall be supplied with locking lugs and removable moisture/vapor shield and shall consist of a design flow and peak flow micronically molded filter, baffled perimeter settling zone, non-mechanical flow equalization, flow distribution deck, lifting handles, level indicator, adjustment lugs, chlorination feed tube, unbaffled perimeter settling zone, solids contact zone, vertical inlet zone, compartmented settling zone consisting of thirty-seven baffled chamber plates, effluent stilling well, final discharge zone, adjustable outlet weir, dechlorination feed tube, outlet zone and gasketed discharge flange. All components shall be manufactured from inert synthetic materials or rubber, assembled in circular fashion and connected to a PVC outlet coupling. The outlet coupling shall permit a solvent weld connection to the discharge piping. Each Bio-Kinetic device shall be installed such that the inverts of the design flow equalization ports are located at the normal liquid level of the gravity flow treatment facility. If intermittent flow rates exceed the capacity of the design flow ports, flow shall be held upstream until the intermittent flow dissipates or continues to increase. If the intermittent flow continues to increase, it will reach the pair of sustained flow equalization ports. With four ports in use, flow through the system increases while the Bio-Kinetic device continues to provide non-mechanical flow equalization to all upstream and downstream processes. Two peak flow equalization ports shall be supplied to equalize intermittent periods of peak hydraulic loading. Blue Crystal tablet chlorination system and Bio-Neutralizer tablet dechlorination system feed tubes shall be positioned such that the flow-activated chemical cannot make contact with the liquid upstream of the feed tubes. Treatment systems utilizing only slotted or screen filtration do not provide non-mechanical flow equalization throughout all gravity flow processes or chemical addition and shall not be considered for this application.



BIO-KINETIC TERTIARY DEVICE

NON-MECHANICAL FLOW EQUALIZATION

The Bio-Kinetic device shall provide non-mechanical, demand use, flow equalization to the entire gravity flow wastewater treatment facility. Flow equalization shall control normal residential flow rates and reduce typical residential flow surges (e.g. shower @ 10 minutes duration, bathtub discharge @ 5 minutes duration, clothes washer discharge @ 2 minutes duration, and dishwasher discharge @ 2 minutes duration). The flow equalization rate shall be dependent upon the hydraulic loading pattern, the duration of flow surges and the size of the treatment facility tankage. In order to fully utilize the upstream flow equalization capacity, the transfer pipe connecting the upstream facility to the Bio-Kinetic wastewater management system shall be not longer than 10 feet and shall fall no more than 1/4" over the entire length. The transfer pipe may be installed at greater length and/or with more fall, but shall result in decreased flow equalization rates that are dependent upon overall pipe length and total fall. At a 2,000 gallon per day residential loading pattern, minimum performance of the device shall equalize daily flow more than 60% when used with a treatment facility having at least 80 square feet of upstream liquid surface area. Flow equalization shall increase detention time of the wastewater in all treatment processes and shall prevent hydraulic upset and solids washout. Flow equalization shall result in additional solids being retained in the upstream portion of the treatment facility, insuring fewer and more stabilized solids in the effluent. Remaining solids shall be further reduced by the Bio-Kinetic wastewater management system. Reduced hydraulic and organic loading shall result in increased treatment and disposal system life.

BLUE CRYSTAL® CHLORINATION SYSTEM

The BK 2000 shall be equipped with a supply of Blue Crystal residential disinfecting tablets installed in the chlorine feed tube of the wastewater management system. Blue Crystal tablets shall be specifically formulated for consistent chlorine dosage to the sustained, variable and intermittent flows that are typical of domestic wastewater treatment systems. The tablets shall be manufactured from pure calcium hypochlorite and shall contain a minimum of 70% available chlorine. The tablets shall incorporate beveled edges to enhance the chemical dissolution pattern. Each tablet within the feed tube shall be 2⁵/₈" diameter, compressed to a 1" thickness, weigh approximately 5 ounces and be white in color with blue crystals for easy identification. The tablets shall dissolve in direct proportion to the flow rate, releasing controlled amounts of chlorine.

BIO-NEUTRALIZER® DECHLORINATION SYSTEM

The BK 2000 shall be equipped with a supply of Bio-Neutralizer dechlorination tablets installed in the dechlorination feed tube of the wastewater management system. The active ingredients of the dechlorination tablets shall be specifically formulated to chemically neutralize both free and combined chlorine. The tablets shall incorporate beveled edges to enhance the chemical dissolution pattern. Each tablet within the feed tube shall be 2⁵/₈" diameter, compressed to a ¹³/₁₆" thickness, weigh approximately 5 ounces and be green in color for easy identification. The tablets shall dissolve in direct proportion to the flow rate, releasing controlled amounts of chemical for the instantaneous removal of residual chlorine.

TEN YEAR LIMITED WARRANTY

The manufacturer shall provide a limited warranty against defects in material and workmanship under normal use and service for a period of ten years. The limited warranty shall cover all components of the Bio-Kinetic wastewater management system purchased from the manufacturer, including retention basin, ring sections, safety/service guard, access cover, system mounting casting, extension risers and Bio-Kinetic tertiary device. A detailed copy of the warranty shall be provided to the regulatory agency, contractor and customer as required.

EQUIPMENT MANUFACTURER

The equipment specified herein shall be the product of a manufacturer having a minimum of seven years experience in the construction of prefabricated wastewater treatment equipment and systems. Bids shall be prepared on the basis of the equipment and material specified herein for purposes of determining the low bid. This is not done, however, to eliminate other products of equal quality and efficiency. If equipment is to be substituted, approval of such substitution must be made prior to the execution of any order. It is assumed that substitution will result in a reduction of cost to the contractor and that if accepted, these savings will be passed along by a reduction in the base bid.

PROGRESS THROUGH SERVICE SINCE 1906






220 REPUBLIC STREET
NORWALK, OHIO, USA 44857-1196
TELEPHONE (419) 668-4471
FAX (419) 663-5440
www.norweco.com

DISTRIBUTED LOCALLY BY:

Singulair®, Modulair®, Travalair®, Lift-Rail®, Microsonic®, Norweco®, Bio-Dynamic®, Bio-Sanitizer®, Bio-Neutralizer®, Bio-Kinetic®, Bio-Static®, Bio-Gem®, Blue Crystal®, Grease Buster® and "BUSTER" logo® are registered trademarks of Norwalk Wastewater Equipment Company, Inc.

©MMII NORWECO, INC.

SINGULAIR®



norweco®

*Engineering the future of water
and wastewater treatment*





SINGULAIR®

A dynamic combination of electro-mechanical equipment, solid state technology and web-based monitoring that translates to increased property value, performance certified for you

The new state-of-the-art Singulair treatment system is the trouble-free, energy-efficient alternative to that out-dated, unmanageable septic tank. It sets a new standard for properties that are not connected to centralized sewers. It quietly, efficiently and automatically treats all incoming wastewater, returning harmless effluent to the environment in just 24-hours. Because it operates only 30-minutes every hour, the new Singulair uses half the energy required by continuous-run systems.

We've been providing progress through service since 1906. When you consider the facts presented in this brochure, you will see why Norweco is recognized everywhere as providing today's answer for the protection of tomorrow's environment.

solutions in wastewater treatment



Norweco distributors are located throughout the United States and much of the rest of the world. Research, product development, manufacturing, marketing and sales support are conducted inside our offices and factory in Norwalk, Ohio. Everyone at Norweco is committed to shaping the future of our industry.

engineering the future


of water and wastewater treatment

Specify Singulair®

Your local Norweco distributor is fully trained to install your Singulair System and any other Norweco product you choose to protect your environment. Each of our distributors has completed a nationally accredited Singulair factory-training program.

The Singulair System comes to you complete, including delivery, tank setting, equipment installation, plant start-up and service. A series of service and adjustment inspections are scheduled for the first two years of operation at the time your system is installed. These inspections are included in the sale so that your system continues to perform at the highest level to protect you and your investment. Extended service contracts are also available from your Norweco distributor.

Singular® rivals the performance of the world's most advanced treatment equipment



Inlet

Untreated wastewater enters the system here.

Pretreatment Chamber

Wastewater enters at the Singular inlet and is equalized here as anaerobic bacteria and gravity precondition it.

Aeration Chamber

Here, safe, living aerobic bacteria convert the wastewater into stable substances. Flow equalization maximizes this biological oxidation and assures 24-hour retention and treatment.

Aerator provides complete treatment

Our exclusive aerator infuses the fresh air that safe, living microorganisms require to fully digest and treat wastewater inside the Aeration Chamber. Powered by our 1725 RPM, 115 volt, fractional horsepower motor, our quiet, reliable aerator is inexpensive to operate, reduces heat build up and dramatically increases bearing life. Each aerator is precision engineered, tested and certified to operate only 30-minutes per hour. Only the stainless steel aspirator shaft and reinforced nylon aspirator come in contact with liquid in the Aeration Chamber.

Clarification Chamber

Flow equalization enhances the settling of biologically active substances inside the Clarification Chamber. Wastewater has now been converted into clarified liquids in this chamber.

Flow Equalization Ports

They control the flow through all upstream and downstream processes and they regulate the amount of treated effluent that can enter the Bio-Kinetic System.

Bio-Kinetic® System

Constructed entirely of plastic and rubber components that are impervious to this environment, our Bio-Kinetic System combines filtration, settling, non-mechanical flow equalization, optional disinfection, adjustable outlet weir and optional dechlorination features into a single, revolutionary package.

Precast Concrete Tank

Every Singular System is constructed of high quality, non-corrosive materials under our rigid quality control standards. The tank, access risers and cover are reinforced precast concrete manufactured locally by your factory-trained, licensed Norweco distributor.

Inspection Cover

Access is safe and easy.

Outlet

Only a clear, safe and odorless liquid exits the system here for return to your environment.



SERVICE PRO® Control Center

EVERY SINGULAR AERATOR IS INSTALLED WITH A SOLID STATE ELECTRICAL CONTROL CENTER. EACH IS EQUIPPED WITH RESETTABLE CURRENT SENSOR, ON/OFF SELECTOR SWITCH, RED WARNING LIGHT, TIME CLOCK, AUDIBLE ALARM, AUXILIARY INPUTS AND FCC LICENSED AUTODIALER FOR REMOTE MONITORING OF INDIVIDUAL COMPONENTS.

Progress Through Service Since 1906. Ultimately, our success over all these years boils down to perceived, appreciated and consistently delivered quality service to our customers.

customer focus



Consider the facts:

- The Singulair Bio-Kinetic System meets or exceeds government standards. The Singulair System is performance certified and listed by NSF International. The Singulair is certified to NSF Standard 40 and our Bio-Kinetic System is certified to NSF Standard 46. Underwriters Laboratories and the Canadian Standards Association have recognized, certified and/or listed all electromechanical components. The auto dialer telemetry system is licensed by the Federal Communications Commission.
- The Bio-Kinetic System includes 3 positive filtration zones with 8 independent settling zones.
- 48-hour retention in the Singulair System reduces pumping frequency as compared to smaller capacity systems.
- Operating costs are low. The only electrical component is our low RPM aerator.
- Excessive hydraulic flows can cause major problems for septic tanks, sand filters and any treatment method that does not provide flow equalization. The exclusive non-mechanical flow equalization feature of our Bio-Kinetic System guarantees that all incoming wastewater is fully treated, regardless of heavy use periods.
- You can install an efficient Singulair plant for about the same cost as an old-fashioned septic tank.
- Eliminates odors and all unsightly, unsanitary conditions so common with septic tanks.
- Durable, reliable components are safely installed out-of-sight below grade. No exposed power cords, compressors, filters or air lines accessible to children or pets.
- No need to purchase a separate tank – our precast concrete pretreatment chamber is part of the Singulair System.
- The Singulair System automatically equalizes influent and effluent flow through all treatment and disposal stages. Flow variations from guests, parties or vacations do not effect treatment performance.
- All flow is equalized an average of 50% at the NSF Standard 40 600 GPD (gallons per day) design loading pattern.
- Your local, factory-trained, certified and licensed Norweco distributor sells, installs and services your Bio-Kinetic System with pride. You'll find your distributor's name and contact info conveniently posted on the system's control center.



Optional Blue Crystal® Residential Disinfecting Tablets


OUR PURE CALCIUM HYPOCHLORITE TABLETS ARE SPECIALLY FORMULATED FOR USE IN THE SINGULAIR SYSTEM FOR EFFICIENT, RELIABLE DISINFECTION. EACH BLUE CRYSTAL TABLET CONTAINS AT LEAST 70% AVAILABLE CHLORINE. PACKAGED IN RE-SEALABLE CONTAINERS, OUR TABLETS ARE AVAILABLE FROM YOUR LOCAL NORWECO DISTRIBUTOR IN 10 AND 100 POUND POLYETHYLENE PAILS.



Optional Bio-Neutralizer® Dechlorination Tablets

RELIABLY, SAFELY AND ECONOMICALLY REDUCE RESIDUAL CHLORINE AND PROTECT ENVIRONMENTALLY SENSITIVE SURFACE WATER WITH OUR SPECIALLY FORMULATED TABLETS. PACKAGED IN EASY TO HANDLE, RE-SEALABLE CONTAINERS, OUR BIO-NEUTRALIZER DECHLORINATION TABLETS ARE AVAILABLE IN 25 AND 45 POUND POLYETHYLENE PAILS FROM YOUR LOCAL NORWECO DISTRIBUTOR.

Today's Answer for the Protection of Tomorrow's Environment



comprehensive protection, guaranteed



Singulair is warranted against defects in material and workmanship under normal use and service by a comprehensive 50 year Warranty and Exchange Program.

This 2 year Limited Warranty and 48 year Exchange provides single source protection and covers all system components. Complete Warranty and Exchange information, a Warranty Registration Card and Owner's Manual are included with purchase.

The Singulair Bio-Kinetic System components have been listed, licensed and/or certified by each of the following agencies/organizations.



norweco[®]

*Engineering the future of water
and wastewater treatment*

220 Republic Street
Norwalk, Ohio, U.S.A. 44857-1156
PH: 419.668.4471
FAX: 419.663.5440
www.norweco.com

Progress Through Service Since 1906

We engineer, manufacture, install and maintain advanced water and wastewater treatment technologies for residential properties, communities and commercial properties that are not connected to sewer lines. Norweco treatment systems are in service all over the world.

Norweco[®], Norweco.com[®], Singulair[®], Modulair[®], Travalair[®], Lift-Rail[®], Microsonic[®], Bio-Dynamic[®], Bio-Sanitizer[®], Bio-Neutralizer[®], Bio-Kinetic[®], Bio-Static[®], Bio-Gem[®], Bio-Regeneration[®], Bio-Perc[®], Blue Crystal[®], ClearCheck[®], ChemCheck[®], Service Pro[®], Grease Buster[®] and "BUSTER" logo are all registered trademarks of Norwalk Wastewater Equipment Company, Inc.

Print postage online - Go to usps.com/postageonline

POSTAGE REQUIRED.

PLEASE PRESS FIRMLY

PLEASE PRESS



UNITED STATES POSTAL SERVICE

Flat Rate Mailing Envelope

For Domestic and International Use

Visit us at usps.com

U.S. POSTAGE PAID
MOUNTAIN HOME, AR
72653
FEB 16, '10
AMOUNT
\$4.90
00055264-16

1006 72118

UNITED STATES POSTAL SERVICE

INTERNATIONAL PRIORITY MAIL

Any amount of mailable material may be enclosed, as long as the envelope is not modified, and the contents are entirely confined within the envelope with the adhesive provided as the means of closure.

INTERNATIONAL RESTRICTIONS APPLY:

4-POUND WEIGHT LIMIT ON INTERNATIONAL APPLIES

Customs forms are required. Consult the *International Mail Manual (IMM)* at pe.usps.gov or ask a retail associate for details.

PRIORITY MAIL
UNITED STATES POSTAL SERVICE

For Domestic and International Use

From Strider Consulting, Inc.
1029 Hwy. 201 North
Mountain Home, AR 72653

TO JOHN BAILEY P.E.
NPDES PERMITS
ADEQ
5301 NORTSHORE DR.
NORTH LITTLE ROCK AR 72118
5317

Label 228, January 2008

INTERNATIONAL PRIORITY MAIL

Country of Destination/Pays de destination:



USPS packaging products have been awarded Cradle to Cradle CertificationSM for their ecologically-intelligent design. For more information go to mbdc.com/usps
Cradle to Cradle CertifiedSM is a certification mark of MBDC.

Please recycle.



Recycled Paper



EP14F

This packaging is the property of the U.S. Postal Service[®] and is provided solely for use in sending Priority Mail[®] shipments. Misuse may be a violation of federal law. This packaging is not for resale. EP14F © U.S. Postal Service; Oct. 2008; All rights reserved.

WASTEWATER TECHNOLOGY

Report on Evaluation of
Norweco Inc.
Singulair® Model 960
Wastewater Treatment System

under the provisions of
NSF Standard 40
on Individual Aerobic
Wastewater Treatment Plants



NSF International
3475 Plymouth Road
PO Box 130140
Ann Arbor, Michigan 48113-0140 USA

**Report on the Performance Evaluation of the
Norweco Singulair® Model 960
Wastewater Treatment System**

**Under the provisions of ANSI/NSF Standard 40
Relating to Individual Aerobic Wastewater Treatment Plants**

April 1996

EXECUTIVE SUMMARY

Testing of the Singulair® Model 960 Wastewater Treatment System was conducted under the provisions of ANSI/NSF Standard 40 for Individual Aerobic Wastewater Treatment Plants (July 1990 revision). ANSI/NSF Standard 40 was developed by the NSF Joint Committee on Wastewater Technology.

The performance evaluation was conducted at the NSF Wastewater Technology Test Facility in Chelsea, Michigan, using wastewater diverted from the Chelsea municipal wastewater collection system. The evaluation consisted of seven months of testing, during which a seven and a half week stress test was conducted. The evaluation consisted of three weeks of dosing without sampling to allow for plant start-up, sixteen weeks of dosing at design flow, seven weeks of stress test and three weeks of dosing at design flow. Sampling started in the early summer and continued through the fall and into winter, covering a full range of operating temperatures.

Standard 40, in Section H. (3) of Appendix A, provides for exclusion of up to ten percent of the effluent sample days, not to exceed one during stress testing, in completing the pass/fail determination. No sample days were excluded in the pass/fail determination for this evaluation.

Over the course of the evaluation, the average effluent BOD₅ was 6 mg/L, ranging between <5 and 18 mg/L, and the average effluent suspended solids was 10 mg/L, ranging between <5 and 37 mg/L. The effluent pH ranged from 7.7 to 8.2.

The Singulair® Model 960 produced an effluent that successfully met the performance requirements established by ANSI/NSF Standard 40 for Class I effluent:

The maximum arithmetic mean of seven consecutive sample days was 10 mg/L for BOD₅ and 19 mg/L for suspended solids, both well below the allowed maximum of 45 mg/L. The maximum arithmetic mean of 30 consecutive sample days was 8 mg/L for BOD₅ and 13 mg/L for suspended solids, both well below the allowed maximum of 30 mg/L. Average removal rates for 30 consecutive sample days ranged from 95 to 97 percent for BOD₅ and from 94 to 98 percent for suspended solids, consistently above the requirement of 85 percent.

The effluent pH during the entire evaluation ranged between 7.7 and 8.2 within the required range of 6.0 to 9.0. The plant also met the requirements for noise levels (less than 60 dbA at a distance of 20 feet) and color, threshold odor, oily film and foam.

PREFACE

Performance evaluation of individual aerobic wastewater treatment plants is achieved within the provisions of ANSI/NSF Standard 40: Individual Aerobic Wastewater Treatment Plants (revised July 1990), prepared by the NSF Joint Committee on Wastewater Technology and adopted by the NSF Board of Trustees.

Conformance with the Standard is recognized by issuance of the NSF Mark. This is not to be construed as an approval of the equipment but rather a certification of the data provided by the test and an indication of compliance with the requirements expressed in the Standard.

Plants conforming to Standard 40 are classified as Class I or Class II plants according to the quality of effluent produced by the plant during their performance evaluation. Class I plants must also demonstrate performance consistent with the effluent color, odor, oily film and foam requirements of the Standard. Class I plants must satisfy the requirements of meeting EPA Secondary Treatment Guidelines¹ for five day biochemical oxygen demand, suspended solids and pH.

Permission to use the NSF Mark is granted only after the equipment has been tested and found to perform satisfactorily, and all other requirements of the Standard have been satisfied. Continued use of the Mark is dependent upon evidence of compliance with the Standard and NSF General and Program Specific Policies as determined by periodic reinspection of the equipment at the factory, distributorships and reports from the field.

NSF Standard 40 requires the testing laboratory to provide the manufacturer of an individual aerobic wastewater treatment plant a report including significant data and appropriate commentary relative to the performance evaluation of the plant. NSF policy specifies provision of performance evaluation reports to appropriate state regulatory agencies at publication. Subsequent direct distribution of the report by NSF is made only at the specific request of or by permission of the manufacturer.


The following report contains results of the entire testing program, a description of the plant, its operation and key process control equipment, and a narrative summary of the test program, including test location, procedures and significant occurrences. The plant represented herein reflects the equipment authorized to bear the NSF Mark.

CERTIFICATION

NSF *International* has determined by performance evaluation under the provisions of ANSI/NSF Standard 40 (revised July 1990) that the Singulair® Model 960 Wastewater Treatment System manufactured by Norweco, Inc., has fulfilled the requirements of ANSI/NSF Standard 40. The Norweco Singulair® Model 960 has therefore been authorized to bear the NSF Mark so long as Norweco continues to meet the requirements of Standard 40 and NSF General and Program Specific Policies.

General performance evaluation and stress tests were performed at the Wastewater Technology Site of NSF *International*, located in Chelsea, Michigan. The raw waste utilized in the test was diverted comminuted municipal waste. The characteristics of the waste are included in the tabulated data of this report.

The observations and analyses included in this report are certified to be correct and true copies of the data secured during the performance tests conducted by NSF on the wastewater treatment plants described herein. The manufacturer has agreed to present the data in this certification in its entirety whenever it is used in advertising, prospectuses, bids or similar uses.



Thomas J. Bruursema
General Manager
Wastewater Treatment Unit Certification



Thomas Stevens
Manager
Engineering and Research Services

TABLE OF CONTENTS

	<u>Page</u>
Executive Summary	2
Preface	3
Certification	4
Table of Contents	5
1.0 Process Description	7
2.0 Performance Evaluation	7
2.1 Description of Unit Evaluation	7
2.2 Test Protocol	8
2.3 Test Chronology	9
3.0 Analytical Results	10
3.1 Summary	10
3.2 Biochemical Oxygen Demand	10
3.3 Suspended Solids	14
3.4 pH	14
3.5 Temperature	17
3.6 Dissolved oxygen	17
3.7 Color, threshold odor, oily film, foam	17
3.8 Noise	17
4.0 References	17
Appendices	
Appendix A - Plant Specifications and Drawings	
Appendix B - Standard 40 Performance Evaluation Protocol and Requirements	
Appendix C - Analytical Results	

This page intentionally blank

1.0 PROCESS DESCRIPTION

The Norweco Singulair® Model 960 wastewater treatment system utilizes patented, extended aeration, activated sludge and filtration processes to achieve treatment. In the activated sludge process, microorganisms remove soluble contaminants from the wastewater, utilizing them as a source of energy for growth and production of new microorganisms. The organisms tend to be flocculent and form clumps, or floc, that physically entrap particulate organic matter. The organic matter is attacked by extracellular enzymes that solubilize the solids to make them available to the microorganisms as a food source. The conversion of the organic matter from soluble to biological solids allows for removal of the organic matter by settling of the solids in the treatment process.²

Extended aeration is a modification of the activated sludge process in which the microorganisms are allowed to remain in the treatment process for long periods of time. The large inventory of biological solids in the process provides a buffer for shock loading of organic matter. The long aeration period allows for the organisms in the system to consume themselves, reducing the total amount of solids produced by the treatment process.

The organisms primarily responsible for the degradation of the organic matter are facultative bacteria in the aerobic state. As such, the transfer of oxygen into the wastewater by an aeration system is critical to the treatment process. The aeration system also provides for the mixing of the wastewater and organisms to provide contact between the organic contaminants in the wastewater and the organisms that provide for removal of the contaminants. For this reason, an activated sludge process is referred to as a suspended growth system. The Norweco Singulair® Model 960 wastewater treatment system incorporates a timed aeration cycle, and provides the proper environment for the development of facultative bacteria.

2.0 PERFORMANCE EVALUATION

2.1 Description of Plant Evaluated

The Singulair® Model 960 System tested in this evaluation has a rated capacity of 500 gallons per day (gpd). Specifications and drawings are included in Appendix A. The system achieves treatment by a flow equalized, flow through process, starting with a pretreatment chamber, followed by an aeration chamber provided with an infused air system operating on a timed run cycle. Settling is accomplished in a clarification chamber following the aeration chamber. A Bio-Kinetic® System located in the clarification chamber provides flow equalization, optional chlorination, final filtration, settling and optional dechlorination prior to effluent discharge.

The Singulair® Model 960 System is made up of four treatment stages. Incoming wastewater flows into the pretreatment chamber for removal of easily separated solids. Anaerobic bacteria break down the solids and begin to solubilize organic particles. A baffle at the outlet of the chamber provides for retention of floating solids in the chamber. Wastewater is transferred from the pretreatment chamber by hydraulic displacement into the aeration chamber through a cast-in-place transfer tee.

The aeration chamber provides a retention time of at least 24 hours. Aeration is achieved by release of air through a rapidly spinning aspirator submerged in the aeration chamber. The spinning of the aspirator in the wastewater draws air down the aspirator shaft, releasing small bubbles that cause the wastewater to rise in the chamber, establishing a circulation pattern. The infused air provides oxygen for the aerobic bacteria, as well as mixing of the wastewater with the bacteria.

The aerator run cycle is controlled by the use of a time clock. Its design does not permit the aerator to be "off" more than thirty minutes per hour. While the time clock is adjustable, any adjustment automatically results in additional run time. The seven month test was performed at full design load (500 gpd), with the aerator running only thirty minutes per hour.

From the aeration chamber, the wastewater passes by hydraulic displacement into the clarification chamber through a cast-in-place transfer port located at the bottom of the wall between the aeration chamber and the clarification chamber. Initial separation of solids takes place in the clarification chamber. The quiescent design of the clarification chamber allows gravity settling of the solids and sludge. Three of the four side walls in the clarifier are sloped to form a hopper. These 60° sloped walls direct material down to the transfer opening. A stationary sludge return device, located in the clarifier, utilizes hydraulic currents to return settled activated sludge from the bottom of the clarifier back to the aeration chamber.

A Bio-Kinetic® System, connected to an outlet coupling cast into the concrete tank, provides the final treatment stage. The Bio-Kinetic® System is located in the center of the clarification chamber and extends down into the chamber. The outlet coupling allows for installation and service of the System from ground level. The System is made up of three filtration zones, seven settling zones and three pairs of flow equalization ports. Wastewater from the aeration chamber flows up through the clarification chamber to the Bio-Kinetic® System where it passes through the design flow filter mesh that extends around the baffled perimeter settling zone. The design flow filter mesh provides for initial filtration and entrapment of solids. Peak flow filter mesh is located above the design flow mesh. Flow control through the System is provided by two design flow equalization ports and two sustained flow equalization ports. The ports become submerged orifices as the water level in the chamber rises, equalizing the flow rate through the entire plant. Extreme hydraulic flows are handled through a pair of peak flow equalization ports, which act to return the plant to normal operating levels. All flow passing through the flow equalization ports drops to a deck that directs flow through an optional chlorine tablet feeder and vertically downward to the unbaffled perimeter settling zone. From this area, flow is displaced to the contact basin and then onto the baffled chamber plates. A continuous baffle on each of 37 plates acts as a kinetic filtration weir with a 1/16 inch opening provided between plates. A larger open area immediately downstream of the baffle provides for settling and storage of solids. The clarified water then passes to an effluent stilling well, final settling zone, adjustable outlet weir, optional dechlorination tablet feeder and discharge zone.

2.2 Test Protocol

The ANSI/NSF Standard 40 Performance Evaluation method and requirements are included in Appendix B. Start up of the plant is accomplished by filling one-third of the volume with raw wastewater and the remainder of the volume with fresh water. The plant is then dosed at the design loading rate (500 gpd) for three weeks. Doses were made during three dosing periods:

- 6 a.m. to 9 a.m. - 35 percent of daily rated capacity
- 11 a.m. to 2 p.m. - 25 percent of daily rated capacity
- 5 p.m. to 8 p.m. - 40 percent of daily rated capacity

After a three week start up period, the plant is subjected to the following loading sequence:

- Design loading - 16 weeks
- Stress loading - 7 weeks
- Design loading - 3 weeks

During the design loading periods, 24-hour composite samples are collected of the influent and effluent five times per week. The samples are analyzed for BOD₅, suspended solids and volatile suspended solids. On-site determinations of the effluent temperature, pH and dissolved oxygen are also made five times per week. In plant measurements of aeration chamber temperature, pH, dissolved oxygen and suspended solids are also made during the evaluation.

Stress testing is designed to evaluate how the plant performs under non-ideal conditions, including high and low hydraulic loadings and electrical or system failure. The test sequence includes (1) Wash Day stress, (2) Working Parent stress, (3) Power Failure stress, and (4) Vacation stress. Detailed descriptions of the stress sequences are shown in Appendix B.

During the stress test sequences, 24 hour composite samples are collected before and for seven days after each stress dosing pattern. The analyses and on-site determinations completed on the samples are the same as described for the design load testing. Additional samples are collected during the Wash Day and Working Parent stresses for informational purposes only and are not included in the pass/fail calculations. These samples include two samples collected during the Wash Day stress, two during the Working Parent Stress, one sample collected immediately after the power is renewed to the plant during the Power Failure stress and one collected with the start of dosing in the Vacation stress.

In order for the plant to achieve Class I effluent it is required to produce an effluent which meets the EPA guidelines for secondary effluent discharge¹:

BOD₅ and Suspended Solids: (a) the arithmetic mean of all effluent samples collected in a period of 30 consecutive sample days must be ≤ 30 mg/L, with ≥ 85 percent removal; and (b) the arithmetic mean of all effluent samples collected in a 7 consecutive sample day period must be ≤ 45 mg/L.

pH: Effluent values remain between 6.0 and 9.0.

Requirements are also specified for effluent color, odor, oily film and foam, as well as maximum noise levels allowed from the plant. In determining if the plant meets the effluent requirements, ten percent of the samples during the testing, not to exceed one sample during stress testing, may be excluded from the pass/fail determination. A minimum of 118 sample days, 23 during the stress test sequence, must be collected and analyzed for the test to be valid.

2.3 Test Chronology

The system was installed under the direction of the manufacturer on May 17, 1995. Dosing, at the rate of 500 gpd, was started on May 22, 1995. After three weeks of start up, sampling was started on June 12, 1995. The stress test sequence was started on October 2, 1995, and ended on November 22, 1995. The testing was completed on December 18, 1995, although sampling continued through January 9, 1996. No maintenance or mechanical adjustment was performed during the test.

3.0 ANALYTICAL RESULTS

3.1 Summary

Chemical analysis of samples collected during the evaluation were completed using the procedures in *Standard Methods for the Examination of Water and Wastewater*³, or U.S. Environmental Protection Agency procedures⁴. Copies of the data generated during the evaluation are included in Appendix C. The results of the all chemical analyses and on-site observations and measurements made during the evaluation are summarized in Table I.

Guidelines for evaluating the analytical results from the testing are described in Section 5.1 and Section H of Appendix A in ANSI/NSF Standard 40. In completing the pass/fail determination on the data generated from the testing, ten percent (a total of twelve) of the samples collected during testing (not to exceed one sample during stress testing) can be excluded from the pass/fail calculations. Samples collected for informational purposes during the stress test sequence are not included in the pass/fail determinations. During testing of the Norweco Model 960 System, no sample days were excluded from the pass/fail determination.

Section 2.9 and Section E of Appendix A of the Standard define influent wastewater characteristics as they apply to testing under the Standard. Typical domestic wastewater is defined as having a BOD₅ concentration between 100 and 300 mg/L and a suspended solids concentration between 100 and 350 mg/L. By the Program Specific Policies for *Wastewater Treatment Devices and Related Products and Components* (dated January 1, 1991):

When the influent Biochemical Oxygen Demand and/or Suspended Solids fall outside the ranges specified in Section 2.9 of Standard 40, the effluent samples for the two calendar days immediately following the occurrence may be excluded in the 7 and 30 sample averages.

The Policy does not require exclusion of data following a day with influent concentrations outside the defined ranges, but allows for discard should the influent strength have an apparent impact on plant performance. There were eight sample days when the influent strength fell outside the specified range, but none were determined to have an impact on plant performance.

3.2 Biochemical oxygen demand

The carbonaceous five day biochemical oxygen demand (BOD₅) analyses were completed using the EPA Method 405.1. The results of the analyses completed on the samples collected during the testing, except those collected for informational purposes, are shown in Figure 1.

Influent BOD₅:

The influent BOD₅ ranged from 120 to 360 mg/L during the evaluation, with an average concentration of 184 mg/L and a median concentration of 180 mg/L.

TABLE I. SUMMARY OF ANALYTICAL RESULTS

	<u>Average</u>	<u>Std. Dev.</u>	<u>Minimum</u>	<u>Maximum</u>	<u>Median</u>	<u>Interquartile Range</u>
BOD₅ (mg/L)						
<i>Influent</i>	184	35	120	360	180	160-200
<i>Effluent</i>	6	2	<5	18	5	<5-7
Suspended Solids (mg/L)						
<i>Influent</i>	238	57	150	450	225	200-270
<i>Aeration Chamber</i>	659	269	250	1,300	605	440-890
<i>Effluent</i>	10	6	<5	37	8	6-14
Volatile Suspended Solids (mg/L)						
<i>Influent</i>	204	47	120	370	200	170-220
<i>Aeration Chamber</i>	532	204	200	990	490	360-700
<i>Effluent</i>	9	4	<5	30	7	5-12
pH						
<i>Influent</i>	-	-	7.4	7.9	7.7	7.5-7.8
<i>Aeration Chamber</i>	-	-	7.4	7.8	7.7	7.6-7.7
<i>Effluent</i>	-	-	7.7	8.2	7.9	7.9-8.0
Temperature (°C)						
<i>Influent</i>	18	2	13	21	19	17-20
<i>Aeration Chamber</i>	19	4	10	23	20	17-22
<i>Effluent</i>	19	4	10	23	20	17-22
Dissolved Oxygen (mg/L)						
<i>Aeration Chamber</i>	5.6	1.5	2.8	9.0	5.4	4.4-6.6
<i>Effluent</i>	2.1	0.8	1.0	4.7	1.9	1.4-2.4

Notes: The median is the point where half of the values are greater and half are less.

The interquartile range is the range of values about the median between the upper and lower 25 percent of all values.

Effluent BOD₅:

The effluent BOD₅ concentrations ranged from <5 to 18 mg/L over the course of the evaluation, with an average concentration of 6 mg/L. The median effluent BOD₅ concentration was 5 mg/L.

Standard 40 requires that over the course of the evaluation, the effluent BOD₅ not exceed 45 mg/L on a 7-day average and 30 mg/L on a 30-day average, and represent a reduction of not less than 85 percent of the 30-day average influent. The averages refer to seven and thirty consecutive sample averages, and not consecutive days. A plot of the 7 and 30-day average concentrations and 30-day average percent removal, is shown in Figure 2.

Figure 1. Biochemical Oxygen Demand





Figure 2. Effluent BOD Averages and Percent BOD Removal



The 7-day average for effluent BOD₅ ranged from 5 to 10 mg/L, the 30-day averages ranged from 5 to 8 mg/L and the percent removal ranged from 95 to 97 percent. As shown in Figure 2, the Norweco Model 960 System met the requirements of Standard 40 for effluent BOD₅.

3.3 Suspended solids

Suspended solids and volatile suspended solids analyses were completed using Methods 209C and 209D of *Standard Methods*. The results of the suspended solids analyses over the entire evaluation are shown in Figure 3. The data from both analyses are summarized in Table I.

Influent suspended solids:

The influent suspended solids ranged from 150 to 450 mg/L during the evaluation, with an average concentration of 238 mg/L. The median influent suspended solids concentration during the evaluation was 225 mg/L. The influent volatile suspended solids ranged from 120 to 370 mg/L during the evaluation, with an average concentration of 204 mg/L and a median concentration of 200 mg/L.

Aeration chamber suspended solids:

The aeration chamber suspended solids ranged from 250 to 1,300 mg/L during the evaluation, with an average concentration of 659 mg/L. The aeration chamber volatile suspended solids ranged from 200 to 990 mg/L, with an average concentration of 532 mg/L. The median values for the aeration chamber were 605 mg/L suspended solids and 490 mg/L volatile suspended solids.

Effluent suspended solids:

The effluent suspended solids concentration ranged from <5 to 37 mg/L during the evaluation, with an average concentration of 10 mg/L and a median concentration of 8 mg/L.

Over the course of the evaluation, ANSI/NSF Standard 40 requires that the effluent suspended solids not exceed 45 mg/L on a 7-day average, 30 mg/L on a 30-day average and that the plant achieve not less than 85 percent reduction of the 30-day average influent suspended solids concentration. A plot of the 7-day and 30-day averages, as well as the percent removal, is shown in Figure 4.

The 7-day average suspended solids ranged from 5 to 19 mg/L, the 30-day averages ranged from 6 to 13 mg/L and the percent reduction ranged from 94 to 98 percent. As shown in Figure 4, the Norweco Model 960 System met the requirements of ANSI/NSF Standard 40 for effluent suspended solids.

3.4 pH

Over the entire evaluation period, the influent pH ranged from 7.4 to 7.9 (median of 7.7), while the aeration chamber pH ranged from 7.4 to 7.8 (median of 7.7). The effluent pH ranged from 7.7 to 8.2 during the evaluation (median of 7.9), within the 6 to 9 range required by ANSI/NSF Standard 40. The pH data for the evaluation are shown in Appendix C.

Figure 3. Suspended Solids





Figure 4. Effluent SS Averages and Percent SS Removal



3.5 Temperature

Influent temperatures over the evaluation period ranged from 13 to 21 °C (median of 19 °C). Effluent temperatures ranged between 10 and 23 °C (median of 20 °C). The temperature data are shown in Appendix C.

3.6 Dissolved oxygen

Dissolved oxygen (DO) was measured in the aeration chamber and effluent during the evaluation. The aeration chamber DO ranged between 2.8 and 9.0 mg/L (median of 5.4 mg/L), while the effluent DO ranged between 1.0 and 4.7 mg/L (median of 1.9 mg/L). All dissolved oxygen data are shown in Appendix C.

3.7 Color, threshold odor, oily film, foam

Three samples of the effluent were analyzed for color, odor, oily film and foam as prescribed in NSF Standard 40. The effluent was acceptable according to the requirements in NSF Standard 40, with color less than 15 units, non-offensive threshold odor, no visible evidence of oily film and no foam.

3.8 Noise

A reading of the noise level at a distance of 20 feet from the plant was taken while the plant was in operation, using a hand-held decibel meter. The reading was below the 60 dbA required under ANSI/NSF Standard 40.

4.0 REFERENCES

1. "Environmental Protection Agency Guidelines for Secondary Treatment", Federal Register, Volume 28, No. 159, 1973.
2. Grady, Jr., C.P., and H.C. Lim, Biological Wastewater Treatment: Theory and Applications, Marcel Dekker Publishers, New York, 1980.
3. APHA, AWWA, WPCF, Standard Methods for the Examination of Water and Wastewater, 17th Edition, American Public Health Association, Washington, D.C.
4. U.S. EPA, Methods for Chemical Analysis of Water and Wastes, U.S. Environmental Protection Agency, Washington, D.C.

This page intentionally left blank.

APPENDIX A
PLANT SPECIFICATIONS

PLANT SPECIFICATIONS
Norweco Singulair® Model 960


Plant Capacity

Design Flow	500 gpd
Plant Hydraulic Capacity	
Pretreatment Chamber	450 gallons
Aeration Chamber	600 gallons
Settling Chamber	250 gallons
Hydraulic Retention Time (at Design Flow)	
Pretreatment Chamber	21.6 hours*
Aeration Chamber	28.8 hours*
Settling Chamber	12.0 hours*
Total Hydraulic Retention Time	62.4 hours*

- * Note: The flow equalization provided by the Bio-Kinetic® System results in an increased detention time for each chamber. The amount of flow control and exact increase in the detention time is dependent upon the specific daily flow pattern.

Aerators and Control Centers

Model 95 Aerator	CSA Listed
Type	Floodproof
Motor	1/6 HP, 1725 RPM, 115V, 60Hz, 1 pH, 3.6 Full Load Amps,
Output	3 CFM
Model 95 Control Center	CSA Listed
Type	115v, 60 Hz, 1 phase with visual alarm and time clock. Run setting adjustable from 30 minutes per hour <u>minimum</u> , to continuous run.
Audible Alarm	Optional
Model 93 Aerator	CSA Listed
Type	Floodproof
Motor	1/6 HP, 3450 RPM, 115V, 60Hz, 1 Ph, 4.2 Full Load Amps,
Output	3 CFM
Model 93 Control Center	CSA Listed
Type	115v, 60 Hz, 1 phase with visual alarm and (optional) time clock. Run setting adjustable from 30 minutes per hour <u>minimum</u> , to continuous run.
Audible Alarm	Optional




NOTES



1. UNDERGROUND POWER SUPPLY MUST BE WIRED INTO APPROVED SINGULAIR® CONTROL CENTER.
2. SINGULAIR® CONTROL CENTER MUST BE WIRED INTO A SEPARATE 10 AMP CIRCUIT BREAKER AT MAIN ELECTRICAL SERVICE PANEL IN THE FACILITY.
3. AERATOR AND AERATOR CONTROL CENTER MUST BE PROPERLY GROUNDED.
4. THE LOCAL LICENSED NORWECO DISTRIBUTOR WILL PLACE THE AERATOR INTO SERVICE WHEN THE FACILITY IS READY TO BE OCCUPIED.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING
 ©MCMXCVI NORWECO, INC.

	REVISION DATE	REVISION
	1-25-96	
	DRAWN BY	JMM
	APPROVED BY	GJS
MODEL 93 AND MODEL 95 SINGULAIR® AERATOR MOUNTING AND INSTALLATION DETAIL		DATE
		1-8-95
		SCALE
		NTS
THIS DRAWING IS THE PROPERTY OF NORWALK WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.		DRAWING NO.
		PC-5-7600






0.063-45° CHAMFER
BOTH ENDS OF I.D.



- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
 2. MATERIAL: STAINLESS STEEL.
 3. REMOVE BURRS; ENSURE NO SHARP EDGES.
 4. TOLERANCES ARE SPECIFIED IN MANUFACTURING PROCEDURE.

NORWECO. SPECIALTY VALVED EQUIPMENT COMPANY		REVISION
SINGULAR® MODEL 93 AND MODEL 95 INTERMEDIATE SHAFT		DATE: 1-8-95 SCALE: NTS
THIS DRAWING IS THE PROPERTY OF NORWECO. IT IS TO BE KEPT IN CONFIDENCE AND NOT TO BE REPRODUCED OR IN ANY MANNER WITHOUT WRITTEN PERMISSION FROM NORWECO.		DRAWING NO: PC-5-7506
DATE: 1-25-90	DRAWN BY: JMM	APPROVED BY: GJS
		DATE: 1-8-95


U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.



- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
 2. BALANCE 0.010 IN-0Z. MAXIMUM.
 3. TOLERANCE: 10:00'S.
 4. COLOR MUST MATCH APPROVED SAMPLE.
 5. FACES MUST BE FLAT WITHIN 0.010 T.I.P.
 6. BORE AND CIRCUMFERENCE MUST BE COAXIAL AND TRACK WITHIN 0.010 T.I.R.
 7. MATERIAL: ABS 911.

		REVISION DATE: 1-25-94 DRAWN BY: JMM APPROVED BY: GJS DATE: 1-8-95 SCALE: NTS DRAWING NO: PC-5-7508
SINGULAIR® MODEL 93 FOAM RESTRICTOR		THIS DRAWING IS THE PROPERTY OF NORWECO WATERFILTER EQUIPMENT COMPANY AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE WRITTEN PERMISSION FROM NORWECO.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.




- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
 2. BALANCE 0.010 IN-07 MAXIMUM.
 3. TOLERANCE: ±0.005.
 4. COLOR MUST MATCH APPROVED SAMPLE.
 5. FACES MUST BE FLAT WITHIN 0.010 T.I.R.
 6. BORE AND CIRCUMFERENCE MUST BE CONCENTRIC AND TRACK WITHIN 0.010 T.I.R.
 7. MATERIAL: ABS 911.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.

		REVISION 1-12-96 DRAWN BY JMM
SINGULAIR® MODEL 95 FOAM RESTRICTOR		APPROVED BY GJS
DATE 1-12-96		SCALE NTS
DRAWING NO. 5-7595		CHECKED BY NTS

THIS DRAWING IS THE PROPERTY OF NORWECO, INC. IT IS TO BE USED ONLY FOR THE PURPOSES SPECIFIED HEREON. IT IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT WRITTEN PERMISSION FROM NORWECO, INC.



REASON FOR REVISION	REVISION
DATE	DATE
1-25-96	JMM
DRAWN BY	APPROVED BY
	GJS
	DATE
	1-8-95
	SCALE
	NTS
	DRAWING NO.
	PC-5-7509

NORWECO
NORWALK, OHIO

SINGULAIR®
MODEL 93 AND MODEL 95
ASPIRATOR TIP


WE DRAWING IS THE PROPERTY OF NORWECO. IT IS TO BE USED ONLY FOR THE PROJECT AND MODEL SPECIFIED HEREON. NO REPRODUCTION IN WHOLE OR IN PART IS PERMITTED WITHOUT WRITTEN PERMISSION FROM NORWECO.

SECTION A-A

- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
 2. DIMENSION DETERMINED BY LENGTH OF 4-6 FULL THREADS.
 3. BALANCE 0.010 IN-DZ MAXIMUM.
 4. TOLERANCE: ±0.005.
 5. COLOR MUST MATCH APPROVED SAMPLE.
 6. TIPS MUST BE EQUALLY AND ACCURATELY SPACED AND TRACK IN THE SAME PLANE WITHIN 0.010 T.I.R.
 7. MATERIAL: GLASS-FILLED POLYPROPYLENE.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXXVI NORWECO, INC.

	A	B
MODEL 93	2.500	2.687
MODEL 95	4.139	3.193



- NOTES:
1. ALL DIMENSIONS ARE IN INCHES.
 2. EXTERNAL DIMENSIONS ARE DEPENDENT ON MANUFACTURING PROCESS.
 3. ALL DIMENSIONS ARE INTERIOR.


REVISION	REVISION
DATE	DATE
1-23-96	1-23-96
DRAWN BY	DRAWN BY
JMM	JMM
APPROVED BY	APPROVED BY
GJS	GJS
DATE	DATE
1-9-96	1-9-96
SCALE	SCALE
NTS	NTS
DRAWING NO.	DRAWING NO.
PC-5-8602	PC-5-8602

NORWECO
 A DIVISION OF
 NORWALCO, OHIO

SINGULAR®
 MODEL 960-500 GPD
 SLUDGE RETURN DEVICE


THIS DRAWING IS THE PROPERTY OF NORWECO. IT IS TO BE USED ONLY IN CONNECTION WITH THE PRODUCT FOR WHICH IT WAS DESIGNED. NO PARTS ARE TO BE REPRODUCED OR COPIED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.

U.S. AND FOREIGN PATENTS GRANTED AND PENDING ©MCMXCVI NORWECO, INC.




U.S. AND FOREIGN PATENTS GRANTED AND PENDING
 ©MCMXCVI NORWECO, INC.


NORWECO WASTEWATER EQUIPMENT COMPANY		REVISION DATE 1-25-96	REVISION
DRAWN BY JMM		APPROVED BY GJS	
DATE 1-8-95		SCALE NTS	DRAWING NO. PC-5-8500
<small>THIS DRAWING IS THE PROPERTY OF NORWECO WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO.</small>			




CROSS-SECTION THRU HOLES SHOWN AT 45° FROM SECTION A - A SCALE 2X




TOP VIEW



PARTIAL SECTION A-A



SIDE SECTION RECEIVING FLANGE CAST IN TANK



SECTION B - B FLOW DECK PARTIALLY SECTIONED

U.S. AND FOREIGN PATENTS GRANTED AND PENDING
 ©MCMXCVI NORWECO, INC.

NORWECO CORPORATE WASTEWATER EQUIPMENT COMPANY	REVISION DATE	REVISION
	1-25-98	
	DRAWN BY	JMM
	APPROVED BY	GJS
	DATE	1-8-95
	SCALE	NTS
THIS DRAWING IS THE PROPERTY OF NORWECO WASTEWATER EQUIPMENT COMPANY AND MAY NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION FROM NORWECO		DRAWING NO. PC-5-8600

This page intentionally left blank.

APPENDIX B

**NSF STANDARD 40 PERFORMANCE EVALUATION
METHOD AND REQUIREMENTS**

TEST METHOD

A. PURPOSE

The purpose of this test method is to verify that a plant complies with the applicable class effluent requirements during a six-month period.

Performance evaluation of the plant shall be independent of design and construction. However, structural weaknesses or defects and failures of process support equipment, shall be reported in the test results.

B. PREQUALIFICATIONS

1. **APPLICATION:** The application for performance evaluation of a particular model or model series shall include a basic description, design data, drawings, and parts and materials specifications for the plant and all equipment and appurtenances. A complete installation, operation, and maintenance manual, including a thorough discussion of process fundamentals, shall accompany the application.
2. **MODEL SERIES:** For a series of plants of the same model, varying in rated treatment capacities between 1514 and 5678 L (400 and 1500 gallons) per day, results achieved by the smallest plant in the series shall be indicative of the capabilities of all other plants in the series. The design and configurations of larger capacity plants shall be proportionally identical to the plant tested.¹

C. TESTING SEASON

The test can be carried out at any time of the year. If the test is conducted during cold weather, the plant and equipment shall be protected from freezing. If the test is conducted during warm weather, the temperature of the aeration compartment contents shall not exceed 30°C (86°F).

D. ANALYTICAL METHODS

All sample collection and analytical methods shall be those in the seventeenth edition of Standard Methods for the Examination of Water and Wastewater, published by the American Public Health Association², except as otherwise specified.

E. INFLUENT WASTEWATER CHARACTERISTICS

The influent wastewater characteristics shall be equivalent to wastewater generated from a normal household complying with the following typical domestic wastewater parameters:

BOD ₅	100-300 mg/L
SS	100-350 mg/L

¹When defining "proportionally identical," some of the parameters that should be considered are hydraulics, dimensions, mixing, and filtration.

²American Public Health Association, 1015 Fifteenth St., N.W., Washington, DC 20005.

F. LOADING REQUIREMENTS

1. DESIGN LOADING: The plant shall be hydraulically loaded at its rated daily capacity³ according to the following pattern of flow:

6 a.m. - 9 a.m.	35% of total daily flow
11 a.m. - 2 p.m.	25% of total daily flow
5 p.m. - 8 p.m.	40% of total daily flow

2. STRESS TESTING⁴: The plant shall be hydraulically loaded as indicated in the applicable figure in the following sequence:

- Wash Day (Figure A1),
- Working Parents (Figure A2),
- Equipment or Power Failure (electrical equipment off) (Figure A3),
- One week vacation followed by shock loading. Typical of a family's return from vacation (Figure A4).

G. TEST METHOD

1. GENERAL:

- a. Should mechanical malfunctions at the test facility occur during testing (dosing interruption, comminutor failure, sampler malfunction, etc.) the testing agency shall determine the potential adverse affect on the performance of the system and determine what analytical values shall be included in the thirty- and seven-sample averages.
- b. The plant shall be installed, operated, and maintained according to the manufacturer's instructions during the test period. If these instructions conflict with provisions in this Appendix, the provisions in this Appendix shall be used.

³Rated daily capacity is the designed treatment of the plant. Note the example below:

Effect of Testing at Design Loading

Assume average family = 5 persons

and average water use = 189 L/person/day (50 gals/person/day); then daily household waste = 946 Lpd (250 gpd).

Therefore, testing at rated daily capacity provides greater loading to plant than average family might be expected to contribute.

If minimum plant size = 1892 Lpd (500 gpd), then design loading simulates: Use by 10 persons @ 189 L/person/day (50 gals/person/day); or use by 5 persons @ 378 L/person/day (100 gals/person/day), or equal.

⁴Basis for 60% loading used to simulate working parents, equipment/power failure, and return from vacation:

Assume 5-person occupance and 1892 Lpd (500 gpd) design capacity for aerobic system; Then

2 flushes/person @ 95 L/flush (25 gals) = 189 L (50 gals)

1 shower/person @ 76 L/shower (20 gals) = 379 L (100 gals)

3 loads washing @ 132 L/load (35 gals) = 379 L (105 gals)

food preparation and dishes (est.) = 114 L (30 gals)

1079 L (285 gals)

= 60% Design Flow (approximately)

- c. If the plant under test is installed at a higher grade than a typical field installation, the manufacturer may insulate the plant if normal treatment temperatures could be affected.

2. START-UP PROCEDURES:

- a. The plant shall be assembled according to the manufacturer's instructions. Equipment shall be checked by the manufacturer to determine that it is structurally sound. All defects shall be reported. If no defects are detected, that fact shall be indicated by the testing agency.
- b. If no defects are detected and the plant is judged to be structurally sound, it shall be filled to capacity with one-third wastewater and two-thirds water⁵.
- c. The wastewater loading pattern provided in Section F.1 (normal loading) shall begin. Sampling and testing shall begin within three weeks after the plant is filled and placed into operation, and continue without interruption until the end of the test, with the following exception:

The testing agency shall make repairs for unexpected mechanical malfunctions that are explained in the manufacturer's operation manual. Routine service and maintenance of the plant will not be allowed during the test period.

- d. **LOADING SEQUENCE:** The plant shall be subjected to the following loading sequence:

Design loading (Section F.1) - 16 weeks
Stress sequence (Section F.2) - 7 weeks
Design loading (Section F.1) - 3 weeks

The plant shall be returned to design loading for seven days between each stressing sequence.

3. SAMPLING:

a. GENERAL:

- The daily composite sample shall consist of flow-proportional samples collected at least once per hour during periods of influent flow.

b. DESIGN LOADING:

- The evaluation analyses as specified in Appendix A, Table 1 shall be followed.
- All samples shall be collected and analyzed on a five-days-per-week basis.

c. STRESS TESTING:

- Samples collected immediately following each stressing shall include 24-hour composites of influent and effluent and analyzed in accordance with Appendix A, Table 1.
- Samples shall be collected immediately before the beginning of each sequence and each 24 hours for 7 days following each stress sequence.

NOTE: Two samples shall be collected during the working period and wash day stresses and analyzed for BOD₅, SS, and pH. The data shall not be used in determining acceptance.

⁵Start-up of plant with two-thirds water and one-third wastewater is not intended to dictate actual field start-up procedures.

**TABLE 1
GENERAL TEST SAMPLING**

Sample Location	Sample Type	Test Frequency	DO mg/L	BOD ₅ mg/L	Suspended Solids (SS), mg/L	Volatile Suspended Solids (VSS), Percent	Settleable Solids in mL/L 45 min.	Temp. °C	pH
Raw Influent	24 hr. Composite*	Monday thru Friday		X	X	X		X ¹	X ¹
Final Effluent	24 hr. Composite*	Monday thru Friday	X ¹	X	X	X		X ¹	X ¹
Aeration Chamber	Grab	Monday thru Friday	X ¹		X	X	X	X ¹	X ¹

*See Item 3.a.

¹In situ measurement.

H. ACCEPTANCE

1. The plant shall meet the applicable performance requirements of Section 5 of this standard.
2. To evaluate the pass/fail criteria set forth in Section 5 of this Standard a minimum of 118 sample days (23 during stressing) shall be collected and analyzed.
3. Due to the biological process, it is understood that aerobic systems may have days of upset. Therefore, for both Class I and Class II plants, 10% of the samples during testing (not to exceed one sample during stress testing) will not be included in the pass/fail determination.

I. REPORTS

- The testing agency shall provide a report to the manufacturer that includes significant data showing test results for the plant tested in accordance with this standard. Appropriate comments shall be provided. All data shall be included in the report, along with rationale for exclusion of any data due to adverse conditions during testing.

Figure A.1

Wash Day Loading

Added to plants 3 times in one 5-day week with one 24-hour period between each loading




Figure A.2

Working Parents

No loading 9 am to 5 pm for 5 consecutive days




Figure A.3

Equipment or Power Failure
 All power to plant off for 48 hours, 1 time only





Figure A.4

One Week Vacation
 No loading over 9-day period but all power on sudden shock when family returns home



PERFORMANCE REQUIREMENT⁶

- 5.0 EFFLUENT QUALITY: Plants shall be classified according to the effluent quality results obtained under the loading and operating conditions in Appendix A.
- 5.1 CLASS I EFFLUENT: Plants providing a Class I effluent shall be shown to meet EPA Secondary Treatment Guidelines⁷ for BOD₅, SS, and pH. These are as follows:
- 5.1.1 BOD₅ and SS
- Arithmetic mean of all effluent samples collected in a period of 30 consecutive⁸ days shall be ≤ 30 mg/L and ≥ 85 percent removal.
 - Arithmetic mean of all effluent samples collected in a period of 7 consecutive days shall be ≤ 45 mg/L.
 - Individual effluent samples shall not exceed a BOD₅ of 60 mg/L and SS of 100 mg/L.
- 5.1.2 pH - Effluent values shall remain between 6.0 and 9.0.
- 5.1.3 Effluent shall be tested three times during the six-month evaluation period for color, odor, oily film, and foam. The effluent shall be diluted 1:1000 with distilled water. Plants tested for Class I effluent characteristics shall not exceed:
- Color - 15 units;
 - Threshold Odor - nonoffensive;
 - Oily Film - nonvisible evidence other than air bubbles;
 - Foam - none.
- 5.2 CLASS II EFFLUENT: Plants providing a Class II effluent shall be shown to meet an effluent quality level for BOD₅ of 60 mg/L and for SS of 100 mg/L. These maximum values shall not be exceeded more than 10 percent of the time.
- 5.3 STRESS REQUIREMENTS: Measured values for BOD₅ and SS of effluent composite samples collected beginning 24 hours after completion of each stressing condition (48 hours after the power outage stress), as described in Appendix A, shall not exceed the applicable class effluent requirements in Item 5.1 and 5.2.
- 5.4 NOISE: Mechanical component parts shall be installed or protected so the noise produced does not exceed 60 dbA when measured 6.0 m (20 feet) from the plant or appurtenances.
- 5.5 MODIFICATION OF TEST METHODS: The manufacturer shall follow the procedures in Appendix C to request a modification of a specific test method. A request for a modification of a test method may be needed due to the following:
- The design of the plant precludes effective testing in accordance with the Standard.
 - The manufacturer submits a design change to a previously tested plant that may not require full performance testing.

⁶The performance limits set forth in section 5 take into account limitations of the respective analytical techniques relative to precision and accuracy. The limits shall be rigidly applied in the evaluation of test data in lieu of statistical interpretation.

⁷Federal Register, Vol 49, September 20, 1987, Title 40 Protection of Environment, Chapter 1 - EPA, Subchapter D - Water Programs, Part 133 Secondary Treatment Information, Item 133.102 Secondary Treatment.

⁸For Standard 40 applications, consecutive days shall be interpreted as consecutive sampling days.

APPENDIX C
ANALYTICAL RESULTS

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: June 11, 1995
Weeks Into Test: 1
Weekend Dosing: Sunday - 500 gallons
Monday - 500 gallons
Tuesday - 500 gallons
Wednesday - 500 gallons
Thursday - 500 gallons
Friday - 500 gallons
Saturday - 500 gallons

Plant Code: 6/139
Week Beginning: June 18, 1995
Weeks Into Test: 2
Weekend Dosing: Sunday - 500 gallons
Monday - 500 gallons
Tuesday - 500 gallons
Wednesday - 500 gallons
Thursday - 500 gallons
Friday - 500 gallons
Saturday - 500 gallons

Dosed Volume (gallons)	Monday	Tuesday	Wednesday	Thursday	Friday
Dissolved Oxygen (mg/L)	7.5	7.8	7.2	6.8	6.4
	4.2	4.5	4.7	3.5	3.8
Temperature (°C)	16	16	16	16	17
	18	18	18	18	18
pH	7.5	7.7	7.5	7.5	7.5
	7.6	7.6	7.8	7.6	7.6
Biochemical Oxygen Demand (mg/L)	8.1	8.1	8.2	8.0	8.0
	210	150	200	190	190
Suspended Solids (mg/L)	<5	5	7	6	7
	210	230	260	240	220
Volatile Suspended Solids (mg/L)	250	250	280	280	310
	7	8	8	6	8
45 Minute Settleable Solids (mL/L)	190	200	230	210	190
	210	200	240	230	250
aeration chamber	6	7	8	5	6
	300	430	350	400	360

Notes
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: June 18, 1995
Weeks Into Test: 2
Weekend Dosing: Sunday - 500 gallons
Monday - 500 gallons
Tuesday - 500 gallons
Wednesday - 500 gallons
Thursday - 500 gallons
Friday - 500 gallons
Saturday - 500 gallons

Dosed Volume (gallons)	Monday	Tuesday	Wednesday	Thursday	Friday
Dissolved Oxygen (mg/L)	7.8	5.5	7.8	6.4	6.2
	3.2	2.8	2.7	2.5	2.9
Temperature (°C)	17	17	18	18	18
	18	19	20	20	20
pH	7.5	7.6	7.5	7.6	7.4
	7.8	7.8	7.7	7.8	7.7
Biochemical Oxygen Demand (mg/L)	8.1	8.1	8.1	8.0	8.1
	190	190	250	240	260
Suspended Solids (mg/L)	10	12	9	5	6
	250	310	340	260	370
Volatile Suspended Solids (mg/L)	350	360	370	360	420
	7	5	6	<5	6
45 Minute Settleable Solids (mL/L)	220	260	300	230	320
	300	300	320	320	360
aeration chamber	6	<5	<5	<5	<5
	320	380	380	480	650

Notes
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: June 25, 1995

Plant Code: 6139

Week Beginning: July 2, 1995

Plant Code: 6139

Weeks Into Test: 3

Weeks Into Test: 4

Weekend Dosing: Sunday - 500 gallons

Weekend Dosing: Sunday - 500 gallons

Monday 500 Tuesday 500 Wednesday 500 Thursday 500 Friday 500

Monday 500 Tuesday 500 Wednesday 500 Thursday 500 Friday 500

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	6.2	6.6	6.4	6.5
	effluent	2.0	2.1	2.2	2.0
Temperature (°C)	influent	18	18	18	19
	aeration chamber	21	21	21	20
pH	effluent	21	21	21	20
	influent	7.4	7.5	7.6	7.5
Biochemical Oxygen Demand (mg/L)	aeration chamber	7.7	7.8	7.7	7.7
	effluent	8.0	7.9	7.9	8.0
Suspended Solids (mg/L)	influent	210	210	170	210
	aeration chamber	<5	<5	<5	<5
Volatile Suspended Solids (mg/L)	influent	370	370	270	310
	aeration chamber	450	440	410	400
45 Minute Settleable Solids (mL/L)	influent	<5	<5	<5	<5
	aeration chamber	290	290	210	180
aeration chamber	360	360	350	350	360
	effluent	<5	<5	<5	<5
aeration chamber	480	550	500	600	700

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGSJ-92

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	5.9	5.4	5.9	5.2
	effluent	1.3	1.0	1.3	1.2
Temperature (°C)	influent	18	18	19	19
	aeration chamber	20	20	20	20
pH	effluent	20	20	20	20
	influent	7.8	7.8	7.8	7.6
Biochemical Oxygen Demand (mg/L)	aeration chamber	7.5	7.7	7.7	7.6
	effluent	8.0	7.9	7.9	8.0
Suspended Solids (mg/L)	influent	160	170	170	150
	aeration chamber	5	<5	<5	<5
Volatile Suspended Solids (mg/L)	influent	160	180	180	180
	aeration chamber	460	480	490	460
45 Minute Settleable Solids (mL/L)	influent	6	<5	<5	<5
	aeration chamber	140	150	150	150
aeration chamber	380	420	430	380	
	effluent	<5	<5	<5	<5
aeration chamber	800	950	900	850	

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGSJ-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: July 9, 1995 Plant Code: 6/139
 Weeks Into Test: 5
 Weekend Dosing: Sunday - 500 gallons Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	eration chamber	5.5	5.2	4.2	4.2
	Effluent	1.7	1.6	1.7	1.9
Temperature (°C)	Influent	(1)	19	20	19
	eration chamber	20	20	20	21
pH	effluent	20	20	20	21
	Influent	(1)	7.9	7.7	7.8
Biochemical Oxygen Demand (mg/L)	eration chamber	7.8	7.7	7.6	7.8
	effluent	7.9	7.9	7.9	8.1
Suspended Solids (mg/L)	Influent	(1)	150	200	200
	eration chamber	<5	<5	<5	<5
45 Minute Settleable Solids (mL/L)	Influent	(1)	220	190	260
	eration chamber	490	420	420	450
Volatiles	eration chamber	6	<5	<5	<5
	effluent	(1)	190	170	220
Suspended Solids (mg/L)	eration chamber	430	360	360	370
	effluent	6	<5	<5	<5
45 Minute Settleable Solids (mL/L)	eration chamber	700	350	280	270
	effluent				

Notes: No influent sample on 7/10 because of sampler problem; no pH readings on 7/14 because of malfunction of the pH meter.
 (1) Site problem
 (2) Malfunction of system under test
 (3) Weather problem
 (4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: July 16, 1995 Plant Code: 6/139
 Weeks Into Test: 6
 Weekend Dosing: Sunday - 412 gallons Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	275	412	500	500
Dissolved Oxygen (mg/L)	eration chamber	6.0	5.4	5.9	5.6
	effluent	2.5	2.0	1.9	2.4
Temperature (°C)	Influent	20	20	20	19
	eration chamber	22	22	22	22
pH	effluent	22	22	22	22
	Influent	7.5	7.6	7.6	7.6
Biochemical Oxygen Demand (mg/L)	eration chamber	7.7	7.5	7.6	7.5
	effluent	7.9	7.9	7.9	7.9
Suspended Solids (mg/L)	Influent	220	180	310	200
	eration chamber	<5	<5	<5	<5
45 Minute Settleable Solids (mL/L)	Influent	280	210	300	270
	eration chamber	390	430	380	350
Volatiles	eration chamber	<5	<5	<5	<5
	effluent	230	180	260	220
Suspended Solids (mg/L)	eration chamber	340	370	340	300
	effluent	<5	<5	<5	<5
45 Minute Settleable Solids (mL/L)	eration chamber	320	480	300	410
	effluent				

Notes: Low dosing on 7/16, 7/18 and 7/19 caused by problem with influent pumps.
 (1) Site problem
 (2) Malfunction of system under test
 (3) Weather problem
 (4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: July 23, 1995 Plant Code: 6/139
 Weeks Into Test: 7
 Weekend Dosing: Sunday - 289 gallons Saturday - 125 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	469	500	500	500	500
Dissolved Oxygen (mg/L)	eration chamber	6.4	5.9	5.6	5.4
	effluent	(1)	3.0	2.8	2.4
Temperature (°C)	influent	20	20	20	19
	eration chamber	22	22	22	22
pH	influent	(1)	22	22	22
	eration chamber	7.5	7.6	7.4	7.5
Biochemical Oxygen Demand (mg/L)	influent	7.5	7.5	7.5	7.6
	effluent	(1)	7.9	7.8	7.8
Suspended Solids (mg/L)	influent	220	150	150	150
	eration chamber	(1)	5	<5	5
Volatile Suspended Solids (mg/L)	influent	180	240	160	190
	eration chamber	(1)	300	280	310
45 Minute Settleable Solids (mL/L)	influent	(1)	15	8	9
	eration chamber	150	190	140	170
aeration chamber	influent	(1)	260	240	270
	effluent	(1)	13	7	8
aeration chamber	influent	160	120	100	125
	effluent	160	120	100	130

Notes: (1) Site problem
 (2) Malfunction of system under test
 (3) Weather problem
 (4) Other

TGS/9-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: July 30, 1995 Plant Code: 6/139
 Weeks Into Test: 8
 Weekend Dosing: Sunday - 500 gallons Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	450	500
Dissolved Oxygen (mg/L)	eration chamber	5.7	5.7	5.0	5.4
	effluent	2.4	2.1	2.4	2.2
Temperature (°C)	influent	20	20	20	20
	eration chamber	22	22	22	22
pH	influent	22	22	22	23
	eration chamber	7.7	7.5	7.5	7.5
Biochemical Oxygen Demand (mg/L)	influent	7.7	7.7	7.6	7.7
	effluent	7.9	7.9	7.8	7.8
Suspended Solids (mg/L)	influent	190	150	150	150
	eration chamber	5	<5	6	6
Volatile Suspended Solids (mg/L)	influent	200	230	280	220
	eration chamber	280	320	310	330
45 Minute Settleable Solids (mL/L)	influent	10	23	16	13
	eration chamber	160	210	210	170
aeration chamber	influent	240	270	250	280
	effluent	10	18	14	11
aeration chamber	influent	150	150	210	120
	effluent	150	150	210	50

Notes: (1) Site problem
 (2) Malfunction of system under test
 (3) Weather problem
 (4) Other

TGS/9-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: August 6, 1995
Weeks Into Test: 9
Weekend Dosing: Sunday - 500 gallons
Monday - 500 gallons
Tuesday - 500 gallons
Wednesday - 500 gallons
Thursday - 500 gallons
Friday - 500 gallons
Plant Code: 6/139

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	eration chamber	4.4	4.6	4.8	5.3
	effluent	1.9	1.6	1.5	1.4
Temperature (°C)	influent	20	20	20	20
	eration chamber	22	22	22	22
pH	effluent	22	22	22	22
	influent	7.4	7.5	7.6	7.7
Biochemical Oxygen Demand (mg/L)	eration chamber	7.7	7.7	7.7	7.6
	effluent	7.9	7.9	7.9	8.0
Suspended Solids (mg/L)	influent	150	190	360	160
	eration chamber	6	<5	<5	<5
Volatile Suspended Solids (mg/L)	influent	150	220	280	180
	eration chamber	430	510	470	510
45 Minute Settleable Solids (mL/L)	influent	6	7	5	5
	eration chamber	130	170	190	240
45 Minute Settleable Solids (mL/L)	influent	360	430	400	340
	eration chamber	<5	7	<5	<5
45 Minute Settleable Solids (mL/L)	influent	280	500	580	500
	eration chamber	600	600	600	600

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: August 13, 1995
Weeks Into Test: 10
Weekend Dosing: Sunday - 500 gallons
Monday - 500 gallons
Tuesday - 500 gallons
Wednesday - 500 gallons
Thursday - 500 gallons
Friday - 500 gallons
Plant Code: 6/139

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	eration chamber	4.3	3.9	3.7	4.0
	effluent	1.1	1.0	1.1	1.3
Temperature (°C)	influent	20	20	20	20
	eration chamber	23	23	23	23
pH	effluent	23	23	23	23
	influent	7.6	7.5	7.5	7.7
Biochemical Oxygen Demand (mg/L)	eration chamber	7.7	7.6	7.6	7.7
	effluent	7.9	7.8	7.9	8.0
Suspended Solids (mg/L)	influent	210	190	190	190
	eration chamber	<5	<5	6	5
Volatile Suspended Solids (mg/L)	influent	240	290	260	210
	eration chamber	630	630	610	580
45 Minute Settleable Solids (mL/L)	influent	6	6	6	8
	eration chamber	210	250	230	180
45 Minute Settleable Solids (mL/L)	influent	520	520	510	490
	eration chamber	5	<5	6	7
45 Minute Settleable Solids (mL/L)	influent	580	460	510	620
	eration chamber	500	500	500	500

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: August 20, 1995
Weeks Into Test: 11
Weekend Dosing: Sunday - 500 gallons

Plant Code: 6139
Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	463	500	500	500	500
Dissolved Oxygen (mg/L)	4.3	4.3	3.7	4.6	4.1
	1.3	1.7	1.0	1.0	1.2
Temperature (°C)	20	20	20	20	20
	23	23	23	23	23
pH	7.7	7.7	7.7	7.6	7.5
	7.7	7.7	7.7	7.7	7.7
Biochemical Oxygen Demand (mg/L)	190	190	180	200	200
	<5	<5	<5	<5	<5
Suspended Solids (mg/L)	290	240	210	270	290
	620	590	620	660	660
Volatile Suspended Solids (mg/L)	7	6	5	7	7
	250	210	200	240	250
45 Minute Settleable Solids (mL/L)	500	480	510	540	540
	7	<5	<5	6	6
	800	800	900	790	700

Notes: Dosing shortage on 8/21 due to a problem with the Chelsea site dosing system.
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: August 27, 1995
Weeks Into Test: 12
Weekend Dosing: Sunday - 263 gallons

Plant Code: 6139
Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	4.5	4.0	4.2	3.3	3.9
	1.5	1.2	1.1	1.0	1.5
Temperature (°C)	20	21	20	21	20
	23	23	23	23	23
pH	7.5	7.6	7.7	7.7	7.7
	7.7	7.7	7.7	7.6	7.7
Biochemical Oxygen Demand (mg/L)	230	200	200	250	160
	5	5	5	<5	5
Suspended Solids (mg/L)	440	250	330	450	270
	720	680	640	760	700
Volatile Suspended Solids (mg/L)	9	14	10	8	7
	370	200	280	360	200
45 Minute Settleable Solids (mL/L)	600	540	510	610	540
	8	10	8	6	6
	800	560	700	500	780

Notes: Dosing shortage on 8/27 due to a plugged Chelsea site influent pump.
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: September 3, 1995 Plant Code: 6/139
Weeks Into Test: 13
Weekend Dosing: Sunday - 500 gallons Thursday - 500 gallons Friday 500

	Monday	Tuesday	Wednesday	Thursday	Friday	
Dosed Volume (gallons)	500	500	500	481	500	
Dissolved Oxygen (mg/L)	aeration chamber	4.3	3.6	3.9	3.3	2.8
	effluent	1.1	1.3	1.1	1.0	1.4
Temperature (°C)	influent	19	20	20	21	20
	aeration chamber	23	23	23	23	23
pH	effluent	23	23	23	23	23
	influent	7.7	7.7	7.7	7.6	7.7
Biochemical Oxygen Demand (mg/L)	aeration chamber	7.6	7.7	7.6	7.7	7.6
	effluent	7.8	8.0	7.9	8.0	7.8
Suspended Solids (mg/L)	influent	(4)	190	220	250	220
	aeration chamber	(4)	<5	5	7	8
Volatiles Suspended Solids (mg/L)	influent	(4)	360	320	350	310
	aeration chamber	(4)	810	810	880	900
45 Minute Settleable Solids (mL/L)	influent	(4)	7	8	13	12
	aeration chamber	(4)	330	270	310	260
45 Minute Settleable Solids (mL/L)	influent	(4)	660	640	700	720
	aeration chamber	(4)	6	6	11	12
45 Minute Settleable Solids (mL/L)	influent	660	600	520	600	700
	aeration chamber					

Notes: Dosing shortage on 9/7 due to a plugged Chelsea site influent pump.
Samples lost due to laboratory error on 9/4.

- (1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: September 10, 1995 Plant Code: 6/139
Weeks Into Test: 14
Weekend Dosing: Sunday - 500 gallons Thursday - 500 gallons Friday 500

	Monday	Tuesday	Wednesday	Thursday	Friday	
Dosed Volume (gallons)	500	500	500	500	500	
Dissolved Oxygen (mg/L)	aeration chamber	4.2	3.2	4.1	3.4	4.4
	effluent	1.8	1.7	1.6	1.5	1.6
Temperature (°C)	influent	20	20	20	20	20
	aeration chamber	22	22	21	21	21
pH	effluent	22	21	21	21	21
	influent	7.7	7.7	7.7	7.6	7.6
Biochemical Oxygen Demand (mg/L)	aeration chamber	7.6	7.6	7.5	7.5	7.5
	effluent	7.9	7.9	7.8	7.9	7.9
Suspended Solids (mg/L)	influent	190	160	160	180	170
	aeration chamber	8	6	7	9	8
Volatiles Suspended Solids (mg/L)	influent	230	250	210	180	200
	aeration chamber	890	910	920	980	880
45 Minute Settleable Solids (mL/L)	influent	14	13	16	20	16
	aeration chamber	190	230	180	180	170
45 Minute Settleable Solids (mL/L)	influent	700	720	730	770	710
	aeration chamber	12	12	13	16	12
45 Minute Settleable Solids (mL/L)	influent	490	500	700	500	570
	aeration chamber					

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: September 17, 1995
Weeks Into Test: 15
Weekend Dosing: Sunday - 500 gallons

Plant Code: 6/139
Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	4.4	4.4	4.3	5.0
	effluent	1.7	1.5	1.9	1.5
Temperature (°C)	influent	20	20	20	20
	aeration chamber	21	21	21	20
pH	effluent	21	21	21	20
	influent	7.6	7.7	7.6	7.7
Biochemical Oxygen Demand (mg/L)	aeration chamber	7.6	7.6	7.6	7.6
	effluent	7.9	7.8	7.9	7.9
Suspended Solids (mg/L)	influent	210	160	160	140
	aeration chamber	6	7	7	5
Volatile Suspended Solids (mg/L)	influent	240	190	180	200
	aeration chamber	1000	1000	1100	1100
45 Minute Settleable Solids (mL/L)	influent	14	20	14	15
	aeration chamber	240	170	160	170
Notes:	effluent	800	810	840	920
	influent	10	18	11	12
Notes:	aeration chamber	540	500	650	620
	effluent	540	500	650	620

(1) Silt problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: September 24, 1995
Weeks Into Test: 16
Weekend Dosing: Sunday - 500 gallons

Plant Code: 6/139
Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	aeration chamber	4.4	4.0	5.0	4.4
	effluent	1.4	2.0	1.4	1.4
Temperature (°C)	influent	19	19	19	19
	aeration chamber	19	19	19	19
pH	effluent	19	19	19	19
	influent	7.7	7.7	7.8	7.7
Biochemical Oxygen Demand (mg/L)	aeration chamber	7.7	7.6	7.6	7.7
	effluent	8.0	8.0	7.9	7.8
Suspended Solids (mg/L)	influent	160	160	180	200
	aeration chamber	7	6	7	7
Volatile Suspended Solids (mg/L)	influent	220	250	240	220
	aeration chamber	1000	1000	1000	1100
45 Minute Settleable Solids (mL/L)	influent	20	18	19	18
	aeration chamber	190	220	210	200
Notes:	effluent	810	830	820	880
	influent	16	16	16	16
Notes:	aeration chamber	540	450	330	400
	effluent	540	450	330	400

(1) Silt problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: October 1, 1995
Weeks Into Test: 17

Plant Code: 6/139

	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)	431	463	431	463	431	463	506
Dissolved Oxygen (mg/L)	eration chamber	4.5					
	effluent	1.5					
Temperature (°C)	influent	19					
	eration chamber	20					
pH	influent	19					
	eration chamber	7.6					
Biochemical Oxygen Demand (mg/L)	influent	7.7					
	effluent	7.9		8.0		7.9	
Suspended Solids (mg/L)	influent	220		170		150	
	eration chamber	7		6		8	
Volatile Suspended Solids (mg/L)	influent	260		240		260	
	eration chamber	1100					
45 Minute Settleable Solids (mL/L)	influent	15		12		18	
	eration chamber	220		210		220	
45 Minute Settleable Solids (mL/L)	influent	840					
	eration chamber	12		12		12	
45 Minute Settleable Solids (mL/L)	influent	450					
	eration chamber						

(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

Notes: Wash day stress 10/2 through 10/6.

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: October 8, 1995
Weeks Into Test: 18

Plant Code: 6/139

	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)	500	500	500	500	500	500	463
Dissolved Oxygen (mg/L)	eration chamber	5.5	5.0	5.2	4.5	5.0	5.8
	effluent	2.0	2.2	2.0	2.2	2.2	2.0
Temperature (°C)	influent	18	19	19	19	18	18
	eration chamber	19	18	18	18	18	19
pH	influent	18	18	18	18	18	18
	eration chamber	7.8	7.5	7.5	7.5	7.5	7.5
Biochemical Oxygen Demand (mg/L)	influent	7.6	7.6	7.5	7.5	7.6	7.5
	effluent	7.9	7.9	7.8	7.9	7.8	7.9
Suspended Solids (mg/L)	influent	140	190	200	180	170	180
	eration chamber	<5	<5	<5	<5	<5	<5
Volatile Suspended Solids (mg/L)	influent	140	220	220	240	200	210
	eration chamber	820	880	960	980	1000	1100
45 Minute Settleable Solids (mL/L)	influent	8	10	8	10	11	7
	eration chamber	120	200	190	210	170	190
45 Minute Settleable Solids (mL/L)	influent	620	680	760	780	810	860
	eration chamber	6	8	8	8	9	6
45 Minute Settleable Solids (mL/L)	influent	520	340	380	400	510	450
	eration chamber						

(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

Notes: Working parent stress started 10/14.

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: October 15, 1995
Weeks into Test: 19

Plant Code: 6/139

Dosed Volume (gallons)	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dissolved Oxygen (mg/L)	463	463	463	438	500	500	500
	eration chamber					4.7	4.2
						1.6	1.2
						18	17
Temperature (°C)						18	18
						18	18
pH						7.7	7.9
						7.6	7.5
Biochemical Oxygen Demand (mg/L)		7.9		8.0		7.9	7.9
		170		170		160	180
		<5		5		<5	<5
Suspended Solids (mg/L)		170		230		280	250
						1100	1200
Volatile Suspended Solids (mg/L)		9		12		12	8
		160		210		220	210
45 Minute Settleable Solids (mL/L)		8		10		10	6
						640	680

Notes: Working parent stress ended 10/18.
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: October 22, 1995
Weeks into Test: 20

Plant Code: 6/139

Dosed Volume (gallons)	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dissolved Oxygen (mg/L)	508	500	500	500	325	0	438
	eration chamber	4.4	6.0	4.7	5.1	5.8	
		1.3	1.5	1.4	1.4	1.5	
		17	18	18	18	17	
Temperature (°C)		17	17	17	17	17	
		17	17	17	17	17	
pH		7.9	7.5	7.9	7.7	7.8	
		7.6	7.8	7.6	7.5	7.6	
Biochemical Oxygen Demand (mg/L)		8.0	8.0	8.0	7.8	7.9	
		140	170	170	180	180	
		<5	<5	<5	<5	6	
Suspended Solids (mg/L)		150	220	270	320	280	
		1000	1100	1300	1200	1100	
Volatile Suspended Solids (mg/L)		8	8	8	10	9	
		130	190	220	250	210	
45 Minute Settleable Solids (mL/L)		820	840	890	930	880	
		6	6	7	8	8	
		500	590	580	520		

Notes: Power failure stress 10/26 through 10/28.
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: October 29, 1995
Weeks Into Test: 21

Plant Code: 6/139

Dosed Volume (gallons)	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dissolved Oxygen (mg/L)	500	500	500	500	506	500	500
		6.2	5.9	6.4	5.9	5.9	4.1
Temperature (°C)		1.6	1.5	1.9	1.4	1.9	1.5
		18	17	18	17	17	16
pH		16	15	16	16	16	16
		16	16	16	16	16	16
Biochemical Oxygen Demand (mg/L)		7.7	7.9	7.8	7.6	7.6	7.8
		7.7	7.5	7.7	7.6	7.5	7.4
Suspended Solids (mg/L)		7.9	8.0	7.9	8.0	8.0	7.7
		160	200	160	150	170	140
Volatile Suspended Solids (mg/L)		10	5	<5	<5	5	7
		180	220	170	200	250	160
45 Minute Sulfite Solids (mL/L)		18	9	8	10	8	6
		160	190	160	170	210	140
aeration chamber		730	700	680	680	730	750
		15	6	7	6	6	<5
aeration chamber		540	350	500	330	490	480

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: November 5, 1995
Weeks Into Test: 22

Plant Code: 6/139

Dosed Volume (gallons)	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dissolved Oxygen (mg/L)	325	0	0	0	0	0	0
		4.5					
Temperature (°C)		1.8					
		16					
pH		16					
		15					
Biochemical Oxygen Demand (mg/L)		7.8					
		7.5					
Suspended Solids (mg/L)		7.7					
		170					
Volatile Suspended Solids (mg/L)		<5					
		150					
45 Minute Sulfite Solids (mL/L)		1000					
		7					
aeration chamber		140					
		800					
aeration chamber		6					
		580					

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

Note: Vacation stress started 11/5.

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: November 12, 1995
 Weeks Into Test: 23

Plant Code: 6/139

	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)	0	0	369	500	500	500	500
Dissolved Oxygen (mg/L)	eration chamber				8.4	8.7	8.1
	effluent				3.0	4.1	3.4
Temperature (°C)	influent				16	16	15
	eration chamber				13	13	13
pH	effluent				12	13	12
	influent				7.7	7.7	7.8
Biochemical Oxygen Demand (mg/L)	eration chamber				7.8	7.7	7.7
	effluent				8.0	8.0	8.0
Suspended Solids (mg/L)	influent				160	150	150
	eration chamber				14	20	15
Volatile Suspended Solids (mg/L)	influent				190	180	200
	eration chamber				640	600	600
45 Minute Settleable Solids (mL/L)	influent				31	33	26
	eration chamber				160	160	180
	influent				480	440	480
	eration chamber				22	25	18
	influent				160	160	160
	eration chamber				160	160	200

Notes: Vacation stress ended 11/14/95.
 (1) Site problem
 (2) Malfunction of system under test
 (3) Weather problem
 (4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Stress Test Evaluation

Week Beginning: November 19, 1995
 Weeks Into Test: 24

Plant Code: 6/139

	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Dosed Volume (gallons)	500	500	500	500	450	500	500
Dissolved Oxygen (mg/L)	eration chamber	6.8	5.5	6.8	7.0	7.8	7.8
	effluent	2.7	2.4	2.2	2.2	2.1	2.4
Temperature (°C)	influent	14	15	16	15	15	14
	eration chamber	12	13	13	13	12	12
pH	effluent	12	12	12	12	12	12
	influent	7.8	7.7	7.8	7.9	7.8	7.8
Biochemical Oxygen Demand (mg/L)	eration chamber	7.7	7.7	7.6	7.8	7.7	7.6
	effluent	7.9	8.0	8.0	7.9	8.0	7.9
Suspended Solids (mg/L)	influent	130	170	170	180	150	260
	eration chamber	9	7	6	5	6	7
Volatile Suspended Solids (mg/L)	influent	170	220	230	220	170	300
	eration chamber	570	810	770	560	580	570
45 Minute Settleable Solids (mL/L)	influent	13	10	9	8	10	8
	eration chamber	150	200	210	190	160	270
	influent	480	640	600	420	460	470
	eration chamber	12	8	8	6	8	8
	influent	200	280	260	180	150	200
	eration chamber						

Notes: Dosing shortage on 11/23 due to a problem with the Chelsea site dosing system.
 (1) Site problem
 (2) Malfunction of system under test
 (3) Weather problem
 (4) Other

TGS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: November 26, 1995 Plant Code: 6/139
Weeks Into Test: 25
Weekend Dosing: Sunday - 500 gallons Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	238
Dissolved Oxygen (mg/L)	7.9	9.0	7.5	7.1	7.8
	2.1	2.5	2.4	2.5	2.7
Temperature (°C)	15	15	15	15	15
	12	12	12	12	12
pH	12	12	12	12	12
	7.8	7.7	7.8	7.8	7.8
Biochemical Oxygen Demand (mg/L)	7.6	7.7	7.6	7.7	7.7
	8.0	8.0	7.9	8.0	7.9
Suspended Solids (mg/L)	200	200	170	150	160
	7	11	10	6	6
Volatile Suspended Solids (mg/L)	270	260	290	230	200
	660	700	670	680	560
45 Minute Settleable Solids (mL/L)	9	12	8	10	10
	230	210	240	190	180
45 Minute Settleable Solids (mL/L)	640	530	540	530	470
	7	8	7	8	8
45 Minute Settleable Solids (mL/L)	200	190	200	200	180

Notes: (1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

Notes: Dosing shortage on 12/1 caused by a clogged Chelsea site influent pump.

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: December 3, 1995 Plant Code: 6/139
Weeks Into Test: 26
Weekend Dosing: Sunday - 500 gallons Saturday - 500 gallons

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	8.1	7.6	8.4	7.6	8.0
	2.6	2.3	2.8	3.0	3.1
Temperature (°C)	15	15	15	15	14
	12	12	12	12	11
pH	12	12	12	11	11
	7.6	7.8	7.8	7.7	7.8
Biochemical Oxygen Demand (mg/L)	7.7	7.7	7.7	7.7	7.7
	7.9	7.9	8.0	7.9	8.0
Suspended Solids (mg/L)	230	160	210	220	190
	7	7	10	18	10
Volatile Suspended Solids (mg/L)	220	240	230	270	200
	600	730	720	650	620
45 Minute Settleable Solids (mL/L)	12	18	16	37	14
	200	200	200	240	170
45 Minute Settleable Solids (mL/L)	480	560	570	520	490
	10	14	12	30	12
45 Minute Settleable Solids (mL/L)	150	200	190	150	160

Notes: (1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TGS/3-92

Notes:

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: December 10, 1995
Weeks Into Test: 27
Weekend Dosing: Sunday - 500 gallons

Plant Code: 6/139
506 gallons
Saturday

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	eration chamber	8.4	8.8	8.6	8.4
	effluent	3.4	3.4	3.1	3.5
Temperature (°C)	influent	13	14	14	13
	eration chamber	11	10	10	10
pH	effluent	10	10	10	10
	influent	7.8	7.9	7.8	7.8
Biochemical Oxygen Demand (mg/L)	eration chamber	7.7	7.7	7.6	7.6
	effluent	7.9	7.9	7.9	7.8
Suspended Solids (mg/L)	influent	190	170	180	170
	eration chamber	8	8	10	9
Volatile Solids (mg/L)	influent	210	230	210	250
	eration chamber	540	560	580	580
45 Minute Settleable Solids (mL/L)	influent	16	16	16	17
	eration chamber	190	180	180	210
45 Minute Settleable Solids (mL/L)	influent	460	480	440	470
	eration chamber	16	12	14	13
45 Minute Settleable Solids (mL/L)	influent	130	130	125	130
	eration chamber	130	130	125	120

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TOS/3-92

NSF International
Standard 40 - Individual Wastewater Treatment Plants
Plant Effluent

Week Beginning: December 17, 1995
Weeks Into Test: 28
Weekend Dosing: Sunday - 500 gallons

Plant Code: 6/139
500 gallons
Saturday

	Monday	Tuesday	Wednesday	Thursday	Friday
Dosed Volume (gallons)	500	500	500	500	500
Dissolved Oxygen (mg/L)	eration chamber	8.5	7.7	8.3	7.6
	effluent	3.9	3.4	3.3	3.5
Temperature (°C)	influent	14	14	13	13
	eration chamber	10	10	10	10
pH	effluent	10	10	10	10
	influent	7.8	7.8	7.8	7.9
Biochemical Oxygen Demand (mg/L)	eration chamber	7.7	7.7	7.7	7.7
	effluent	7.8	7.9	7.8	7.9
Suspended Solids (mg/L)	influent	210	200	230	210
	eration chamber	11	10	10	10
Volatile Solids (mg/L)	influent	200	300	290	260
	eration chamber	540	570	560	580
45 Minute Settleable Solids (mL/L)	influent	27	23	18	19
	eration chamber	180	250	260	230
45 Minute Settleable Solids (mL/L)	influent	440	460	480	480
	eration chamber	23	18	17	16
45 Minute Settleable Solids (mL/L)	influent	130	120	120	120
	eration chamber	130	120	120	120

Notes:
(1) Site problem
(2) Malfunction of system under test
(3) Weather problem
(4) Other

TOS/3-92